

# Shri Amarnathji Shrine Board



## Jammu and Kashmir

Tender Document

For

Civil Works along Baltal Axis

(Lower Camps)

For

Yatra – 2022

**General Manager (Works)**  
Shri Amaranthji Shrine Board

04.03.2022

**CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2022**

**DETAILED NOTICE INVITING TENDER (DNIT)**

(Issued under no. SASB/DNIT/W/1341/2022/07

dated 04.03.2022)

<b>S. No.</b>		<b>PAGE(S)</b>
1.	Notice Inviting Tender (NIT) for advertisement	3-4
2.	Standard Bidding Document (Eligibility Criteria)	5 - 6
4.	Instructions to Bidders	6 -8
5.	Terms and Conditions of Contract	8-12
6.	Schedule – A (Technical Bid)	13-14
7.	Bid Securing Declaration (Format)	15
7.	Schedule – B (Financial Bid)	16-48



## SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov - April)  
Tele: 0191-2555662, Telefax: 0191-2503399

### NOTICE INVITING TENDER CIVIL WORKS ALONG BALTAL AXIS (LOWER CAMPS) FOR YATRA - 2022

For and on behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited **ON PERCENTAGE BASIS** from registered **JK PWD, CPWD, MES/ Railways Contractors** having a valid registration, for the execution of **Civil Works as mentioned below**. The bids shall be received in the office of **General Manager (Works)**, Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **17.03.2022** upto **1400 hours**.

S. No.	Name of work	Estimated cost (Rs in lakh)	Cost of bid document (in Rs)	Earnest Money/ Bid Security (in Rs)	Class of Contractor	Time of Completion
1	Dismantling of safety panel of departure lounge pre Yatra ,refixing of panels to convert as temporary room to be utilized during Yatra and re-fixing to Departure Lounge as safety panels post Yatra 2022.	1.73	600.00	<b>Bid Security Declaration to be made by the Bidder on non judicial stamp paper duly attested by Notary as per prescribed format.</b>	DEE	10 days
2	Repairs and renovation of Base Hospital Baltal including fixing of CGI sheet roofing before Yatra and dismantling of roofing and safe storage after conclusion of Yatra.	1.83	600.00		DEE	15 days
3	Construction of 6 Nos Soakage Pits at Baltal Base Camp.	3.50	600.00		DEE	25 days
4	Construction of pucca bases (30Nos) of toilets in CRPF Camp and Tentage area at Baltal Camp.	3.60	600.00		DEE	25 days
5	Remodelling of old pucca toilet blocks (40 units) in Baltal Base Camp Area.	8.00	600.00		DEE	30 days
6	Construction of 20 No. & 10 No. Pucca Bases of Toilets /Baths including sewer line in Langar Store area enroute Baltal to Dumail & Dumail Camp respectively.	3.60	600.00		DEE	25 days
7	Construction of 02 No. and 01 No. Soakage Pits in Langar Store Area enroute Baltal to Dumail and at Dumail camp respectively.	1.78	600.00		DEE	18 days
8	Construction of 4 No. temporary rooms for medical and other departments after dismantling of safety panels of SASB complex at Dumail before start of Yatra and dismantling of temporary rooms and re-fitting of safety panels to SASB complex at Dumail after culmination of Yatra 2022.	0.95	600.00		DEE	7 days
9	Minor repairs and painting of Toilet/Baths (300 Nos) including writing numerical for numbering of Toilet/Baths at Lower Camps for Yatra 2022.	5.96	600.00		DEE	30 days

10	Providing and laying of sewer line for disposal of Langar sullage (enroute Baltal to Dumail) to Soakage Pits for Yatra 2022.	11.92	600.00		DEE	30 days
11	Restoration of defunct sewer line in CRPF area and Langars to Grease Trap including repair to firegaps between Langars at Baltal for Yatra 2022.	6.32	600.00		DEE	30 days
12	Assembling/erection of Toilet/Baths including repairs before commencement of Yatra including dismantling and safe storage in SASB stores after conclusion of Yatra at Baltal	5.50	600.00		DEE	20 days
13	Assembling/erection of Toilet/Baths including repairs before commencement of Yatra including dismantling and safe storage in SASB stores after conclusion of Yatra at Neelgrath & enroute Rangamoh to Dumail.	7.50	600.00		DEE	20 days

**Position of AAA: Accorded**

2. Detailed NIT (DNIT) can be downloaded from SASB website (www.shriamarnathjishrine.com) upto 16.03.2022 and the cost of Bid document in the shape of **Demand Draft (Non Refundable)** drawn in favour of Director Finance, Shri Amarnathji Shrine Board (SASB), Jammu shall be attached with the Bid document.
3. The Bids, duly completed, along with **Bid Security Declaration**, must reach the office of **General Manager (Works)** latest by **17.03.2022 upto 1400 Hrs.** The Bidders, in their own interest, are advised to deliver the bids personally in the office of **General Manager (Works)**, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through **Speed Post/ Registered Post**. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reasons.
4. The Technical bid shall be opened on **17.03.2022 at 1430 Hrs** in the Office of **General Manager (Works) at Jammu Office (address mentioned above)** in presence of the Bidders who may wish to be present on the occasion.
5. The site for the work is available. The intending bidders are strongly advised to inspect the site of work before bidding.
6. The Bidder shall quote strictly as per **PERCENTAGE BASIS**.
7. Not more than three bid documents shall be issued to a single Bidder.
8. In case the last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day up to **1400 hours**.
9. The successful Bidder is bound to enter into an **agreement** with **General Manager (Works), SASB, within ten days from the date of the receipt of Letter of Intent (LoI)**.
10. All addenda, corrigenda, dedenda and amendment shall be uploaded on website only and not in print media and the Bidders are advised to keep themselves updated on this account.

**No: SASB/DNIT/W/1341/2022/07**  
**Dated: 04.03.2022**

**Sd/-**  
**General Manager (Works)**  
Shri Amarnathji Shrine Board

**1. STANDARD BIDDING DOCUMENT**

**ELIGIBILITY CRITERIA**

The Bidder must be a Contractor registered with J&K, PWD, CPWD, MES/ Railways and must fulfil all the following eligibility requirements concurrently to technically qualify for bidding process:

Average Annual Turnover during the last three years, ending 31<sup>st</sup> March of the previous working financial year (i.e. 2017-18, 2018-19 & 2019-20) should be 30% of the advertised cost.

- 1.1 The bidder should have an experience of having successfully completed similar works in Hilly Regions during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-
  - a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or
  - b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or
  - c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.
- 1.2 The Bidder should not have been blacklisted on an earlier occasion by any of the Union Territory Government Organizations, U.T Autonomous Bodies or Local Bodies/ Municipalities.
- 1.3 The Bidder must submit the following documents:
- 1.4 General Profile of the Bidder defining legal status, place of registration, principal place of business, cell no. with correspondence address.
- 1.5 Registration card must be renewed for the current Financial Year 2021-22 along with no objection certificate (NOC) from the issuing authority.
- 1.6 Certified copies of Annual Turnover from Bank
- 1.7 Certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works, for fulfilling the eligibility criteria.
- 1.8 Certified copy of PAN Card (self attested).
- 1.9 Certified copy of GSTIN Registration and latest clearance certificate form GS-3B latest quarter month.
- 1.10 Bid Security Declaration.
- 1.11 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect during technical evaluation or during execution of work, the following penalties are to be imposed;
  - i. in case the work is allotted to the agency, the contract shall be terminated and work executed through an alternate agency at the risk & cost of the allottee,
  - ii. Earnest Money Deposit, shall be forfeited

iii. The Bidder/ Allottee shall be debarred from tendering in SASB for next three years.

## **2. INSTRUCTION TO BIDDERS**

- 2.1 Detailed NIT (DNIT) can be downloaded from SASB website (www.shriamarnathjishrine.com) upto 16.03.2022 in which the cost of DNIT shall be payable in the shape of **Demand Draft (Non Refundable)** drawn in favour of Director Finance, Shri Amarnathji Shrine Board (SASB), Jammu.
- 2.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes super scribed “**Technical Bid for the work of \_\_\_\_\_ Yatra 2022**” and “**Financial Bid for the work of \_\_\_\_\_ Yatra 2022**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of \_\_\_\_\_ (Yatra 2022)**” **mentioning NIT No. & date.** The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 2.3 The bids, duly completed, along with **Bid Security Declaration** must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered/Speed Post to General Manager (Works), SASB at the aforesaid address, so as to reach latest on **17.03.2022 upto 1400 hours.** Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by speed post.
- 2.4 The cost of DNIT should be placed inside the envelope containing the Technical bid and Bid Security Declaration.
- 2.5 It would be deemed that by submitting the bid, the Bidder has made complete examination of the DNIT, received all information from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 2.6 Each Bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 2.7 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid not substantially responsive to the DNIT in every respect will be at Bidder’s risk and may result in the rejection of the bid.
- 2.8 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be indicated in words as well as in figures. In case of any variation between

amount in figures and words, amount quoted in words shall be taken as authentic.

- 2.9 The rate quoted by the Contractor in overall percentage basis (w.r.t. SSR-2020) tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 2.10 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of DNIT as acceptance of all conditions contained therein and for the purpose of identification. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 2.11 Bids must be received at the address specified in this document not later than the **date and time stipulated in the DNIT**. The General Manager (Works) may, at his discretion, extend the deadline for submission of bids. Any bid received after due date and time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 2.12 Clarifications, if any, may be sought by the Bidders prior to so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by General Manager (Works), SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hoisted on SASB website ([www.shriamarnathjishrine.com](http://www.shriamarnathjishrine.com)) and NOT in newspaper(s). The Bidders should keep themselves updated on this account.
- 2.13 The Technical Bid shall be opened on **17.03.2022 at 1430 Hrs** in the Office Chamber of General Manager (works) in presence of the authorized representatives of the Bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 2.14 The General Manager (Works), SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the Bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 2.15 The bid shall remain valid and open for acceptance for a period (i.e. Bid Validity Period) of **60 days from the last date prescribed for its receipt**.
- 2.16 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.

- 2.17 The General Manager (Works) may award the Contract to the Bidder whose bid has been evaluated to be responsive and who is eligible and qualified to perform the contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible Bidder a letter, hereinafter referred to as the 'Letter of Intent' (LoI) prescribing the amount which the Shrine Board will pay to the eligible Bidder in consideration of work/ services to be executed by the eligible Bidder as prescribed in the Contract.
- 2.18 The eligible Bidder will have to enter into an agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the **ten days** of the receipt of Letter of Intent.
- 2.19 General Manager (Works), SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reasons thereof. Any enquiry after the submission of tender will not be entertained.
- 2.20 Shri Amarnathji Shrine Board shall not be responsible for release of any DD/ CDR pledged to Director Finance, SASB without submitting his tender in the tender box. However, the CDRs of unsuccessful Bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

### **3. TERMS AND CONDITIONS OF THE CONTRACT:**

- 3.1 The Bidders are required to quote rate **above/below percentage on SSR of 2020** shown in the rate list of Schedule-B, (Format of Financial Bid). Percentages should be quoted in figures and words. The Bidders must also calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 3.2 Bids shall have to be submitted separately for each work as indicated in the DNIT.

#### **3.3 Imbalanced bids:**

- i. All bids (received from bidders) valuing less than 80% of the tendered cost shall be treated as imbalanced bids.
- ii. Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money Deposit) in the shape of CDR/FDR in favour of Director Finance, SASB. This Additional Earnest Money Deposit should be equal to the difference between the bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.
- 3.4 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- (i) First 3 days of delay      Penalty @1% of contract value.



- (ii) 4<sup>th</sup> day upto 10<sup>th</sup> day @2% of contract value
- (iii) Beyond 10 days Earnest Money Deposit shall be forfeited and the contract automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm.

- 3.5 Not with standing **Clause 3.4 above**, in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 3.6 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).
- 3.7 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per PWD/ CPWD, MES/Railway Book of specifications.
- 3.8 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencement of work at site.
- 3.9 The Contractor shall submit **pictorial evidence (Photographs)** of execution of work (pre execution, during execution and after completion of work) with his claim.
- 3.10 The Contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 3.11 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the Contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 3.12 The agency shall abide by all major Laws applicable to establishment engaged for execution of work.
- 3.13 The Contractor shall abide at all times by all the applicable labour enactments and rules made there under, regulations, notifications and bye laws of the U.T or Central Government or Local Authority and any other

labour laws (including rules), regulations, bylaws that may be passed or notifications that may be issued under any labour law in future either by the U.T. or the Central Government or the local authority. The Contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.

- 3.14 All risks of loss or damage to physical property and of personal injury and death which may arise during and in consequence of the performance of the contract shall be the sole responsibility of the Contractor.
- 3.15 Insurance cover to labour machinery work plant material equipment by the contractor shall be mandatory.
- 3.16 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 3.17 Laws governing the contract :- The contract shall be governed by the laws of land.
- 3.18 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of **Letter of Intent** (LoI).
- 3.19 In case of occurrence of Force Majeure conditions, the agency shall promptly inform CEO, SASB about occurrence of such conditions. On receipt of the agency's Report and after ascertaining as to whether Force Majeure condition exists (such as a Government Order/Regulation, war, an accident creating a disturbed condition, terrorist activity, court order, strikes/ riots, civil commotion, pandemic like COVID-19 etc.) CEO, SASB shall suspend the agency's license. SASB shall not be liable for any damage or liability of any kind arising out of Force Majeure conditions and/ or any other cause beyond the reasonable control of SASB.
- 3.20 In the event of any doubt, dispute or difference of opinion in regard to terms & conditions of the agreement, the concerned parties shall endeavor to settle the same amicably with the SASB through any officer nominated in this behalf. In case, any such doubt, dispute or difference of opinion remains unresolved, the matter shall be referred to the Hon'ble Lieutenant Governor, J&K (Chairman of SASB), who shall be competent to refer the same to any retired Hon'ble Judge of the High Court of Jammu Kashmir & Ladakh for its resolution. The decision so rendered or award, if any, passed shall govern the rights, duties & obligations of the concerned parties and shall be final. No such disputes shall be referred during the currency of the Yatra.
- 3.21 All questions relating to the arbitrations shall be determined in accordance with provisions of the Arbitration and Conciliation Act, 1996 and the amendments

thereto and any re-enactment or modification thereof and the rules framed there under

- 3.22 The rates quoted by the Contractor shall be inclusive of all taxes including GST etc as applicable.
- 3.23 If during the period of one year from the date of completion of work, the defects which have been caused by bad workmanship, use of inferior materials on the work, the Contractor shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the work shall be got rectified through alternate resourceful agency and the cost thereof shall be recovered from the dues of the Contractor.
- 3.24 The Earnest Money Deposit of the successful Bidder shall be released after completion of work in full and issue of completion certificate by the DGM, SASB.
- 3.25 The quantities of items of work provided in the NIT as per BOQ are approximate and may increase/ decrease upto 20% during execution of work as per necessity at site.

#### **4. Payment Clause:**

- 4.1 Payment shall be made to the Contractor for complete item of work including cost of material and labour (finished work) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site duly checked by the Deputy General Manager (Works).
- 4.2 The payment to the Bidder shall be made after successful completion of work within the stipulated time as per specifications and Terms & Conditions of agreement after satisfactory use/ function of the work during complete Yatra Period.
- 4.3 Any extra item (s) executed at site of work shall be paid strictly as per LoA (Contractor's appreciation/ depreciation on J&K **Sanctioned Schedule of Rates 2020.**)

#### **5 Time of completion:**

- 5.1 The time of completion of works stands mentioned against each work in the NIT.
- 5.2 Time of completion shall mean;  
Period of time of completion of work in all respects before start of Yatra – 2022 including the period of time involved in completely dismantling of the pre-fabricated structures with due care from damages and safe storage of the materials in the SASB stores to the entire satisfaction of the Deputy General Manager (Works) or his authorised representative.

**General Manager (Works)**  
Shri Amarnathji Shrine Board

# **SCHEDULE A (TECHNICAL BID)**

## **PART A: DETAILS OF COST OF DNIT AND BID SECURITY DECLARATION**

<b>S. No.</b>	<b>Particular of item</b>	<b>Details</b>
1	Amount and details of payment towards the cost of DNIT:	Rs. (inwords):
		DD No.
		Date:
2	Bid Securing Declaration	Dated:
		Bid No.
		Name of Notary

## **PART – B: BASIC DETAILS ABOUT THE AGENCY.**

i) Name and address of :      Name: \_\_\_\_\_  
the Agency.

Address: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Phone: \_\_\_\_\_

E-mail: \_\_\_\_\_

## **PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.**

The Bidder is required to furnish the following information/ documents:  
(Please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Card/ other documents; *please see DNIT – Para 1.5 of ‘Standard Bidding Document’*)
2. The Bidder must furnish certified copies of bank statement -*please see DNIT – Para 1.6 of ‘Standard Bidding Document’*

#	Financial Year	Turnover (Rs.)
1	2017-18	
2	2018-19	
3	2019-20	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 1.7 of Standard Bidding Document’*

S. No.	Name of work	Name of Client	Value of Completed work (in Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/No)

4. General Profile of the Bidder – *Para 1.4 of ‘Standard Bidding Document’*
5. Certified copy of PAN Card - *Para 1.8 of ‘Standard Bidding Document’*
5. Certified copy of GSTIN – *Para 1.9 of ‘Standard Bidding Document’*
7. Bid Security Declaration – *para 1.10 of Standard Bidding Document’*
8. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 1.11 of Standard Bidding Document’.*

**Form of Bid Security Declaration**

(Duly notarized)

**The General Manager (Works),  
Shri Amarnathji Shrine Board, J&K**

**NIT No.& Date:** \_\_\_\_\_

**Name of work.** \_\_\_\_\_

1. I \_\_\_\_\_ s/o \_\_\_\_\_  
r/o \_\_\_\_\_ declared that;

I understand that, according to your conditions, bids must be supported by a Bid Securing Declaration.

2. I accept that I may be disqualified from any Contract with the Shri Amarnathji Shrine Board for a period of three years from the date of notification if am in a breach of any obligations (s) under the bid conditions, because I;

a). have withdrawn/ modified/amended, impaired or derogated from the tender, my bid during the period of bid validity specified in the Letter of Bid, or

b). having been notified of the acceptance of my Bid by the SASB during the period of bid validity of (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with Instructions to Bidders.

3. I understand this Bid- Securing Declaration shall cease/ expire to be valid if undersigned is not the successful Bidder, upon the earlier of (i) the receipt of your notification of the name of the successful Bidder; or (ii) sixty days Bid Validity Period.

**Signature of person**

(Signing the Bid Securing Declaration)

Dated on \_\_\_\_\_ day of \_\_\_\_\_

## SCHEDULE – B (Format for Financial Bid)

### Rate List/ Quantity Schedule

**Name of Work:- Dismantling of safety panel of departure lounge pre Yatra ,refixing of panels to convert as temporary room to be utilized during Yatra and re-fixing to Departure Lounge as safety panels post Yatra 2022.**

**Adv. Amount: Rs.1.73lakh**

**S.No: 01**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Dismantling roofing including ridges, hips, valleys and gutters etc including propping, bracing the structure including welding, and stacking material within 50m lead of G.S Sheet. (Pre and Post Yatra)	506.13	Sqm	₹ 113.90	
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size) For CC strip at back of rooms to block rain water from entering.	0.26	Cum	₹ 4,943.40	
3	Engagement of labour for strengthening of Departure Lounge with available material after conclusion of Yatra 2022 ,	-	-	-	
3a	Blacksmith	3	Day	₹ 980.70	



3b	Helpers	6	Day	₹ 673.00
4	Carriage of cement by Mechanical Transport from Ganderbal to Neelgrath for an avg. lead 60 km	0.06	Tonne	₹ 618.19
5	Carriage of sand & bajri by MT for an average lead of 10 Km.	0.35	Tonne	₹ 244.22

### Part-B

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be Quoted by Bidder (in Rs.)
I	II	III	IV	V
6	Fixing of safety panel to convert as in temporary room for the use of officials during yatra and around the departure lounge vertically to avoid damages during winter (complete).	506.13	Cum	
7	Fixing of G.I chain link fencing of required mesh size 50mmx50mm including strutting with nuts,bolts and washels as required complete including repairs to damaged chain link fencing and angle iron posts including dismantling after conclusion of Yatra. Labour only.	130.00	Sqm	
8	Hire charges of genset, welding set including cost of electrodes and POL for repairs/strengthening of Departure Lounge with available material,for replacing of door of the washroom of meeting hall after conclusion of Yatra 2022.	3.00	Days	

9	Provision for electrification in 6 no Temporary CGI panels sheds and renovation of defunct electrical points in Departure Lounge and SASB Huts (Quantities subject to actual measurement at site). (Approved brand and make)	-	-	
9a	a) Wire 1.5 mm <sup>2</sup> - 90 m each	2	Each	
9b	b) Wire 2.5 mm <sup>2</sup> - 90 m each	1	Each	
9c	c) PVC Channel(1") 2m length	30	Meter	
9d	d) Tape Roll	1	Each	
9e	e) 1 Way Gangue Box	10	Each	
9f	f) 2 Way Gangue Box	10	Each	
9g	g) 3 Way Gangue Box	10	Each	
9h	h) 4 Way Gangue Box	5	Each	
9i	i) 5 Way Gangue Box	5	Each	
9j	j) S.S Combine box type 16 Amp	6	Each	
9k	k) Switch 6 Amp	20	Each	
9l	l) 5 Pin 6 Amp Socket	10	Each	
9m	m) Bulb Holder	10	Each	
9n	n) Angle Holder	10	Each	
9o	o) 12 Watt LED	10	Each	
9p	p) MCB 16 Amp	4	Each	
9q	q) MCB DP 63 Amp	1	Each	
<b>Total cost of bid (to be quoted both in figures and words) Total of Part-A and Part-B</b>				

JE

DGM

Signature of  
Bidder

### **SCHEDULE – B (Format for Financial Bid)**

#### **Rate List/ Quantity Schedule**

<b>Name of Work:- Repairs and renovation of Base Hospital Baltal including fixing of CGI sheet roofing before Yatra and dismantling of roofing and safe storage after conclusion of Yatra.</b>					
<b>S.No: 02</b>			<b>Adv. Amount: Rs. 1.83 lakh</b>		
<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate as per JKSR of 2020 (in Rs.)</b>	<b>Rate to be quoted by the Bidder(in %age above or below)</b>

I	II	III	IV	V	VI
<b>Part-A</b>					
1	Engagement of labourers for repairs to steel trusses of Hangar including strengthening of truss by way of welding including closure of the hospital post Yatra by welding from all sides ,for clearance of foreign matter,shifting of Toilets stacked in the premises pre yatra and shifting back it to the ward post yatra, washing of flooring ,Refixing of ceiling of Hanger rooms and ceiling of CGI sheets with seal damaged in winter, repairs/restoration of electrification etc.				
1a	Blacksmith	6	Days	₹ 980.70	
1b	Carpenter	3	Days	₹ 980.70	
1c	Electrician	6	Days	₹ 980.70	
1d	Helper	22	Days	₹ 673.00	
2	Dismantling of CGI sheet walls, roofing prefab huts vertical curved side and stacking within 50m lead including opening of doors, windows etc (complete in all respect)	298.42	sqm	₹ 113.90	
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	69.04	sqm	₹ 17.00	
4	Providing and applying white cement based putty of specified thickness, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete-1 mm thick	69.04	sqm	₹ 129.50	

5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade, one or more coats on old work.	110.46	sqm	₹ 80.10
6	Providing and fixing Sanitary fittings to the washrooms			
7	a)PTMT Bib Cock of approved quality and colour-15mm nominal bore,86mm long,weight not less than 88 gms.	8	Each	₹ 194.90
8	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete.-50mm thick with 20 mm nominal size stone aggregate.	16.72	sqm	₹ 505.00
9	Carriage of cement from Ganderbal to site of work by MT including L/U complete for 70 Km lead	0.33	Tonne	₹ 694.99
10	Carriage of sand and bajri below 40 mm size for an average lead of 5 km.	1.12	cum	₹ 179.37

### Part-B

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be Quoted by Bidder (in Rs.)
I	II	III	IV	V
11	Fixing of corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers etc complete.	298.87	sqm	

12	Fixing of ridges or hips of width 60 cm overall width overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mmdia G.Ilimpet and bitumen washers complete 0.63mm thick with zinc coating not less than 275gm/m <sup>2</sup> pre Yatra and dismantling of the same post Yatra 2022.	15.4	meter	
13	Fixing of PVC Sheet 2mm thick to vertical portion of the Hall (Main Ward) including dismantling of the same after conclusion of Yatra 2022.	109.84	sqm	
14	Providing and fixing 5.5 mm thick pre-laminated MDF Board grade 2 type 2 (IS 4587.)	17.57	sqm	
15	Construction of temporary kitchen shed of size (3.75mx3.05m) with available material of wooden ballies/batterns and CGI sheets excluding cost of materials and Carriage of wooden ballies , CGI sheets and 2 No washbasins from SASB store to site including loading,unloading complete.	36.89	sqm	
16	Providing and fixing Sanitary fittings to the washrooms			
16a	C.P angle valve of approved quality and colour	8	Each	
16b	Elbow,Tee (1/2 ")	14	Each	
16c	PVC connection pipe to fittings and Geyser	8	Each	
17	Providing and fixing of flex signage with frame as approved by Engineer-in-charge for Base Hospital including carriage and erection.	24.38	sqm	

<p><b>Total cost of bid (to be quoted both in figures and words)</b>  <b>Total of Part-A and Part-B</b></p>	
---	--

Junior Engineer

DGM

Signature of Bidder

**SCHEDULE – B (Format for Financial Bid)**

Rate List/ Quantity Schedule

Name of Work:- Construction of 6 Nos Soakage Pits at Baltal Base Camp.

S.No: 03

Adv. Amount: Rs. 3.50 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI

<b>Part-A</b>					
1	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres - All kinds of soil :	173.16	Cum	₹ 252.05	
2	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil	86.58	Cum	₹ 81.65	
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	4.24	Cum	₹ 4,419.85	
4	Dry random rubble masonry with hard stone in foundation and plinth: Without bond stone -Nallah	84.78	Cum	₹ 2,355.95	
5	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level- 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	5.77	Cum	₹ 6,344.25	
6	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm wide.	65.94	Rm	₹ 242.30	



7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level- Thermo-Mechanically Treated bars of grade Fe-500D or more.	300	Kg	₹ 79.25
8	Carriage of Cement and steel bars by MT for 70 Km Lead.	2.86	Tonne	₹ 694.99
9	Carriage of sand, bajri and metal by MT for an average lead of 5 km	13.5	Cum	₹ 179.37
<b>Total cost of bid (to be quoted both in figures and words) Total of Part-A</b>				

Junior Engineer

DGM

Signature of Bidder

### **SCHEDULE – B (Format for Financial Bid)**

#### **Rate List/ Quantity Schedule**

**Name of Work:- Construction of pucca bases (30Nos) of toilets in CRPF  
Camp and Tentage area at Baltal Camp.**

**S.No: 04**

**Adv. Amount: Rs. 3.60 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder (in %age above or below)

I	II	III	IV	V	VI
<b>Part A</b>					
1	Earth work in excavation by manual means over areas for foundation , drains, cables, cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	19.98	Cum	₹ 436.00	
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	9.48	Cum	₹ 4,419.85	
3	Providing and laying in position cement concrete of specified grade including curing but excluding cost of centring and shuttering all works up to plinth level. 1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 20 mm nominal size) nallah stone.	17.7	Cum	₹ 4,943.40	
4	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	32.4	sqm	₹ 505.00	
5	Centring and shuttering including strutting, propping etc. removal of frame work for bases, columns and plinths.	177.06	sqm	₹ 262.30	
6	Cement concrete pavement with 1:2:4 (1cement: 2 coarse sand: 4 graded crushed stone aggregate 20 mm nominal size) including finishing and curing complete.	3.174	Cum	₹ 6,408.55	
7	Extra for making chequers of approved pattern on cement concrete floors, steps, landing, pavements etc	42.3	sqm	₹ 60.40	

8	Construction of cement concrete manhole of clear size 450x600x450mm having sides 200 mm thick constructed with M10 mix over 150mm thick mud mat laid with M7.5 and inside channel made with M15. The manhole is covered with precast RCC slab made with M20 mix of size 1000x850x100mm including earthwork and carriages of material upto site etc (complete job)	12	Nos	₹ 4,446.00
9	Carriage of Cement by MT for 70 Km Lead from Ganderbal to Baltal.	7.176	Tonne	₹ 694.99
10	Carriage of sand, bajri and metal by MT for an average lead of 5 km	43.5	Cum	₹ 179.37
<b>PART B</b>				
<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be Quoted by Bidder (in Rs.)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>
11a	110 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure	30.00	meter	
11b	10mm dia PVC Bends	18	Each	
11c	110mm dia PVC Tee	30	Each	
11d	110mm dia PVC sockets	36	Each	
11e	150mm dia PVC Pipe 4kg/cm <sup>2</sup> pressure	48.00	meter	
11f	150mm dia PVC Sockets	18	Each	
11g	150mm dia PVC Bend	12	Each	
11h	150mm dia PVC Tee	6	Each	

Total cost of bid (to be quoted both in figures and words)  
Total of Part-A and Part-B

Junior Engineer

DGM

Signature of Bidder

**SCHEDULE – B (Format for Financial Bid)**

**Rate List/ Quantity Schedule**

Name of Work:- Remodelling of old pucca toilet blocks (40 units) in  
Baltal Base Camp Area.

S.No: 05

Adv.Amount:  
Rs. 8.00 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder (in %age above or below)
I	II	III	IV	V	VI
<b>Part A</b>					
1	Engagement of labour for dismantling of Indian type commodes and making of holes in the walls for fixing of traps /fittings/sewer lines, Dismantling of old sanitary fittings, plumbing items ,fitting of commode, seat cover and flush tank to each unit, minor repairs to doors, vents and windows				
1a	Mason(2nd Class)	16	Days	₹ 891.00	
1b	Fitter Class 1st	32	Days	₹ 980.70	
1c	Asst Fitter 2nd class	8	Days	₹ 891.00	
1d	Helper	88	Days	₹ 673.00	
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	7.152	Cum	₹ 4,419.85	
3	Providing and laying damp-proof Course 50 mm thick with cement concrete 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate 20 mm nominal size) and curing complete	59.52	sqm	₹ 372.85	
4	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1: 4 ( 1 cement : 4 coarse sand) including	43.2	sqm	₹ 1,052.75	

	pointing the joints with white cement and matching pigment etc., complete. In colour such as White, Ivory, Grey, Fume Red Brow			
5	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados over 12 mm thick bed of cement mortar 1:3 ( 1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	151.2	sqm	₹ 1,161.05
6	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth and curing complete	34.2	sqm	₹ 496.65
7	15mm Cement plaster on the rough side of single or half brick wall of mix 1 : 4 ( 1 cement : 4 coarse sand)	24.00	sqm	₹ 300.45
8	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with epoxy coated aluminium rod with L.P/H.P.H.D plastic balls. 20mm nominal bore, 120mm long, weighing not less than 198gms.	8	Each	₹ 488.45
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot and cold water supply, including all CPVC plain and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-			

	charge.6.00+ 5(2.00) = 16.00 Rm			
9a	15mm nominal outer dia pipes.	80.00	meter	₹ 388.55
9b	20mm nominal outer dia pipes.	48.00	meter	₹ 444.70
10	Constructing brick masonry manhole in cement mortar 1:4 ( 1 cement : 4 coarse sand ) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size),inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :Inside size 90x80 cm and 45 cm deep excluding C.I. cover -With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	16	Each	₹ 8,115.13
11	Providing and fixing in position precast R.C.C. manhole cover and frame of required shape and approved quality. LD - 2.5 Rectangular shape 600x450 internal dimensions	16	Each	₹ 1,279.60
12	Providing and fixing 8mm dia C.P/S.S Jet with flexible tube upto 1 meter long with S.S triangular plate to European type W.C of quality and make as approved by Engineer-in-charge.	40	Each	₹ 328.35
13	Providing and fixing PTMT bib cock of approved quality and colour.15 mm nominal bore, 86 mm long, weighing not less than 88 gms.	40	Each	₹ 194.40
14	Providing and fixing PTMT angle stop cock 15mm nominal bore, weighing not less than	80	Each	₹ 230.50

	85gms.				
15	Providing and fixing uplasticized PVC connection pipe with brass unions 30 cm length- 15 mm nominal bore	40	Each	₹ 77.25	
16	Providing and fixing PTMT grating of approved quality and colour. Circular -type 125 mm nominal dia with 25mm waste hole	40	Each	₹ 50.10	
17	Carriage of Cement by MT for 70 Km Lead from Ganderbal to Baltal.	5.28	Tonne	₹ 694.99	
18	Carriage of sand, bajri and metal by MT for an average lead of 5 km	29.00	Cum	₹ 179.37	
19	Carriage of bricks by MT from Ganderbal to Baltal for an avg lead of 70 Km.	3440	Nos	₹ 2.09	
<b>PART B</b>					
<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be Quoted by Bidder (in Rs.)</b>	
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	
20	Providing and laying of sewerage pipe and fittings of approved brand including earthwork,refilling, carriages upto site of erection :				
20a	110 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure	80.00	meter		
20b	150 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure	80.00	meter		
20c	10mm dia PVC Bends	80	Each		
20d	110mm dia PVC Tee	32	Each		
20e	110mm dia PVC sockets	32	Each		
20f	150mm dia PVC Sockets	32	Each		
21	Hire Charges of Welding set including cost of electrodes and POL for repairs to doors,roofing, vents and windows	8	Days		



Total cost of bid (to be quoted both in figures and words)  
Total of Part-A and Part-B

Junior Engineer

DGM

Signature of Bidder

### **SCHEDULE – B (Format for Financial Bid)**

#### **Rate List/ Quantity Schedule**

Name of Work:- Construction of 20 No. & 10 No. Pucca Bases of Toilets /Baths including sewer line in Langar Store area enrout Baltal to Dumail & Dumail Camp respectively.

S.No: 06

Adv. Amount: Rs. 3.60 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Earth work in excavation by manual means over areas for foundation , drains, cables, cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	19.98	Cum	₹ 436.00	
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	9.48	Cum	₹ 4,419.85	
3	Providing and laying in position cement concrete of specified grade including curing but excluding cost of centring and shuttering all works up to plinth level. 1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 20 mm nominal size) nallah stone	17.7	Cum	₹ 4,943.40	
4	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	32.4	sqm	₹ 505.00	

5	Centring and shuttering including strutting, propping etc. removal of frame work for bases, columns and plinths.	177.06	sqm	₹ 262.30
6	Cement concrete pavement with 1:2:4 (1cement: 2 coarse sand: 4 graded crushed stone aggregate 20 mm nominal size) including finishing and curing complete.	3.17	Cum	₹ 6,408.55
7	Extra for making chequers of approved pattern on cement concrete floors, steps, landing, pavements etc	42.3	sqm	₹ 60.40
8	Construction of cement concrete manhole of clear size 450x600x450mm having sides 200 mm thick constructed with M10 mix over 150mm thick mud mat laid with M7.5 and inside channel made with M15. The manhole is covered with precast RCC slab made with M20 mix of size 1000x850x100mm including earthwork and carriages of material upto site etc (complete job)	12	Nos	₹ 4,446.00
9	Carriage of Cement by MT for 70 Km Lead from Ganderbal to Baltal.	7.17	Tonne	₹ 694.99
10	Carriage of sand, bajri and metal by MT for an average lead of 5 km	43.50	Cum	₹ 179.37

### Part-B

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be Quoted by Bidder (in Rs.)
I	II	III	IV	V

11	Providing and laying of sewerage pipe and fittings of approved brand including carriages upto site of erection :			
11a	110 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure	30.00	meter	
11b	150 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure	48.00	meter	
11c	10mm dia PVC Bends	18	Each	
11d	110mm dia PVC Tee	30	Each	
11e	110mm dia PVC sockets	36	Each	
11f	150mm dia PVC Sockets	18	Each	
11g	150mm dia PVC Bend	12	Each	
11h	150mm dia PVC Tee	6	Each	
<b>Total cost of bid (to be quoted both in figures and words) Total of Part-A &amp; Part B</b>				

Junior Engineer

DGM

Signature of Bidder

### **SCHEDULE – B (Format for Financial Bid)**

#### **Rate List/ Quantity Schedule**

Name of Work:- Construction of 02 No. and 01 No. Soakage Pits in Langar Store Area enroute Baltal to Dumail and at Dumail camp respectively.

S.No: 07

Adv. Amount: Rs. 1.78 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder (in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres - All kinds of soil :	86.58	Cum	₹ 252.05	
2	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil	43.29	Cum	₹ 81.65	
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	2.12	Cum	₹ 4,419.85	
4	Dry random rubble masonry with hard stone in foundation and plinth: Without bond stone –Nallah	42.39	Cum	₹ 2,355.95	
5	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level- 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	2.88	Cum	₹ 6,344.25	

6	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm wide	32.97	meter	₹ 242.30
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level- Thermo-Mechanically Treated bars of grade Fe-500D or more.	150	Kg	₹ 79.25
8	Carriage of Cement by MT for 70 Km Lead from Ganderbal to Baltal.	1.43	Tonne	₹ 694.99
9	Carriage of sand, bajri and metal by MT for an average lead of 5 km	6.75	Cum	₹ 179.37
<b>Part-B</b>				
<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be Quoted by Bidder (in Rs.)</b>
I	II	III	IV	V
10	Providing and laying 150 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure dia of approved brand including carriage upto site of erection	9.00	meter	
<b>Total cost of bid (to be quoted both in figures and words) Total of Part-A &amp; Part B</b>				

Junior Engineer

DGM

Signature of Bidder

### **SCHEDULE – B (Format for Financial Bid)**

#### **Rate List/ Quantity Schedule**

Name of Work:- Construction of 4 No. temporary rooms for medical and other departments after dismantling of safety panels of SASB complex at Dumail before start of Yatra and dismantling of temporary rooms and re-fitting of safety panels to SASB complex at Dumail after culmination of Yatra 2022.

S.No: 08

Adv. Amount: Rs. 0.95 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Dismantling of safety panels of Mild Steel frame and stacking properly.	374.00	sqm	₹ 113.90	
<b>Part-B</b>					
S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be Quoted by Bidder (in Rs.)	
I	II	III	IV	V	
2	Fixing of safety panel including welding to convert as rooms for security forces and for medical department during Yatra period(04 rooms) and director office vertically including closure with welding to avoid damages during winter	374.00	sqm		
<b>Total cost of bid (to be quoted both in figures and words)</b>					
<b>Total of Part-A and Part-B</b>					

Junior Engineer

DGM

Signature of Bidder

**SCHEDULE – B (Format for Financial Bid)**

**Rate List/ Quantity Schedule**

**Name of Work:- Minor repairs and painting of Toilet/Baths (300 Nos) including writing numerical for numbering of Toilet/Baths at Lower Camps for Yatra 2022.**

**S.No: 09**

**Adv. Amount: Rs. 5.96 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade (one or more coats on old work.)	6483.00	sqm	₹ 80.10	
2	Applying priming coat: With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	342.00	sqm	₹ 52.75	
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	342.00	sqm	₹ 121.95	
4	Re-lettering with black Japan paint of approved brand and manufacture.	6000.00	cm	₹ 2.90	
<b>Total cost of bid (to be quoted both in figures and words) Total of Part-A</b>					

Junior Engineer

DGM

Signature of Bidder

**SCHEDULE – B (Format for Financial Bid)**

**Rate List/ Quantity Schedule**



Name of Work:- Providing and laying of sewer line for disposal of sullage (enroute Baltal to Dumail) to Soakage Pits for Yatra 2022.

S.No: 10

Adv. Amount: Rs. 11.92 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: for 80% all kinds of soil and 20% ordinary rock.	287.25	cum	₹ 542.37	
2	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc. complete.				
2a	150 mm dia. R.C.C. pipe	200.00	meter	₹ 451.10	
2b	250 mm dia. R.C.C. pipe	320.00	meter	₹ 730.80	
2c	300 mm dia. R.C.C. pipe	265.00	meter	₹ 840.25	

3	Constructing brick masonry manhole in cement mortar 1:4 ( 1 cement : 4 coarse sand ) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size),inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :				
3a	Inside size 90x80 cm and 45 cm deep excluding C.I. cover with common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	16	Each	₹ 8,115.13	
3b	Inside size 90x80 cm and 60 cm deep excluding C.I. cover with common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	21	Each	₹ 9,266.09	
4	Providing and fixing in position precast R.C.C. manhole cover and frame of required shape and approved quality. LD - 2.5 Rectangular shape 600x450 internal dimensions	37	Each	₹ 1,279.60	
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	155.89	cum	₹ 198.70	

6	Extra for levelling & neatly dressing of disposed soil completely as directed by Engineer-in-charge.	131.36	cum	₹ 59.95
7	Carriage of Cement by MT for 70 Km Lead from Ganderbal to Baltal.	9.9	Tonne	₹ 694.99
8	Carriage of sand, bajri and metal by MT for an average lead of 5 km	20.92	Cum	₹ 179.37
9	Carriage of materials from source to site of work by MT for avg distance of 70 Km including L/U complete.			
9a	150 mm dia. R.C.C. pipe	200.00	meter	₹ 28.48
9b	250 mm dia. R.C.C. pipe	320.00	meter	₹ 65.84
9c	300 mm dia. R.C.C. pipe	265.00	meter	₹ 81.38
10	Carriage of bricks by MT from Ganderbal for 70 Km lead.	9446.00	Each	₹ 2.09
<b>Total cost of bid (to be quoted both in figures and words)</b> <b>Total of Part-A</b>				

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:- Restoration of defunct sewer line in CRPF area and Langars to Grease Trap including repair to firegaps between Langars at Baltal for Yatra 2022.**

**S.No: 11**

**Adv. Amount: Rs. 6.32 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate as per JKSR of 2020 (in Rs.)	Rate to be quoted by the Bidder(in %age above or below)
I	II	III	IV	V	VI
<b>Part-A</b>					
1	Dismantling of manhole including R.C.C. top slab, C.I. cover with frame including stacking of useful materials near the site and disposal of unserviceable materials into municipal dumps within 50 m lead as per directions of Engineer-in-Charge:				
1a	Rectangular manhole 90x80 cm and 45 cm deep	5	Each	₹ 1,643.80	
1b	Rectangular manhole 120x90 cm and 90 cm deep.	6	Each	₹ 2,889.95	
2	Engaging of Safai Karamcharis for the clearance of choked sewer lines (to be paid as per actual engaged)	50	Each	₹ 761.25	
3	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: for 80% all kinds of soil and 20% ordinary rock.	65.85	cum	₹ 542.37	
4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc. complete.				
4a	150 mm dia. R.C.C. pipe	50.00	meter	₹ 451.10	

4b	250 mm dia. R.C.C. pipe	50.00	meter	₹ 730.80
4c	300 mm dia. R.C.C. pipe	100.00	meter	₹ 840.25
4d	450 mm dia. R.C.C. pipe	70.00	meter	₹ 1,348.95
5	Constructing brick masonry manhole in cement mortar 1:4 ( 1 cement : 4 coarse sand ) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size),inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :			
5a	Inside size 90x80 cm and 60 cm deep excluding C.I. cover with common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	15	Each	₹ 9,266.09
5b	Inside size 120x90 cm and 90 cm deep excluding C.I. cover with common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	4	Each	₹ 16,352.05
6	Providing and fixing in position precast R.C.C. manhole cover and frame of required shape and approved quality. LD - 2.5 Rectangular shape 600x450 internal dimensions	19	Each	₹ 1,279.60
7	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 ( 1 cement : 3 coarse sand) finished with a floating coat of neat cement and making necessary channels for the drain etc. complete			

7a	For pipes 250 to 300 mm diameter	6	Each	₹ 683.20
7b	For pipes 350 to 450 mm diameter	4	Each	₹ 985.85
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	25.72	cum	₹ 198.70
9	Extra for levelling & neatly dressing of disposed soil completely as directed by Engineer-in-charge.	40.13	cum	₹ 59.95
10	Carriage of Cement by MT for 70 Km Lead from Ganderbal to Baltal.	5.62	Tonne	₹ 694.99
11	Carriage of sand, bajri and metal by MT for an average lead of 5 km	12.39	Cum	₹ 179.37
12	Carriage of materials from source to site of work by MT for avg distance of 70 Km including L/U complete.			
12a	150 mm dia. R.C.C. pipe	50.00	meter	₹ 28.48
12b	250 mm dia. R.C.C. pipe	50.00	meter	₹ 65.84
12c	300 mm dia. R.C.C. pipe	100.00	meter	₹ 81.38
12d	450 mm dia. R.C.C. pipe	70.00	meter	₹ 189.90
13	Carriage of bricks by MT from Ganderbal for 70 Km lead.	9090.00	Each	₹ 2.09
<b>Total cost of bid (to be quoted both in figures and words)</b> <b>Total of Part-A</b>				

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:- Assembling/erection of Toilet/Baths including repairs before commencement of Yatra including dismantling and safe storage in SASB stores after conclusion of Yatra at Baltal**

**Adv. Amount: Rs. 5.50  
lakh**

**S.No: 12**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be Quoted by Bidder (in Rs.)
I	II	III	IV	V
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by mechanical transport/head load. ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply iii. Supply of nuts & bolts etc of required size. iv. Maintenance of structure of toilet/baths during yatra. v. Excavation/ repair to the cess pits including covering of the same with available material in SASB store. (Complete Job)			
1.1	Indian type toilet and Bathroom	540.00	No.	
1.2	EWC including complete fittings	60.00	No.	
2	Providing and laying of sewerage pipe and fittings of approved brand including carriages upto site of erection :			
2.1	110 mm dia PVC pipe of 4kg/cm <sup>2</sup> pressure	250.00	Rm	
2.2	110 mm dia PVC Bends	250.00	No.	
2.3	110 mm dia PVC Tee	200.00	No.	
2.4	110 mm dia PVC sockets	250 .00	No.	
3	Dismantling of toilets/baths and carriage of material from erection site to SASB store including safe and proper stacking after conclusion of Yatra.			
3.1	Indian type toilet and Bathroom	540.00	No.	
3.2	EWC including complete fittings	60.00	No.	
<b>Total cost of bid (to be quoted both in figures and words)</b>				

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:- Assembling/erection of Toilet/Baths including repairs before commencement of Yatra including dismantling and safe storage in SASB stores after conclusion of Yatra at Neelgrath & enroute Rangamoh to Dumail.**

**Adv. Amount: Rs. 7.50  
lakh**

**S.No: 13**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be Quoted by Bidder (in Rs.)
I	II	III	IV	V
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by mechanical transport/head load. ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply iii. Supply of nuts & bolts etc of required size. iv. Maintenance of structure of toilet/baths during yatra. v. Excavation/ repair to the cess pits including covering of the same with available material in SASB store. (Complete Job)			
1.1	Indian type toilet and Bathroom	500.00	No.	
1.2	EWC including complete fittings	100.00	No.	
2	Providing and laying of sewerage pipe and fittings of approved brand including carriages upto site of erection :			
2.1	110 mm dia PVC pipe of 4kg/cm2 pressure	300.00	Rm	
2.2	110 mm dia PVC Bends	300.00	No.	
2.3	110 mm dia PVC Tee	250.00	No.	
2.4	110 mm dia PVC sockets	300.00	No.	
3	Dismantling of toilets/baths and carriage of material from erection site to SASB store including safe and proper stacking after conclusion of Yatra.			
3.1	Indian type toilet and Bathroom	500.00	No.	
3.2	EWC including complete fittings	100.00	No.	
<b>Total cost of bid (to be quoted both in figures and words)</b>				

Junior Engineer

DGM

Signature of Bidder