

Shri Amarnathji Shrine Board



Jammu and Kashmir

Notice Inviting Tender

**Fabrication, Supply and Installation of Sign Boards &
Shelter Sheds for
Service providers at Chandanwari and Sheshnag
Camp along Pahalgam Axis
(Yatra – 2022)**

Sd/-

General Manager (Work)
Shri Amarnathji Shrine Board

Dated: 23.03.2022

**TENDER FOR THE WORK FABRICATION, SUPPLY AND INSTALLATION OF
SHELTER SHEDS FOR
SERVICE PROVIDERS AT CHANDANWARI AND SHESHNAG CAMP
(YATRA – 2022)**

DETAILED NOTICE INVITING TENDER (DNIT)

(Issued under no. SASB/NIT/W/2022/1352/17 dated 22.03.2022)

| # | CONTENT | PAGE(S) |
|----------|--|----------------|
| 1 | Notice Inviting Tender (NIT) for advertisement | 3 |
| 2 | Eligibility requirement | 4 |
| 3 | Documents establishing Bidder's eligibility | 4 |
| 4 | Instructions to Bidders | 5-7 |
| 5 | Job Description | 7-10 |
| 6 | Terms and Conditions of Contract | 10-18 |
| 7 | Schedule – A (Technical Bid) | 19-20 |
| 8 | Bid Security Declaration Form | 21 |
| 8 | Schedule – B (Financial Bid) | 22-26 |



SHRI AMARNATHJI SHRINE BOARD

(Established under an Act of J&K State Legislature)

Chaitanya Ashram, Talab Tillo, Jammu (Nov-April)

Tele: 0191-2569910, Telefax: 0191-2503399

E-mail sasbik2001@gmail.com

NOTICE INVITING TENDERS

FABRICATION, SUPPLY AND INSTALLATION OF SHELTER SHEDS YATRA- 2022

For and on behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format are invited from reputed, experienced and financially sound SSI Unit holders / Micro Small & Medium Entrepreneurs having valid Registration from District Industries Centre, for the below mentioned works. The Bids shall be received in the Office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu on or before 30.03.2022 upto 1400 hours.

| S. No. | Name of work | Approx. Amount (Rs. In Lakhs) | Cost of Tender Document (in Rs) | Earnest Money/ Bid Security (in Rs) | Last date for submission of Tenders |
|--------|--|-------------------------------|---------------------------------|--|-------------------------------------|
| I | Fabrication, supply and installation of Shelter Shed for Service providers at Chandanwari Camp | 2.80 | 200.00 | Bid Security Declaration to be made by the bidder in the shape notarized sworn statement on prescribed Format | 30.03.2022 upto 1400 hours |
| II | Fabrication, supply and installation of Shelter Shed for Service providers at Sheshnag Camp | 3.00 | 200.00 | | |
| III | Fabrication, Supply and Installation of Sign Boards at various Yatra Camps and Enroute Pahalgam Axis for Yatra -2022 | 3.80 | 200 | | |

- Detailed NIT (DNIT) can be downloaded from SASB website (www.shriamarnathjishrine.com) from 24.03.2022 to 29.03.2022 on payment of cost of document in the shape of Demand Draft (Non Refundable) drawn in favour of Director Finance, Shri Amarnathji Shrine Board (SASB), Jammu.
- The Bids, duly completed, along with Bid Security Declaration, must reach the office of General Manager (Works) latest by 30.03.2022 upto 1400 Hrs. The Bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through Speed Post/ Registered Post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reasons.
- The Technical bid shall be opened on 30.03.2022 at 1430 Hrs in the Office of General Manager (Works) at Jammu Office (address mentioned above) in presence of the Bidders who may wish to be present on the occasion.
- The site for the work is available. The intending bidders are strongly advised to inspect the site of work before bidding.
- Not more than three bid documents shall be issued to a single Bidder.
- In case the last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day upto 1400 hours.
- The successful Bidder is bound to enter into an agreement with General Manager (Works), SASB, within ten days from the date of the receipt of Letter of Intent (LoI).
- All addenda, corrigenda, dedenda and amendment shall be uploaded on website only and not in print media and the Bidders are advised to keep themselves updated on this account.

No: SASB/NIT/W/2022/1352/17
Dated: 23.03. 2022

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

2. **ELIGIBILITY REQUIREMENT**

- 2.1 The Bidder must be a registered Micro, Small or Medium Enterprise, with Government of Jammu and Kashmir, District Industries Centre.
- 2.2 Consortium or a Joint Venture in any form shall not be eligible for bidding.
- 2.3 Average annual turnover during the last three years, ending 31st March of the previous financial year (i.e. 2017-18, 2018-19, 2019-20), should be equal to 30% of the estimated amount of the work.
- 2.4 The bidder should have an experience of having successfully completed similar works in Hilly Regions during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-
 - a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or
 - b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or
 - c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.
- 2.5 The Bidder should not have been blacklisted on previous occasion by any of the Central/ Union Territory Government Organizations, Statutory Central/ U.T. Autonomous Bodies, Central/ U.T. Public Sector Undertakings, Central/ U.T. Government owned Hospitals or Local Bodies/ Municipalities.

3. **DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY**

- 3.1 Registration Certificate from any District Industries Centre of Jammu and Kashmir.
- 3.2 Certified copies of Bank Turn over
- 3.3 Certified copy of PAN Card.
- 3.4 Certified Copy of GSTIN (along with latest clearance certificate/ Acknowledgement receipt of GST return Copy "Form - GSTR3B" Ending February-2022)
- 3.5 Bid security declaration duly notarised
- 3.6 General information/ Profile of the Bidder.
- 3.7 An affidavit by the Bidder, on Rs. 100 stamp paper, stating that every information furnished in the Tender Document is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. (If any information is found to be incorrect at any time, the Security Deposit shall be liable to be forfeited without any notice).

4. **INSTRUCTIONS TO BIDDERS:**

Sealed Bids in Two-Bid Format are hereby invited from original Equipment Manufacturers for the Design, Fabrication, Supply and Installation of Sheds at Shrine Board Camps (*for details of these locations, please read Scope of Work*).

- 4.1 Detailed NIT (DNIT) can be downloaded from SASB website (www.shriamarnathjishrine.com) from 24.03.2022 to 29.03.2022 on payment of cost of document in the shape of Demand Draft (Non Refundable) drawn in favour of Director Finance, Shri Amarnathji Shrine Board (SASB), Jammu.
- 4.2 The Tenderers are required to submit two separate **Bids** i.e. – **Technical** and **Financial**, as per format given in **Schedule A** and **Schedule B** of the DNIT respectively. The two **Bids** should be submitted in two separately sealed envelopes super-scribed “**Technical Bid for _____ Yatra 2022**” and “**Financial Bid for _____ Yatra 2022**”. Both the sealed envelopes should be put in a third envelop, sealed and super-scribed “**Tender for Fabrication, Supply and Installation of _____ Yatra 2022**”. The bids shall be submitted as per format prescribed in **Schedule A** and **Schedule B** only.
- 4.3 The Tender, duly completed, along with **Bid Security Declaration** must be dropped in the Tender Box kept in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered Post/ Speed Post to General Manager (Works) at aforesaid address by **1400 hours** on **30.03.2022**. Tenders received after the afore-stated date and time will not be considered. The Shri Amarnathji Shrine Board takes no responsibility for any delay/ loss of documents or correspondence sent by post.
- 4.4 The intending Bidders are advised to obtain information about the actual conditions on ground. The Bidder shall bear all costs associated with the preparation and submission of his bid and the SASB will, in no case, be responsible for those costs, regardless of the conduct or outcome of the bidding process.
- 4.5 The Bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all relevant information as prescribed in the Tender Document or submission of Tender not substantially responsive to the Tender Document in every respect will be at Bidder’s risk and may result in the rejection of the bid.
- 4.6 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be indicated in words as well as in figures. In case of any variation between amount in figures and words, amount quoted in words shall be taken as authentic.
- 4.7 The rate quoted should be inclusive of all taxes including GST.

- 4.8 The rate quoted by the Contractor in item tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.9 Any tenderer which stipulates any alteration to any of the conditions laid down or which proposes any other condition of any description whatsoever is liable to be rejected.
- 4.10 The Bidder must satisfy himself that it fulfils all the prescribed eligibility conditions to avoid rejection of its bid.
- 4.11 Each paper of the Tender document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B (Financial Bid)** is liable to be rejected.
- 4.12 Bids must be received at the address specified above not later than the date and time stipulated in this DNIT. The General Manager (Works), SASB may, at his discretion, extend the deadline for submission of bids. Any bid received after the deadline for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.13 The Bidder shall quote relevant National/ International Code of the parts, along with manufacturer's Name, Trade Mark or Patent No., if any, used in construction of prefab huts.
- 4.14 Clarifications on DNIT, if any, may be sought by the bidders so as to reach the office of General Manager (Works), SASB at least seven days before last date prescribed for submission of bids. Except for any written clarification by, the General Manager (Works), SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on our webpage (www.shriamarnathjishrine.com) and NOT in the newspaper. Bidders shall keep themselves updated on this account.
- 4.15 The Technical Bid shall be opened at **1500 hours** on **30.03.2022** in the office of the General Manager (Works) Shri Amarnathji Shrine Board, Talab Tillo, Jammu in the presence of the authorized representatives of the firms who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.16 The General Manager (Works), SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the bidders, terminate the tender process without assigning any reasons thereof.
- 4.17 The Tender shall remain valid and open for acceptance for a period of 60 days from the last date of receipt of tender.

- 4.18 The General Manager (Works), SASB shall award the Contract to the successful Bidder whose bid has been found to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will communicate the successful Bidder through Registered Post that his bid has been accepted. This letter (hereinafter referred to as the 'Letter of Intent') shall prescribe the amount which the Shrine Board will pay to the Contractor in consideration of work/ services to be executed by the Contractor as prescribed in the Contract.
- 4.19 The eligible Bidder shall be required to furnish a Performance Security Deposit within ten days of receipt of 'Letter of Intent' equal to 10% of the total value of the Contract, in the form of CDR/ FDR in favour of FA & Chief Accounts Officer, SASB. The EMD (if deposited) of the eligible Bidder will be adjusted against the amount to be deposited as Performance Security Deposit. In case the eligible Bidder fails to submit the Performance Security Deposit of the requisite amount within the stipulated period, the 'Letter of Intent' is liable to be withdrawn and the EMD (if deposited) is liable to be forfeited, at the discretion of the Shrine Board.
- 4.20 The eligible Bidder after furnishing the prescribed Performance Security Deposit (PSD) will have to enter into an Agreement with the Shrine Board as per the Terms and Conditions mentioned in the DNIT or such other terms that may be prescribed, within a period of ten days from the date of receipt of 'Letter of Intent'.
- 4.21 General Manager (Works), SASB reserves the right to reject all or any Tender in whole, or in part, without assigning any reasons. Any enquiry after the submission of Bid will not be entertained.

5. Job Description

A. Fabrication, supply and Installation of Shelter shed at Chandanwari (Complete job).

Brief specifications of the Sheds are as given below;

| S. No. | Description |
|--------|--|
| 1 | <p>Steel work in built up tubular round, square or rectangular section including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc. complete.</p> <p>(i)Columnposts=(80x40x2.6mm) 12x2.40M = 28.80 Rm 02x1.80 M = 3.60 Rm Total =32.40 Rm @4.55 kg/Rm =147.42 kg --A</p> <p>(ii) Horizontal Tie = Tubular Section (66x33x2.6mm). 2x3x(4.15+5.40) M = 57.30 Rm Partition= 1x3x5.40) M = 16.20 Rm Door portions = 1x2.40 M = 2.40 Rm Wash room= 1x3x2.0 M+2x3x1.50 M= 15.00 Rm Trusses for Room = 3x17.70 Rm = 53.10 Rm Wash room = 2x2.00 Rm = 4.00 Rm Purlins =2x4x6.00 M = 48.00 Rm Total = 196.00 Rm @3.69 kg/Rm =723.24kg -B</p> <p>iii) M.S Plates 8mm thick</p> |

| | |
|-----|---|
| | <p>Base plates=14x(1x2) x0.20mx0.20m =1.12 M2 @ 62.10 kg/ M2 = 69.56 kg-C</p> |
| | <p>iv) M.S Plates 6 mm thick Top plates = 14x(1x2) x 0.15x0.15 m = 0.63 M2 @47.10Kg/ M2 = 29.68 kg -D</p> |
| | <p>v) M.S cleats for purlins = 62 Nos. x0.15 M = 9.30 Rm @2.36 kg/M = 21.95 kg -E</p> |
| | <p>Total Weight=M.S. Tubular section A+B = 147.42 + 723.24 = 870.7 kg</p> |
| | <p>Total weight of M. Steel C+D+E = 121.19 kg</p> |
| | <p>Nuts & Bolts = 50kg (approx) to be paid as per actual</p> |
| 2 | <p>Providing and fixing pre coated galvanized iron profile sheets(size, shape and pitch of corrugation as approved by Engineer in-Charge) 0.50mm +/- 0.0 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240 mp steel grade5-7microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal /vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.PPGI sheet 0.50 mm</p> <p>Walling = (2+1)x5.40mx2.40m =38.88 M² 2x4.15Mx2.40 m = 19.92 M² Side gable= 2x1/2x 4.15mx1.00 m = 4.15 M² Washroom =$\frac{2x1.50m \times 2.0+2.15 m}{2}$ = 6.23 M² 1x2.0 m x2.0 m = 4.00 M² Roof = 2x6.0mx3.0 m = 36.00 M² 1x2.60x2.00 m = 5.20 M² D/ds for openings Doors 3x1.0mx2.10 m = 6.30 Window = 4x0.45x1.0 = 1.80 = - 8.10 A Total = 106.28 Sqm</p> |
| 3 | <p>Providing and fixing pre coated galvanized steel sheet roofing accessories 0.50 mm (+/- 0.0 5 %) total coated thickness(TCT),Zinc coating 120 grams per sqm as per IS: 277, in 240 m pasteel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws or with polymer coated Jor L hooks, bolts and nuts and GI:Seam bolts, and nuts,GI plain and bitumen washers complete: Ridge =1x6.0M = 6.00 Rm</p> |
| 4 | <p>Providing and fixing of doors/window shutters. Area @ D/ds 2 –A = 8.10 M²</p> |
| 5. | <p>Carriage of material through mechanical transport upto Chandanwari average 100 km lead.</p> |
| 5.a | <p>Mild steel frame structure /tubular material vide item 1 = 1041.89 kg</p> |
| 5.b | <p>PPGI sheets vide item 2 = 106.28 M² @ 4.75 kg/ M² = 504.83 kg vide item 3 = 6 M x 0.6 m = 3.6 M² @ 4.0 kg/ M² = 14.40 kg</p> |
| 5.c | <p>Door/Window shutters @ item 4 8.10 M² @ 20 kg / M² = 162.00 =1723kgs Or 1.72 MT</p> |

B. Fabrication, supply and Installation of Shelter shed at Sheshnag Camp (Complete job).

Brief specifications of the Sheds are as given below;

| S. No. | Description |
|--------|--|
| 1 | <p>Steel work in built up tubular round, square or rectangular section including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc. complete.</p> <p>i) Column posts= (80x40x2.6 mm) 12x2.40M = 28.80 Rm 02x1.80 M = 3.60 Rm Total =32.40 Rm @4.55 kg/Rm =147.47 kg --A</p> <p>(ii) Horizontal Tie = Tubular Section (66x33x2.6mm). 2x3x(4.15+5.40) M = 57.30 Rm Partition= 1x3x5.40) M = 16.20 Rm Door portions = 1x2.40 M = 2.40 Rm Wash room= 1x3x2.0 M+2x3x1.50 M= 15.00 Rm Trusses for Room = 3x17.70 Rm = 53.10 Rm Wash room = 2x2.00 Rm = 4.00 Rm Purlins =2x4x6.00 M = 48.00 Rm Total = 196.00 Rm @3.69 kg/Rm =723.24kg –B</p> <p>iii) M.S Plates 8mm thick Baseplates=14x(1x2) x0.20mx0.20m =1.12 M2 @ 62.10 kg/ M2 = 69.56 kg-C</p> <p>(iv) M.S Plates 6 mm thick Top plates = 14x(1x2) x 0.15x0.15 m = 0.63 M2 @47.10Kg/ M2= 29.68 kg -D</p> <p>V) M.S cleats for purlins = 62 Nos. x0.15 M = 9.30 Rm @2.36 kg/M = 21.95 kg -E</p> <p>Total Weight=M.S. Tubular section A+B = 147.47 + 723.24 = 870.70 kg</p> <p>Total weight of M. Steel C+D+E = 121.19 kg</p> <p>Nuts & Bolts = 50kg (approx) to be paid as per actual</p> |
| 2 | <p>Providing and fixing pre coated galvanized iron profile sheets(size, shape and pitch of corrugation as approved by Engineer in-Charge) 0.50mm +/- 0.0 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240 mpa steel grade5-7microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal /vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.</p> <p>PPGI sheet 0.50 mm</p> <p>Walling=(2+1)x5.40mx2.40m =38.88 M2 2x4.15Mx2.40m = 19.92 M2 Side gable=2x1/2x4.15mx1.00m = 4.15 M2 Washroom =2x1.50m x 2.0+2.15m/2 = 6.23M2 1x2.0 m x2.0 m = 4.00 M2 Roof =2x6.0mx3.0 m = 36.00 M2 1x2.60x2.00 m = 5.20 M2 Total = 114.38</p> <p>D/ds for openings Doors 3x1.0mx2.10 m = 6.30 Window 4x0.45x1.0 = 1.80 Total = 8.10 --A Total = 106.28 Sqm</p> |
| 3 | <p>Providing and fixing pre coated galvanized steel sheet roofing accessories 0.50 mm (+/- 0.0 5 %) total coated thickness(TCT),Zinc coating 120 grams per sqm as per IS: 277, in 240 m pasteel grade, 5-7 microns epoxy primer on both side of the sheet and</p> |

| | |
|-----|---|
| | polyester top coat 15-18 microns using self drilling/self tapping screws or with polymer coated Jor L hooks, bolts and nuts and GI:Seam bolts, and nuts,GI plain and bitumen washers complete: Ridge =1x6.0M = 6.00 Rm |
| 4 | Providing and fixing of doors/window shutters. Area@ D/ds 2 –A 8.10 M ² |
| 5. | Carriage of material through mechanical transport upto Chandanwari average 100 km lead. |
| 5.a | vide item 1 = 991.89kgs PPGI sheets vide item 2 = 504.83 kgs |
| 5.b | Vide Item 3 =6M x 0.6 m = 3.6 M ² @ 4.0 kg/M ² = 14.40 kg Total = 1781.23 Kgs |
| 5.c | Door/Window shutters=162.00 kgs Total = 1700 Kgs Or 1.70 Mt |
| 6. | Head load of material from Chandanwari to Sheshnag. Mild Steel: PPGI Sheets etc. = 1950kgs @ 30kgs/Potter a. 1200 Kg by Ponies @ 80kg/pony = 15ponies b. 500 Kgs by Potter@25 kg/Potter =20 Poter |

All the components are to be supplied as individual members to be assembled at site with nuts and bolts.

C. Fabrication, supply and Installation Sign Boards at various Casmps and enrout for Pahalgam Axis (Complete job).

Brief specifications of the Sheds are as given below;

| S. No | Description |
|-------|---|
| 01 | Steel work in built up tubular round, square or rectangular section including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc. complete. Round pipe 32 mm nominal bore light gague i. Vertical Posts/Legs 2x7'.0" =14.00 rft Hor. Members = 2x4'.0" =8.00 rft Hold Fasts = 2x0'.6" =1.00 rft Total = 23.00 rft Or 7.00 Rm @ 2.54 Kg/Rm = 17.78 Kgs ii. Flats = 30x4mm 10x0'.2" =1.60 rft Or 0.48 Rm @ 0.94 Kgs/Rm =0.45 Kg's iii. M.S. Sheet 1.5mm thick 1x2'.6"x3'.6" =8.75 sft @ 0.81 Sqm @12 kg/sqm = 9.75 Kg's Total Weight for one board = 27.98 Kg's Such for 50 no. sign Boards =27.98x50 = 1399 kgs |
| 02 | Painting with synthetic paint of approved brand and manufacture to give an even two or more coats on new work 2x4'.0"x3'.0" =24.00 sft Add for legs =4 sft Total quantity for one Sign Board =28.00sft Or 2.60 sqm Such for 50 No. Sign Boards = 2.60x50 = 130 sqm |
| 03 | Writing an approved matter printing and pasting vinyl sheet with required adhesive of approved quality for both side of sign boards 2x3'.6"x2'.6" =17.50 sft (For one no Sign board) Such for 50 No. Boards =50x17.50 = 875 sft |
| 04 | Carriage of sign boards from manufacturing unit by mechanical Transport for 50 km's including loading and un loading Qty vide item no. 01 =27.98 kgs Or 0.028 MT (For one no Sign Board) Such for 50 No. Sign Boards =50x0.028= 1.40 MT |
| 05 | Head load of sign boards from road head to upper sites including its installation etc. Complete job. 50 No Sign Boards. |

6 **Terms and Conditions of Contract:**

- 6.1 **Execution of work:** The Contractor shall complete the work strictly and in accordance with the scope of work given in the DNIT (and as modified in the 'Letter of Award') to the total satisfaction of the Engineer-in-charge i.e. General Manager (Works) or any other Engineer appointed by CEO/ Addl. CEO, SASB). The Contractor must keep in daily contact with Engineer-in-charge to receive instructions regarding work. In the case of an item for which specification are not available in the said Specification, relevant BIS specifications applicable as on the date of Tender shall be followed or, alternatively, the specifications may be decided by the Engineer-In-Charge. Though it is not the intent to specify completely herein all aspects of design and constructional features of a prefab hut and details of work to be carried out, the work shall include all incidental and contingent work which, although not specifically mentioned in Scope of Work, are necessary for completion of work in a sound manner with good workmanship and should be acceptable to the Engineer-in-Charge, who will interpret the meaning of the specifications and drawings and shall have the right to reject or accept any work or material, which in his assessment is not complete to meet the requirements of the specifications and or applicable Standards and Codes mentioned elsewhere in the specifications.
- 6.2 **Role of Engineer-in-charge:** The Engineer-in-charge shall carry out general supervision of the work. The work shall be subject to the approval of Engineer-in-charge from time to time for purposes of determination of the question whether the work is executed by the Contractor in accordance with the contract. He has authority to stop the work, whenever he considers such stoppage necessary to ensure the proper execution of the work. The Engineer-in-charge may issue instructions to the Contractor from time to time during the execution of work for the purpose of proper and adequate executions and maintenance of works and the Contractor shall carry out and be bound by the same. He shall also have authority to inspect and reject all works and materials, which do not conform to the specifications. No claim whatsoever on aforesaid account shall be entertained. In case of any clarification the Contractor may appeal to the General Manager (Works) whose decision shall be final and binding on the Contractor. The above inspection shall, however, not relieve the Contractor of his responsibilities in regard to defective materials or workmanship and the necessity for rectifying or replacing the same.
- 6.3 **Manner of Notice:** Any notice required or permitted by the Contract shall be in English language and may be delivered personally or may be sent by fax/ registered (pre-paid) mail/ email, addressed to the last known address of the Contractor/ Shrine Board.

- 6.4 **Contractor Superintendence, Supervision, Technical Staff & Employees:**
- i. The Contractor shall be solely responsible for the manner and the method of executing the work and provide experienced and qualified supervisors and other manpower for continuous and efficient supervision of works and names, and names of such persons shall be intimated to the Engineer-in-charge during execution of the work and as long thereafter as may be necessary for proper fulfilling the obligations under the Contract. The Engineer-in-charge may direct the Contractor to remove or replace any workman whom he (Engineer-in-charge) considers incompetent or unsuitable. The Engineer-in-charge's opinion as to the competence and suitability of any workmen engaged by the Contractor shall be final and binding on the Contractor.
 - ii. The agency shall be solely responsible for **Workmen's Compensation Act, 1923** for payment of **compensation to workmen** and their dependants in case of injury and accident (including certain occupational disease) arising out of and in the course of employment and resulting in disablement or death.
- 6.5 **Information to be supplied by Contractor after award of work:** The Contractor after issue of Letter of Award of work, shall submit within five days of a Time schedule for fabrication, testing, delivery at Chandanwari/ Sheshnag for erection and handing over (completion) for approval of Engineer-in-charge. Any change suggested by Engineer-in-charge shall be incorporated and the work on the contract shall be executed according to the approved schedule as aforesaid. The schedule should be co-related with the date of commencement of Shri Amarnathji Yatra- 2022 (dates to be intimated later). The sheds complete in all respects, but in knock-down condition should reach to the site of installation at Chandanwari/ Sheshnag upto 25th May, 2022.
- 6.6 **Commencement of work and completion of drawings:** The Contractor shall be provided with one set of drawings containing details of construction layout, critical sectional details, piping routes along with dimensions with the Tender Document. These drawings shall be;
- a) All general arrangement drawings.
 - b) Details along with drawings of various assembled equipment as may be needed generally by Shrine Board for purpose of dismantling/ re-erection/ repair/ modification of shelter shed.
- 6.7 **Time Extension:** If the Contractor shall desire an extension of the time limit for completion of the work on the grounds of his having been unavoidably hindered in its execution or on any other ground he shall apply in writing to the Engineer-in-Charge within one day of the date of the hindrance on account of which he desires such extensions and Engineer-in-Charge, if in his opinion (which shall be final) reasonable grounds as shown thereof, authorized such extension of time if any, as may, in his opinion be necessary or proper.

6.8 **Inspection of Work:**

- (i) All work under or in course of execution or executed in pursuance of the contract shall at all times be open to the inspection and supervision of Engineer-in-charge or his subordinate in-charge of the work.
- (ii) The Contractor shall provide and pay for all necessary tools, instruments gadgets and testing equipments required for conducting various tests. Any defects in material and / or in workmanship detected during initial testing shall be rectified by the Contractor at his own cost. The testing shall be carried out in the presence of Engineer-In-Charge or his representative to his entire satisfaction. The Contractor will produce before the Engineer-in-charge a Test Certificate specifying that the material required for work conforms to ISI standard before it is incorporated in the work.
- (iii) Final inspection will be carried out at the installation site by the Engineer-in-Charge. Whenever preliminary inspection, if any, is carried out at Contractor's works the same shall be subjected to final inspection after complete installation of prefab huts at site (respective sites) and the decision of Engineer-in-charge shall be final.
- (iv) The material rejected by Engineer-in-charge must be removed by Contractor within seven days of rejection, failing which the Board reserves the right to get the rejected material removed at the risk and cost of the Contractor.

6.9 **Guarantee and Defect Liability Period:** The work covered by this contract shall be guaranteed by the contractor against faulty material and workmanship **for a period of 12 months from the date of issue of Completion Certificate** by the Engineer-in-Charge. Any part found defective shall be replaced free of all costs by the Contractor. During the guarantee & defect liability, the contractor shall provide, at no extra cost, necessary material and personnel to carry out the repairs and routine maintenance of the prefab huts. If performance of equipment during guarantee period is not found satisfactory, the guarantee period will be extended till satisfactory performance is established for further period of reasonable time decided by competent authority of SASB. The services of the contractor's personnel, if requisitioned during the defect liability period, shall be made available free of any cost to SASB. If the defects noticed during the guarantee period are not removed within a reasonable time SASB shall have the right to remedy the defects at the contractor's risk & cost.

6.10 **Performance Guarantee:** (i) The work shall be executed according to the schedule approved by Engineer-in-charge with all due diligence (time being deemed to be the essence of the contract on the part of the Contractor). The Contractor shall pay as compensation of an amount equal to 2% of the contract value or such smaller amount as Engineer-in-Charge may decide,

for maximum delay of five days that the work remains un-commenced or unfinished after the dates mutually agreed upon by the parties. After a delay of five days, the General Manager (Works) reserves the right to get the part or whole work completed under risks and cost of the Contractor. The CEO/ Addl. CEO, SASB, on a representation from the Contractor is, however, empowered to reduce the amount of compensation and his decision shall be final.

- (ii) In the event of any loss being caused to the Shrine Board as a result of any lapse on the part of Contractor or personnel engaged by him, duly established after an enquiry conducted by the SASB, the said loss will be recovered from the Contractor upto twice the value of the loss. In such matters, the decision of CEO, SASB shall be final and binding on the Contractor.
- (iii) In case, the Contractor fails to submit the Time schedule as prescribed in Clause 5 above, he shall be liable to pay a sum equivalent to 1% of the value of the work as may be fixed by the CEO, SASB concerned and in this respect, the decision of the CEO, SASB shall be final and binding on the Contractor.
- (iv) If it shall appear to Engineer-in-charge, that any part of work has not been executed or executed with unsound, imperfect or unskilful workmanship or with materials of any inferior description or that any materials or articles provided by him for the execution of the work are unsound or of a quality inferior to the contracted for, or otherwise not in accordance with the contract specifications, the Contractor shall, on demand in writing from the Engineer-in-charge specifying the work materials, articles complained or not withstanding that the same have been inadvertently passed, certified and paid for, forthwith rectify or remove and reconstruct the work so specified in whole or in part as the case may require, or as the case, remove the materials or articles so specified and provide other and suitable materials or articles so specified at his own cost and in the event of his failing to do so within a period to be specified by the Engineer-in-charge, then the Contractor shall be liable to pay compensation at the rate of 1% on the amount of the estimate for every day not exceeding ten days and after completion of ten days the Engineer-in-Charge may rectify or remove, and re-execute the work or remove and replace with other materials or articles complained of, as the case may be at the risk and expenses in all respects of the Contractor. The Engineer-in-charge may reduce the rates at which payments are to be made if the quality of work, although acceptable, is not upto required standard, set forth in the DNIT (as modified by Letter of Award).
- (v) Any deviation/ non-compliance with conditions prescribed in the contract shall invoke penalty as decided by CEO/ Addl. CEO, SASB.

- 6.11 **Conformity with Statutory Acts, Rules, Standards and Codes:** The construction and installation shall be carried out in conformity with applicable Acts, Rules, Standards and Codes. Adherence of compliance shall be the sole responsibility of the contractor to the above Acts, Rules, Standards and Codes applicable in Jammu and Kashmir to the said work.
- 6.12 **Safety codes and regulations:** The contractor shall at his own expenses arrange for the safety provisions as per statutory regulations wherever applicable.
- 6.13 **Provision of utilities / tools etc:** Power supply, water supply and other utilities, if required, at site of work during execution under this Contract shall be arranged by the Contractor at his own cost. The contractor shall be responsible for supply and transportation of water to work site in required quantities both for construction works and drinking purpose of his workers. The contractor shall be responsible for provision and transport of adequate and right type of tools/ accessories, manpower etc in time for efficient execution of work and as may be suggested by Engineer-in-Charge in this regard.
- 6.14 **Storage of materials and safe custody:** Lockable storage space, if available shall be made available to the Contractor by the SASB. However, the contractor shall be responsible for watch & ward and safe custody of his equipment and installation till they are formally taken over by SASB. Non-availability of lockable storage space due to any reasons shall not relieve the contractor of his contractual obligations in any manner.
- 6.15 **Liability:**
- i) Except as otherwise expressly provided, neither the Board's nor its servants, agents or nominees, shall have any liability or responsibility whatsoever to whomsoever (including the owner) for loss or damage to the equipment and or loss or damage to the property of contractor and/ or its sub-contractors, irrespective of how much loss or damage is caused unless caused by wilful and gross negligence of the Shrine Board and/ or its servants and/ or any other person. The Contractor shall protect, defend, indemnify and hold harmless the Board from and against such loss or damage and any suit, claim or expense resulting there from.
 - ii) Neither the Board nor its servants, agents, nominees, assignees, sub-Contractors shall have any liability or responsibility whatsoever for injury to, illness, or death of any employee of the Contractor irrespective of how such injury, illness or death is caused unless caused by wilful and gross negligence of the Board and/ or its servants, agents, nominees, assignees. The Contractor shall protect, defend, indemnify and hold harmless the Board from and against such loss or damage and any suit, claim or expense resulting there from.

- 6.16 **patents and other Industrial Property Rights:** The prices stated in the present Contract shall be deemed to include all amounts payable for the use of patents, copyrights, registered charges, trademarks and payments for any other industrial property rights. The seller shall indemnify the buyer against all claims from a third party at any time on account of the infringement of any or all the rights mentioned in the previous paragraphs, whether such claims arise in respect of manufacture or use. The seller shall be responsible for the completion of the supplies including spares, tools, technical literature and training aggregates irrespective of the fact of infringement of the supplies, irrespective of the fact of infringement of any or all the rights mentioned above.
- 6.17 **Terms of payment:** Contractor is to submit the bills in triplicate along with delivery challans to the Engineer-in-charge for works executed by him duly certified by the Engineer-in-charge. 90% Payment to the agency shall be made after supply and assembling/ erection at the respective site and the balance 10% shall be made;
- a) 10% of the contract Value after completion of warranty period of one year.
- 6.18 The Contractor shall have no claim against the Shrine Board in respect of any work which may be withdrawn, but only for work actually completed under this contract. The SASB reserves the right to cancel the Agreement at any time upon full payment of work done and the value of the materials collected by the Contractor for permanent incorporation in the work under this Contract upto the date of cancellation of the Contract. The valuation of the work done and the materials collected shall be estimated by the Board's Engineer in the presence of the Contractor. The Contractor shall have no claim to any further payment whatsoever. The valuation would be carried out ex-party if Contractor fails to turn up despite reasonable notice, which will be binding on the Contractor.
- 6.20 **Contractor to be liable for all taxes / statutory levies:** The rates specified in the tender shall be for finished work including installation at site (Chandanwari and Sheshnag) and inclusive of GST or any other taxes, duties, levies, and other charges etc., in respect of the contract and the rates shall be firm irrespective of any variation in the prevailing rates of taxes, levies, octroi, etc., and any fresh imposition of any of these by State/ Central/ Statuary bodies.
- 6.21. **Income Tax and GSTIN:** i) Deduction on account of Income Tax, GST any other tax in vogue shall be made at the rate prescribed by the relevant authority from time to time from the gross payments due to the contractor in accordance with the statutory provisions.

6.22 Termination and Consequences thereof:

- i) The Contract shall be deemed to be automatically terminated on the expiry of duration of the Contract (or extension), if any, thereof.
- ii) In the event that the Contractor at any time during the term of the Contract, becomes insolvent or makes a voluntary assignment of its assets for the benefit of creditors or is adjudged bankrupt, then the Company shall, by a notice in writing have the right to terminate the Contract and all the Contractor's rights and privileges hereunder, shall stand terminated forthwith.
- iii) If the SASB considers that, the performance of the Contractor is unsatisfactory, or not upto the expected standard, the SASB shall notify the Contractor in writing and specify in details the cause of the dissatisfaction. The Board shall have the option to terminate the Contract by giving seven (07) days notice in writing to the Contractor, if the Contractor fails to comply with the requisitions contained in the said written notice issued by the Board
- iv) In case the Contractor's rights and/ or obligations under the Contract and/ or the Contractor's rights, title and interest to the equipment/ material, are transferred or assigned without the Board's consent, the Board may at its absolute discretion, terminate the Contract.

6.23 Consequences of Termination:

- (i) In all cases of termination herein set forth, the relative obligations of the parties to the Contract shall be limited to the period upto the date of termination. Notwithstanding the termination of the Contract, the parties shall continue to be bound by the provisions of the Contract that reasonably require some action or forbearance after such termination.
- (ii) If at any time during the term of the Contract, breakdown of Contractor's equipment results in Contractor's being unable to perform their obligation hereunder for a period of 7 successive days (not including Force Majeure delay), the Board at its opinion, may terminate the Contract in its entirety without any further right or obligation on the part of the Company, except for the payment of money then due. No notice shall be served by the Board under the condition stated above.
- (iii) Upon termination of the Contract, Contractor shall return to the Board all of the Board's assets, which are in Contractor's possession at the time.
- (iv) Notwithstanding any provisions herein to the contrary, the Contract may be terminated at any time by the Board on giving 7 (seven) days written notice to the Contractor and in the event of such termination, the Board shall not be liable to pay any cost or damage to the Contractor except for payment for service charges and other charges as per the Contract upto the date of termination.

- (v) In the event of termination of Contract, the Board will issue Notice of Termination to the Contractor with date or event after which the Contract will be terminated. The Contract shall then stand terminated and the Contractor shall demobilize their personnel and materials.
- 6.24 **Force Majeure:** In case of occurrence of Force Majeure conditions, the agency shall promptly inform CEO, SASB about occurrence of such conditions. On receipt of the agency's Report and after ascertaining as to whether Force Majeure conditions exists (such as a Government Order/ Regulation, war, an accident creating a disturbed condition, terrorist activity, court order, strikes/ riots, civil commotion, pandemic like COVID-19 etc.) CEO, SASB shall suspend the agency's license. SASB shall not be liable for any damage or liability of any kind arising out of Force Majeure conditions and/ or any other cause beyond the reasonable control of SASB.
- 6.25 **Arbitration:** In the event of any doubt, dispute or difference of opinion in regard to terms & conditions of the agreement, the concerned parties shall endeavor to settle the same amicably with the SASB through any officer nominated in this behalf. In case, any such doubt, dispute or difference of opinion remains unresolved, the matter shall be referred to the Hon'ble Lieutenant Governor, J&K (Chairman of SASB), who shall be competent to refer the same to any retired Hon'ble Judge of the High Court of Jammu Kashmir & Ladakh for its resolution. The decision so rendered or award, if any, passed shall govern the rights, duties & obligations of the concerned parties and shall be final. No such disputes shall be referred during the currency of the Yatra.
- 6.26 All questions relating to the arbitration shall be determined in accordance with provisions of the Arbitration and Conciliation Act, 1996 and the amendments thereto and any re-enactment or modification thereof and the rules framed there under.

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND BID SECURITY DECLARATION

| S. No. | Particular of item | Details |
|---------------|---|-------------------------|
| 1 | Amount and details of payment towards the cost of DNIT: | Rs. (in words): |
| | | Receipt No./ Cheque No: |
| | | Date: |
| 2 | Bid Securing Declaration | Dated: |
| | | Bid No. |
| | | Name of Notary |

PART – B: BASIC DETAILS ABOUT THE AGENCY.

i) Name and address of :
the Agency.

Name: _____

Address: _____

Phone: _____

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:
(Please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

| # | Financial Year | Turnover (Rs.) |
|---|----------------|----------------|
| 1 | 2017-18 | |
| 2 | 2018-19 | |
| 3 | 2019-20 | |

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

| S. No. | Name of work | Name of Client | Value of Completed work (in Rs.) | Date of commencement | Date of completion | Whether supporting documents (attested) enclosed (Yes/ No) |
|--------|--------------|----------------|----------------------------------|----------------------|--------------------|--|
| | | | | | | |
| | | | | | | |
| | | | | | | |

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*
5. Certified copy of GSTIN – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*
7. Bid Security Declaration – *para 3.7 of Documents Establishing Bidder’s Eligibility’*
8. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility.*

Form of Bid Security Declaration

(Duly notarized)

**The General Manager (Works),
Shri Amarnathji Shrine Board, J&K**

NIT No. & Date: _____

Name of work. _____

1. I _____ s/o _____
r/o _____ declared that;

I understand that, according to your conditions, bids must be supported by a Bid Securing Declaration.

2. I accept that I may be disqualified from any Contract with the Shri Amarnathji Shrine Board for a period of three years from the date of notification if am in a breach of any obligations (s) under the bid conditions, because I;

a). have withdrawn/ modified/amended, impaired or derogated from the tender, my bid during the period of bid validity specified in the Letter of Bid, or

b). having been notified of the acceptance of my Bid by the SASB during the period of bid validity of (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with Instructions to Bidders.

3. I understand this Bid- Securing Declaration shall cease/ expire to be valid if undersigned is not the successful Bidder, upon the earlier of (i) the receipt of your notification of the name of the successful Bidder; or (ii) sixty days Bid Validity Period.

Signature of person

(Signing the Bid Securing Declaration)

Dated on _____ day of _____

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Fabrication, Supply and Installation of Shelter Shed for Service Providers for issuance of Smart Cards to Yatris at Chandanwari Camp

S. No. 01

Estimated Amount = Rs. 2.80 lakh

| S. No. | Item of work | Quantity | Unit | Rate to be quoted by the bidder w.r.t. SSR 2020 (inclusive GST) | Amount (in Rs.) |
|---------------|--|-----------------|-------------|--|------------------------|
| 1 | Steel work in built up tubular round, square or rectangular section including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc. Complete. | | | | |
| | Mild Steel Tubular section | 870.70 | Kg | 168.80 | |
| | Mild Steel plates | 121.19 | kg | 92.85 | |
| | Nuts & Bolts (approx) to be paid as per actual | 50 | kg | RTQ | |
| 2 | Providing and fixing pre coated galvanized iron profile sheets(size, shape and pitch of corrugation as approved by Engineer in-Charge) 0.50mm +/- 0.0 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240 mpa steel grade5-7microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal /vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. PPGI sheet 0.50 mm | 106.28 | sqm | 626.25 | |

| | | | | | |
|---|---|------|----------------|--------|--|
| 3. | Providing and fixing pre coated galvanized steel sheet roofing accessories 0.50 mm (+/- 0.0 5 %) total coated thickness(TCT),Zinc coating 120 grams per sqm as per IS: 277, in 240 m pasteel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws or with polymer coated Jor L hooks, bolts and nuts and GI:Seam bolts, and nuts,GI plain and bitumen washers complete. | 6.00 | RM | 408.15 | |
| 4. | Providing and fixing of doors/window shutters. Area | 8.10 | M ² | RTQ | |
| 5. | Carriage of material through mechanical transport upto Chandanwari average 100 km lead. | 1.75 | MT | 925.39 | |
| Total cost of bid (to be quoted both in figures and words) | | | | | |

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pgm.

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Fabrication, Supply and Installation of Shelter Shed for Service Providers for issuance of Smart Cards to Yatrics at Sheshang Camp.

S. No. 02

Estimated Amount = Rs. 3.00 lakh

| S. No | Item of work | Quantity | Unit | Rate to be quoted by the bidder w.r.t. SSR 2020 (inclusive GST) | Amount (in Rs.) |
|--------------|---|-----------------|-------------|--|------------------------|
| 1 | Steel work in built up tubular round, square or rectangular section including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc. complete. | | | | |
| | Mild Steel Tubular section | 870.70 | Kg | 168.80 | |
| | Mild Steel plates | 121.19 | kg | 92.85 | |
| | Nuts & Bolts (approx) to be paid as per actual | 50 | kg | RTQ | |
| 2 | Providing and fixing pre coated galvanized iron profile sheets(size, shape and pitch of corrugation as approved by Engineer in-Charge) 0.50mm +/- 0.0 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240 mpa steel grade5-7microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal /vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. PPGI sheet 0.50 mm6.23 M ² | 106.28 | sqm | 626.25 | |
| 3. | Providing and fixing pre coated galvanized steel sheet roofing accessories 0.50 mm (+/- 0.0 5 %) total coated thickness(TCT),Zinc coating 120 grams per sqm as per IS: 277, in 240 m pasteel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws or with polymer coated Jor L hooks, bolts and nuts and GI:Seam bolts, and | 6.00 | RM | 408.15 | |

| | | | | | |
|--|---|------|--------|--------|--|
| | nuts,GI plain and bitumen washers complete: | | | | |
| 4. | Providing and fixing of doors/window shutters. | 6.00 | sqm | RTQ | |
| 5. | Carriage of material through mechanical transport upto Chandanwari average 100 km lead. | 1.75 | Mt | 925.39 | |
| 6. | Head load of material from Chandanwari to Sheshnag. | | | | |
| | a. Ponies . | 15 | Pony | RTQ | |
| | b. Potter | 20 | Porter | RTQ | |
| Total cost of bid (to be quoted both in figures and words | | | | | |

Note: Any typographical error found in rate list shall be read as per the Rates/ Specifications as provided in the revised SSR of 2020

DGM (W) Pgm.

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

A. Name of Work: Fabrication, supply and Installation Sign Boards at various Casmps and enroute for Pahalgam Axis (Complete job).

S. No. 03

Estimated Amount = Rs. 3.80 lakh

| S. No | Item of work | Quantity | Unit | Rate to be quoted by the bidder w.r.t. SSR 2020 (inclusive GST) | Amount (in Rs.) |
|--|---|-----------------|-------------|--|------------------------|
| 1 | Steel work in built up tubular round, square or rectangular section including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc. Complete. | 1399 | Kg | 168.80 | |
| 2 | Painting with synthetic paint of approved brand and manufacture to give an even two or more coats on new work | 130 | Sqm | 121.95 | |
| 3. | Writing an approved matter printing and pasting vinyl sheet with required adhesive of approved quality for both side of sign boards | 875 | Sft | RTQ | |
| 4. | Carriage of sign boards from manufacturing unit by mechanical Transport for 50 km's including loading and un loading. | 1.40 | MT | 514.39 | |
| 5. | Head load of sign boards from road head to upper sites including its installation etc. Complete job. | 25 | No | RTQ | |
| Total cost of bid (to be quoted both in figures and words | | | | | |

Note: Any typographical error found in rate list shall be read as per the Rates/ Specifications as provided in the revised SSR of 2020

DGM (W) Pgm.

Signature of the Bidder