

CIVIL WORKS ALONG PAHALGAM AXIS FOR YATRA 2016

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no. _____ dated _____)

#	CONTENT	PAGE(S)
1.	Notice Inviting Tender (NIT) for advertisement	2-4
2.	Eligibility criteria	5
3.	Documents establishing Bidder's eligibility	5
4.	Instructions to Bidders	6-8
5.	Scope of work	9
6.	Terms and Conditions of Contract	10-12
7.	Schedule – A (Technical Bid)	13-14
8.	Schedule – B (Financial Bid)	15



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov - April)

Tele: 0191-2555662, Telefax: 0191-2503399

NOTICE INVITING TENDER

TEMPORARY WORKS ALONG PAHALGAM AXIS FOR YATRA 2016

On behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** whose Registration Certificates are valid for Financial Year 2016-2017, for the execution of various Works mentioned below, at the Yatra Base Camps of Nunwan, Chandanwari, Sheshnag, and enroute Chandanwari to Poshpatriupto Dardkote. These bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **22.03.2016** up to 1400 hours.

(Rs in lac)

#	Name of work	Approx. Cost	Earnest Money Deposit (in Rs)	Class of Contractor	Time of Completion	Cost of bid document
1	Assembling of Toilet/ Baths (160 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets at Nunwan Camp after completion of Yatra.	3.20	6400/-	D	15 Days	Rs. 500/-
2	Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking at lower Camp Chandanwari after completion of Yatra.	1.90	3800/-	D	15 Days	Rs. 400/-
3	Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking at upper Camp Chandanwari after completion of Yatra.	1.90	3800/-	D	15 Days	Rs. 400/-
4	Assembling of Toilet/ Baths (75 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets enroute from Chandanwari to Km 5.5 including Pissu Top after completion of Yatra.	1.70	3400/-	D	15 Days	Rs. 300/-
5	Assembling of Toilet/ Baths (75 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets enroute from Km 5.5 to Nagakoti and Zojibal after completion of Yatra	1.74	3500/-	D	15 Days	Rs. 400/-
6	Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets in Block B at Sheshnag Camp after completion of Yatra.	1.95	3900/-	D	15 Days	Rs. 400/-
7	Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets in Block A & C at Sheshnag Camp after completion of Yatra.	1.95	3900/-	D	15 Days	Rs. 400/-
8	Assembling of Toilet/ Baths (112 nos.) including fixing of P.V.C. pipes, with minor repairs and	2.20	4400/-	D	15 Days	Rs. 500/-

	cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets at Sheshnag Camp after completion of Yatra.					
9	Assembling of Toilet/ Baths (50 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets enroute from Sheshnag to M.G. Top after completion of Yatra.	1.60	3200/-	D	15 Days	Rs. 400/-
10	Assembling of Toilet/ Baths (40 nos.) including fixing of P.V.C. pipes, with minor repairs and cleaning / excavation of earthen disposal pits including cost of its dismantling/ stacking of toilets enroute from M.G. Top to Dardkote after completion of Yatra.	1.50	3000/-	D	15 Days	Rs. 300/-
11	Assembling of (02 no.) sheds with attached kitchen and waiting shed for free Medical Camp including cost of its dismantling /stacking of material at Chandanwari Camp.	1.10	2200/-	D	15 Days	Rs. 300/-
12	Assembling of Prefabricated Huts (08 nos.) Adm. Block with minor repairs including cost of its dismantling /stacking of material after yatra at Sheshnag Camp.	4.16	8350/-	D	15 Days	Rs. 500/-
13	Assembling of Prefabricated Huts (08 nos.) in outsourced hut area with minor repairs at Sheshnag Camp including cost of its dismantling/stacking after conclusion of Yatra.	3.20	6400/-	D	15 Days	Rs. 500/-
14	Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths including cost of its dismantling /stacking of material after conclusion of Yatra at Chandanwari Camp.	0.80	1600/-	D	15 Days	Rs. 200/-
15	Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths including cost of its dismantling /stacking of material after conclusion of Yatra at Pissu Top.	0.70	1400/-	D	15 Days	Rs. 200/-
16	Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths including cost of its dismantling /stacking of material after conclusion of Yatra at Zojibal Camp.	0.80	1600/-	D	15 Days	Rs. 200/-
17	Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths and prefabricated huts including cost of its dismantling /stacking of material after conclusion of Yatra at Sheshnag Camp.	1.25	2500/-	D	15 Days	Rs. 300/-
18	Improvement/ Cleaning of Kacha drains including removal of vegetation and grassing on side of drains at Nunwan Camp.	0.50	1000/-	D	15 Days	Rs. 100/-
19	Painting / distempering to Administrative at Nunwan.	0.50	1000/-	D	15 Days	Rs.100/-
20	Construction of dry stone masonry (RRM) soak pits well type for 60 no. toilets behind Langars at Chandanwari Camp.	1.50	3000/-	D	15 Days	Rs. 300/-
21	Construction of dry stone masonry (RRM) soak pits well type for B- block toilets at Sheshnag Camp.	4.50	9000/-	D	15 Days	Rs. 500/-
22	Painting of toilet/ baths at Pissu Top and Zojibal (100 nos.).	1.50	3000/-	D	15 Days	Rs 300/-
23	Stage contract for snow clearance (with frost)	0.50	1000/-	D	10 Days	Rs.100/-

	from paths to toilets and toilet area at Wavbal & M.G. Top.					
24	Laying of sub distribution GI pipe line 15mm dia for providing water supply to toilet/ baths at Nunwan Pahalagam and dismantling/ storage of same at Nunwan Camp after conclusion of Yatra.	0.60	1200/-	D	10 days	Rs 100/-
25	Barbed wire fencing around Medical Camps from Chandanwari to Kelnar and dismantling/ storage of same at designated stores after conclusion of Yatra.	0.90	1800/-	D	20 days	Rs 200/-

2. Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from 9.30 AM to 5.00 PM, on any working day (Monday-Saturday) upto **19.03.2016** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
3. The Tender, duly completed, along with Earnest Money Deposit in the form of CDR in favour of Chief Accounts Officer, Shri Amarnathji Shrine Board payable at Jammu / Srinagar, must reach latest by **1400 hours on 22.03.2016** The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through courier/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reason.
4. The Technical bid shall be opened at **10. am on 24.03.2016** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the Agencies/ Bidders who may wish to be present on the occasion.
5. Not more than two Bid documents shall be issued to a single bidder.
6. In case the last date of receipt of Bid happens to be a holiday, the Bid shall be received on the next working day up to 1400 hours.
7. The successful bidder is bound to enter into an Agreement with General Manager (Works), SASB, within fifteen days from the date of the issue of Letter of Allotment of Work.

No: SASB/NIT/2016/848/11
Dated:29.02.2016

sd/-
General Manager (works)
Shri Amarnathji Shrine Board

II ELIGIBILITY CRITERIA

The Bidder must be a Contractor (registered with PWD J&K) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process:

- 2.1 The Bidder must possess at-least three year's experience (experience from Calendar Year 2011 to 2015 shall only be considered) in the field of Civil Construction in hilly region.
- 2.2 The Bidder should possess the experience of completion of at least three (03) works of similar nature to those mentioned in the DNIT in High altitude area of which at least one work should be of cost not less than fifty percentage of the amount of the tendered work with SASB .
- 2.3 The Bidder should have an average Annual Turnover of at least Rs. 3.00 lakh during at least one of the financial year from Financial Year 2012-13 to Financial Year 2014-15.
- 2.4 The Bidder should not have been blacklisted on an earlier occasion by any of the State Government Organizations, State Autonomous Bodies or Local Bodies/ Municipalities.

III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

- 3.1 Registration Certificate authenticating the same.
- 3.2 Certified copies of Annual Turnover from Bank
- 3.3 Certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works, for fulfilling the eligibility criteria.
- 3.4 Certified copy of PAN Card.
- 3.5 Certified copy of TIN Registration Certificate.
- 3.6 General Profile of the Bidder.
- 3.7 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect at any time, the Security Deposit shall stand forfeited.

IV. INSTRUCTIONS TO BIDDERS

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from 9.30 AM to 5.00 PM on any working day (Monday-Saturday) till 19.03.2016_ on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), J&K.
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed **“Technical Bid for the work of _____ Yatra 2016”** and **“Financial Bid for the work of _____ Yatra 2016”**. Both the sealed envelopes should be put in a third envelop, sealed and superscribed **“Tender for the work of _____ (Yatra 2016)” mentioning NIT No. & date.** The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The Bids, duly completed, along with an Earnest Money Deposit (EMD) of amount prescribed in the DNIT (against each work) only in form of CDR/ Demand Draft drawn in favour of FA/ Chief Accounts Officer/ Financial Advisor “Shri Amarnathji Shrine Board” payable at Jammu, must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered Post/ Courier to FA/ Chief Accounts Officer at the aforesaid address, so as to reach by **1400 hours 22.03.2016 latest.** Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by courier/ post. The technical Bids shall be opened at **10 a.m. on 24.03.2016** in the office of General Manager (Works), (at Jammu office) in presence of the Contractors/ Bidders.
In case last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day up to 1400 hours and shall be opened on the same day at 1500 hours.
- 4.4 Bids not accompanied by EMD shall be summarily rejected. The EMD and cost of DNIT should be placed inside the envelope containing the Technical Bid. The EMD shall be forfeited if the Bidder withdraws his bid during Bid Validity Period.
- 4.5 It would be deemed that by submitting the Bid, the Bidder has made complete examination of the DNIT, received all information requested from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each Bidder can submit only one Bid in response to a work in the DNIT. Any Bidder who submits more than one Bid shall be disqualified.

- 4.8 The Bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of Bid not substantially responsive to the DNIT in every respect will be at Bidder's risk and may result in the rejection of the bid.
- 4.9 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures. The corrections, if any, must be attested by the Bidder. Amounts shall be indicated in words as well as in figures. Where there is a difference between amount mentioned in figures and words, the amount quoted in words shall be taken as authentic.
- 4.10 The Bidder must satisfy himself that it fulfils all the prescribed eligibility conditions to avoid rejection of his Bid.
- 4.11 Each paper of the Bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.12 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The Chief Executive Officer may, at his discretion, extend the deadline for submission of Bids. Any Bid received after the last date/ time for submission of Bids, as stipulated above, shall not be considered and will be returned.
- 4.13 Clarifications, if any, may be sought by the Bidders so as to reach G M (Works) at least seven days before last date prescribed for submission of Bids. Except for any written clarification by Chief Executive Officer, SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on our webpage (www.shriamarnathjishrine.com) and NOT in newspaper(s). The Bidders should keep themselves updated on this account.
- 4.14 The Technical Bid shall be opened at **10 a.m. at 24.03.2016** in the office of General Manager (works) in the presence of the authorized representatives of the Bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.15 The Chief Executive Officer, SASB is not bound to accept the lowest or any Bid and may, at any time by notice in writing to the Bidders, terminate the tender proceedings without assigning any reason whatsoever.

- 4.16 The Bid should remain valid and open for acceptance for a period (i.e. Bid Validity Period) of 60 days from the last date prescribed for its receipt.
- 4.17 To facilitate evaluation of Bids, the GM (Works) may, at his sole discretion, seek clarification in writing from any Bidder regarding the Bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the Bid would be permitted by way of such clarification/ substantiation
- 4.18 The GM (W) may award the Contract to the Bidder whose Bid has been evaluated to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The GM (Works), SASB will send to such eligible Bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible Bidder in consideration of work/ services to be executed by the eligible Bidder as prescribed in the Contract.
- 4.19 The eligible Bidder will have to enter into an Agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the fifteen days of the issue of Letter of Intent.
- 4.20 Chief Executive Officer, SASB reserves the right to reject all or any Bid in whole, or in part, without assigning any reason. Any enquiry after the submission of tender will not be entertained.
- 4.21 Shri Amarnathji Shrine Board shall not be responsible for release of any CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the CDR's of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

V. SCOPE OF WORK

5.1 The Board and the Yatra:

- a) Shri Amarnathji Shrine Board (SASB) was established in 2001 under a statute with a view to providing better management of the Shri Amarnathji Yatra, up-gradation of facilities for the pilgrims, etc. Hon'ble Governor, J&K is the ex-officio Chairman of the Board.
- b) The pilgrimage (Yatra) is undertaken during the period specified in the months of July-August, through two different routes:
 - i) Pahalgam (7500 ft.)- Panjtarni (12729 ft.) - Holy Cave (13500 ft.). This route is 32 km long from Chandanwari to Holy Cave; and,
 - ii) Baltal (9500 ft.), Domel (9577 ft.)- Brarimarg (13120 ft.)- Holy Cave (13500 ft.). This route is 14 km long from Baltal to Holy Cave.

- c) During the Yatra, over 3.5 lakh persons (this number may be exceeded this year) undertake the pilgrimage to the Holy Cave Shrine of Shri Amarnathji, situated at an altitude of 13,500 feet, in District Anantnag, J&K. Baltal (near Sonamarg) and Nunwan (Pahalgam) are the two Base Camps where the Yatris congregate before embarking on the pilgrimage. Other Camps en-route are Sheshnag, Panjtarni and Holy Cave.

5.2 **Site Overview**

- a) The Camps are located at varying altitudes ranging from 7500 ft to 13500 ft above MSL.
- b) Temperature ranges from (-10⁰C to +25⁰C) during Yatra period.
- c) Baltal/ Domel are connected through a motorable road on Srinagar-Leh National Highway and is 110 km away from Srinagar. Pahalgam (Nunwan) is located at a distance of 90 km from Srinagar. It is located at a distance of 38 km from Khanabal which is at 250 km on Jammu - Srinagar National Highway.
- d) The journey to Holy Cave from Baltal involves trekking a distance of 14 km. From Chandanwari (Pahalgam route), the visit to the Holy Cave involves a trek of 32 km.
- e) Average weight that can be carried manually by a *pittoo* is 20 kg and by a pony is 60 kg.
- f) The Bidders will need to acquaint themselves of the nature and quantum of work involved, preferably by undertaking site visits of the Camp locations. Considering the present weather conditions, it would be possible for a bidder to visit Nunwan Camp (Pahalgam) any day, whereas other locations can be visited only after the snow melts.

VI. **TERMS AND CONDITIONS OF THE CONTRACT:**

- 6.1 The bidders are required to quote rate above/ below percentage on SSR of 2012 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. However, where it has been mentioned in column V that the 'Rate to be quoted', the bidder should quote rate in Rupees per unit. All rates/ percentages should be quoted in figures and words. The bidders are also to calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 6.2 Bids shall have to be submitted separately for each Work as indicated in the NIT.
- 6.3 The Security Deposit/ Earnest Money of the unsuccessful bidders shall be released immediately after the work is awarded to successful bidder.

Imbalanced bids :

- 6.4 All Bids (received from bidders) valuing less than 90 % and above 80% of the tendered cost shall be treated as imbalanced bids.
- 6.5 Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money) in the shape of CDR with his bid. This Additional Earnest Money should be equal to the difference between the bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.
- 6.6 Bids amounting to less than 80% of cost mentioned in the Notice Inviting Tender shall be out rightly rejected by GM (Works) SASB and not considered.
- 6.7 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- (i) First 3 days of delay Penalty 1% of contract value.
 - (ii) 4th day upto 10th day 2% of contract value
 - (iii) Beyond 10 days Earnest Money shall be forfeited and the contract shall automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm.
- 6.8 Not with standing Clause -6.7 above in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 6.9 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Work Allotment Letter.
- 6.10 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.
- 6.11 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.
- 6.12 The Contractor shall submit pictorial evidence (Photographs) of execution of work (post execution, during execution and after completion of work) with his claim.
- 6.13 The contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the

tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.

- 6.14 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 6.15 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the state or Central Government or Local Authority and any other labour law (including rules), regulation, byelaws that may be passed or notification that may be issued under any labour law in future either by the state or the Central Government or the local authority. The contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.
- 6.16 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the contract shall be the sole responsibility of the contractor.
- 6.17 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 6.18 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 6.19 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the law.
- 6.20 The Contractor is bound to draw an agreement with GM (Works), SASB within fifteen days from the date of issuance of Allotment Order.
- 6.21 GM (Works), SASB shall be at liberty to suspend the agreement due to any *Force Majeure* conditions such as Government regulations, **court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.**
- 6.22 All disputes and differences between the parties arising out and relating to the agreement to be signed between the GM (Works) SASB and the firm,

including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.

- 6.23 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the State of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 6.24 The rates quoted by the contractor shall be inclusive of all taxes e.g. (sales tax, service tax etc) that are in vogue.
- 6.25 If during the period of three months from the date of completion, the work - defects which have been caused by bad workmanship, use of inferior materials on the work, the contractors shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the cost thereof shall be recoverable from the security deposit of the contractor or from payments due to him.

VII Payment Clause:

- 7.1 Payment shall be made to the contractor for complete item of the work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 7.2 The payment to the bidder shall be made after successful completion of work within the stipulated time (with specification as per the allotment of contract and subsequent drawal of agreement) after satisfactory use/function of the work during complete Yatra Period.

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND EARNEST MONEY

#	Item	Details
1	Amount and details of payment towards the cost of DNIT	Rs. (in words):

		Receipt No./Cheque No:
		Date:
2	Amount and details of Earnest Money Deposit submitted	Rs. <u>(in words)</u> :
		DD No.
		Dated:
		In favour of
		Date of issue:
		Issuing Authority:

PART – B: BASIC DETAILS ABOUT THE AGENCY.

- i) Name and address of : Name: _____
the Agency. Address: _____

- Phone: _____
E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:
(please attach separate sheets where necessary):

1. Registration No. / Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of 'Documents Establishing Bidder's Eligibility'*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of 'Documents Establishing Bidder's Eligibility'*

#	Financial Year	Turnover (Rs.)
---	----------------	----------------

1	2011-12	
2	2012-13	
3	2013-14	
4	2014-15	

3. Documents to show that the contractor possesses relevant experience in past three years. The Bidder must furnish certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder's Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/No)

4. Certified copy of PAN Card - *Para 3.4 of 'Documents Establishing Bidder's Eligibility'*
5. Certified copy of TIN Registration Certificate – *Para 3.5 of 'Documents Establishing Bidder's Eligibility'*
6. General Profile of the Bidder – *Para 3.6 of 'Documents Establishing Bidder's Eligibility'*
7. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder's Eligibility*

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (160 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking at Nunwan Camp

S.No. as per NIT : 01

Adv.Cost: 3.20 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths and shelters: a. Nunwan: Blacksmith 1 st class Blacksmith 2 nd class	10 10	No. No.	Rs 450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets / baths at Nunwan. Mild Steel: i. Sliding door bolts (125mm) ii. Tower Bolt (150x10mm) iii. Oxidized mild steel Handles(125mm) iv. Nuts Bolts	24 40 40 30	No. No. No. Kg	RTQ Rs 35/- Rs.18/- Rs. 75/-		
3	Erection of toilets/baths and Rest Shelters at different location including head load of material from store to erection site. (before start of Yatra) i. Toilets/Baths ii. Sheds for Sanitary Post / Counter	160 04	No. No.	RTQ RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) =50x3m ii. PVC Bends (110mm) iii. PVC single equal Tee: (110x110x110mm) iv. PVC coupler (110mm)	210 100 25 60	RM No. No. No.	Rs. 160/- Rs. 114/- Rs. 200/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper one for six days	15 05	No. No.	Rs. 450/- Rs 300/-		
6	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. For 15 no new pits.	54.37	cum	Rs.240.45		
7	Supply of following items for covering the pits. i. Wooden joists : Budloo or fur wood ii. C.G.I Sheets (0.50mm) 20 sheets iii. Nails & Washers	0.42 240 25	Cum Kg Kg	Rs.30000/- Rs.60/- Rs 60/-		
8	Engagement of Labours for covering of pits: i. Carpenter ii. Mazdoor .	05 07	No. No.	Rs.500/- Rs.300/-		

9	Carriage of material from Anantnag to Nunwan including loading, unloading and head load all complete.	02	Trip	RTQ		
10	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' i. Mazdoor ii. Carpenters	160 05	No. No.	Rs.300/- Rs.500/-		
Part (B)						
11	Dismantling of toilets/ baths at erection sites including carriage of all material from erection site to store with proper stacking at store sites after conclusion of Yatra (complete job including head load)	160	No.	RTQ		
12	Retrieval of C.G.I. sheets from earthen disposal pits including carriage of all material from toilet installation site to store with proper stacking at store after conclusion of Yatra (complete job including head load).	65	pits	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking at lower Camp Chandanwari.

S.No. as per NIT : 02

Adv. Cost: 1.90 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths and shelters: a. Nunwan: Blacksmith 1 st class Blacksmith 2 nd class	05 05	No. No.	Rs 450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets / baths at Nunwan. Mild Steel: i. Sliding door bolts (125mm) ii. Tower Bolt (150x10mm) iii. Oxidized mild steel Handles(125mm) iv. Nuts Bolts	25 25 25 20	No. No. No. Kg	RTQ Rs 35/- Rs.18/- Rs. 75/-		
3	Erection of toilets/baths and Rest Shelters at different location including head load of material from store to erection site. (before start of Yatra) i. Toilets/Baths	100	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) =50x3m ii. PVC Bends (110mm) iii. PVC single equal Tee: (110x110x110mm) iv. PVC coupler (110mm)	210 75 12 38	RM No. No. No.	Rs. 160/- Rs. 114/- Rs. 200/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper one for six days	08 08	No. No.	Rs. 450/- Rs 300/-		
6	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. For 05 no. new pits.	18.12	cum	Rs.240.45		
7	Supply of following items for covering the pits. i. Wooden joists : Budloo or fur wood ii. C.G.I Sheets (0.50mm) 10 sheets iii. Nails & Washers	0.21 120 13	Cum Kg Kg	Rs.30000/- Rs.60/- Rs 60/-		
8	Engagement of Labours for covering of pits: i. Carpenter ii. Mazdoor .	02 05	No. No.	Rs.500/- Rs.300/-		

9	Carriage of material from Anantnag to Chandanwari including loading, unloading and head load all complete.	02	Trip	RTQ		
10	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' i. Mazdoor ii. Carpenters	54 03	No. No.	Rs.300/- Rs.500/-		
Part (B)						
11	Dismantling of toilets/ baths from erection sites with retrieval of CGI sheets from earthen pits including carriage of all material from erection sites both mechanical and head load to store with proper stacking after conclusion of Yatra	100	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking at upper Camp Chandanwari.

S.No. as per NIT : 03

Adv.Cost: 1.90 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths and shelters: a. Nunwan: Blacksmith 1 st class Blacksmith 2 nd class	05 05	No. No.	Rs 450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets / baths at Nunwan. Mild Steel: i. Sliding door bolts (125mm) ii. Tower Bolt (150x10mm) iii. Oxidized mild steel Handles(125mm) iv. Nuts Bolts	25 25 25 20	No. No. No. Kg	RTQ Rs 35/- Rs.18/- Rs. 75/-		
3	Erection of toilets/baths and Rest Shelters at different location including head load of material from store to erection site. (before start of Yatra) i. Toilets/Baths	100	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) =50x3m ii. PVC Bends (110mm) iii. PVC single equal Tee: (110x110x110mm) iv. PVC coupler (110mm)	210 75 12 38	RM No. No. No.	Rs. 160/- Rs. 114/- Rs. 200/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper one for six days	08 08	No. No.	Rs. 450/- Rs 300/-		
6	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. For 05 no. new pits.	18.12	cum	Rs.240.45		
7	Supply of following items for covering the pits. i. Wooden joists : Budloo or fur wood ii. C.G.I Sheets (0.50mm) 10 sheets iii. Nails & Washers	0.21 120 13	Cum Kg Kg	Rs.30000/- Rs.60/- Rs 60/-		
8	Engagement of Labours for covering of pits: i. Carpenter	02	No.	Rs.500/-		

	ii. Mazdoor .	05	No.	Rs.300/-		
9	Carriage of material from Anantnag to Chandanwari including loading, unloading and head load all complete.	02	Trip	RTQ		
10	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4'					
	i. Mazdoor	54	No.	Rs.300/-		
	ii. Carpenters	03	No.	Rs.500/-		
Part (B)						
11	Dismantling of toilets/ baths from erection sites with retrieval of CGI sheets from earthen pits including carriage of all material from erection sites both mechanical and head load to store with proper stacking after conclusion of Yatra	100	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (75 nos.) including fixing of P.V.C. pipes and cleaning/ excavation of earthen disposal pits and its dismantling/ stacking enroute from Chandanwari to KM 5.5 including Pissu Top.

S.No. as per NIT : 04

Adv.Cost: 1.70 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repairs to toilets/baths at Pissutop: Blacksmith 1 st class Blacksmith 2 nd class	04 04	No. No.	Rs.450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets/baths Mild Steel: i. Sliding door bolts (125mm long ii. Tower Bolt (150x10mm) iii. Oxidized mild steel Handles(125mm) iv. Nuts Bolts	10 10 10 10	No. No. No. Kg	RTQ Rs.35/- Rs.18/- Rs.75/-		
3	Erection of toilets/baths at different camps (enroute, PissuTop, up to KM 5.5) including head load of all material from dumping site to the site of erection (complete Job). Toilets/Baths.	75	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mm x3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	75 60 30	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i Fitter (Grade 1) ii Helper	06 03	No. No.	Rs.450/- Rs 300/-		
6	Head load of PVC Pipes and fitting items from Chandanwari to pissutop. i. MS fittings ii. Pittoos	20 12	Kg No.	RTQ RTQ		
7	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. For 10 no new pits.	18.12	cum	Rs.240.45/-		
8	Supply of following items for covering the pits. i. Wooden joists : ii. C.G.I Sheets iii. Nails & Washers : 25 kgs	0.42 240 25	Cum Kg Kg	Rs.30000/- Rs.60/- Rs.60/-		

9	Engagement of Labours for covering of pits: i. Carpenter ii. Mazdoor.	03 02	No. No.	Rs.500/- Rs.300/-		
10	Carriage of material from Anantnag to Chandanwari by M.T. (LMV)	02	Trip	RTQ		
11	Head load of material from Chandanwari to Pissutop. i. CGI sheets ii. Pittoos	240 05	Kg No.	RTQ RTQ		
12	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' i. Mazdoor ii. Carpenters	28 04	No. No.	Rs.300/- Rs.500/-		
Part (B)						
13	Dismantling of toilets/ baths from erection sites with retrieval of CGI sheets from earthen pits including carriage of all material from erection sites both mechanical and head load to store with proper stacking after conclusion of Yatra.	75	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Pgm.

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (75 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking enroute from KM 5.5 to Naga Koti including Zojibal.

S.No. as per NIT : 05

Adv.Cost: 1.74 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repairs to toilets/baths at Zojibal camp : Blacksmith 1 st class Blacksmith 2 nd class	04 04	No. No.	Rs.450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets/baths Mild Steel: i. Sliding door bolts (125mm long ii. Tower Bolt (150x10mm) iii. Oxidized mild steel Handles(125mm) iv. Nuts Bolts	10 10 10 10	No. No. No. Kg	RTQ Rs.35/- Rs.18/- Rs.75/-		
3	Erection of toilets/baths at different camps (from KM 5.5 to Zojibal, and Nagakoti) including head load of all material from dumping site to the site of erection (complete Job). Toilets/Baths.	75	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mm x3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	60 60 30	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i Fitter (Grade 1) ii Helper	06 03	No. No.	Rs.450/- Rs 300/-		
6	Head load of PVC Pipes and fitting items from Chandanwari to pissu top. i. MS fittings ii. Pittoos	20 12	Kg No.	RTQ RTQ		
7	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. For 10 no new pits.	18.12	cum	Rs.240.45/-		
8	Supply of following items for covering the pits. i. Wooden joists : ii. C.G.I Sheets iii. Nails & Washers : 25 kgs	0.42 240 25	Cum Kg Kg	Rs.30000/- Rs.60/- Rs.60/-		
9	Engagement of Labours for covering of pits: i. Carpenter ii. Mazdoor.	03 02	No. No.	Rs.500/- Rs.300/-		

10	Carriage of material from Anantnag to Chandanwari by M.T. (LMV)	02	Trip	RTQ		
11	Head load of material from Chandanwari to Pissutop. i. CGI sheets ii. Pittoos	240 05	Kg No.	RTQ RTQ		
12	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' i. Mazdoor ii. Carpenters	28 04	No. No.	Rs.300/- Rs.500/-		
Part (B)						
13	Dismantling of toilets/ baths from erection sites with retrieval of CGI sheets from earthen pits including carriage of all material from erection sites both mechanical and head load to store with proper stacking after conclusion of Yatra.	75	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Pgm.

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking in Block B at Sheshnag Camp.

S.No. as per NIT : 06

Adv.Cost: 1.95 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths: Blacksmith 1 st class Blacksmith 2 nd class	05 05	No. No.	Rs.450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets/baths at Sheshnag Mild Steel: i. Sliding door bolts (125mm long) ii. Tower Bolt (150x10mm) iii. Oxidized M. S. I Handles(125mm) iv. Nuts Bolts	15 20 20 25	No. No. No. Kg	RTQ Rs.35/- Rs.18/- Rs.75/-		
3	Erection of toilets/baths at different locations including head load of all material from dumping site to the site of erection (complete Job). i. Toilets / Baths.	100	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	90 90 45	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper	10 05	No. No.	Rs.450/- Rs 300/-		
6	Carriage of material from Anantnag to Chandanwari by M.T. including loading, unloading complete.	01	Trip	RTQ		
7	Head load of fitting items & PVC Pipes and fittings from Chandanwari to Sheshnag i.M.S. fittings ii. PVD pipes & fittings	30 08	Kg No.	RTQ RTQ		
8	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil.	36.25	Cum	Rs.240.45/-		
9	Engagement of labours for covering the pits With available material including cutting & fixing					

	the available steel members of old Huts. i. Blacksmith = ii. Helper	05 10	No. No.	Rs.450/- Rs.300/-		
10	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' Mazdoor	50	No.	Rs.300/-		
Part (B)						
11	Dismantling of toilets/ baths at erection sites including carriage of all material from erection site to store with proper stacking at store sites after conclusion of Yatra (complete job including head load)	100	No.	RTQ		
12	Retrieval of C.G.I. sheets from earthen pits with head load of material from works site to store including stacking of material etc complete.	30	pits	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (100 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking in Block A & C at Sheshnag Camp.

S.No. as per NIT : 07

Adv.Cost: 1.95 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths: Blacksmith 1 st class Blacksmith 2 nd class	05 05	No. No.	Rs.450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets/baths at Sheshnag Mild Steel: i. Sliding door bolts (125mm long) ii. Tower Bolt (150x10mm) iii. Oxidized M. S. I Handles(125mm) iv. Nuts Bolts	15 20 20 25	No. No. No. Kg	RTQ Rs.35/- Rs.18/- Rs.75/-		
3	Erection of toilets/baths at different locations including head load of all material from dumping site to the site of erection (complete Job). i. Toilets / Baths.	100	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	90 90 45	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper	10 05	No. No.	Rs.450/- Rs 300/-		
6	Carriage of material from Anantnag to Chandanwari by M.T. including loading, unloading complete.	01	Trip	RTQ		
7	Head load of MS fitting items & PVC Pipes and fittings from Chandanwari to Sheshnag i.M.S. fittings ii. PVC pipes & fittings	30 08	Kg No.	RTQ RTQ		
8	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil.	36.25	Cum	Rs.240.45/-		
9	Engagement of labours for covering the pits With available material including cutting & fixing the available steel members of old Huts.					

	i. Blacksmith = ii. Helper	05 10	No. No.	Rs.450/- Rs.300/-		
10	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' Mazdoor	50	No.	Rs.300/-		
Part (B)						
11	Dismantling of toilets/ baths at erection sites including carriage of all material from erection site to store with proper stacking at store sites after conclusion of Yatra (complete job including head load)	100	No.	RTQ		
12	Retrieval of C.G.I. sheets from earthen pits with head load of material from works site to store including stacking of material etc complete.	30	pits	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Pgm.

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (112 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking at Sheshnag Camp.

S.No. as per NIT : 08

Adv.Cost: 2.20 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths: Blacksmith 1 st class Blacksmith 2 nd class	05 05	No. No.	Rs.450/- Rs.400/-		
2	Supplying of various fitting items for Repairs to doors of toilets/baths at Sheshnag Mild Steel: i. Sliding door bolts (125mm long) ii. Tower Bolt (150x10mm) iii. Oxidized M. S. I Handles(125mm) iv. Nuts Bolts	18 20 20 25	No. No. No. Kg	RTQ Rs.35/- Rs.18/- Rs.75/-		
3	Erection of toilets/baths at different locations including head load of all material from dumping site to the site of erection (complete Job). i. Toilets / Baths.	112	No.	RTQ		
4	Supply of P.V.C items for disposal of toilets. i. PVC pipes (110mmx3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	90 90 45	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper	10 05	No. No.	Rs.450/- Rs 300/-		
6	Carriage of material from Anantnag to Chandanwari by M.T. including loading, unloading complete.	01	Trip	RTQ		
7	Head load of MS fitting items & PVC Pipes and fittings from Chandanwari to Sheshnag i.M.S. fittings ii. PVC pipes & fittings	30 08	Kg No.	RTQ RTQ		
8	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil.	36.25	Cum	Rs.240.45/-		
9	Engagement of labours for covering the pits With available material including cutting & fixing the available steel members of old Huts. i. Blacksmith =	05	No.	Rs.450/-		

	ii. Helper	10	No.	Rs.300/-		
10	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the pit with CGI sheets with earthen cushion and head load of all material from store to works site for pits size 8'x4'x4' Mazdoor	50	No.	Rs.300/-		
Part (B)						
11	Dismantling of toilets/ baths at erection sites including carriage of all material from erection site to store with proper stacking at store sites after conclusion of Yatra (complete job including head load)	112	No.	RTQ		
12	Retrieval of C.G.I. sheets from earthen pits with head load of material from works site to store including stacking of material etc complete.	30	pits	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (50 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking enroute from Sheshnag to M.G. Top.

S.No. as per NIT : 09

Adv.Cost: 1.60 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths: Blacksmith 1 st class Blacksmith 2 nd class	06 06	No. No.	Rs.450/- Rs.400/-		
2	Supplying of nuts & bolts for erection of toilets.	25	Kg	Rs.75/-		
3	Erection of toilets/baths at different Camps (Wavbal and M.G. Top) including enroute where ever required with head load of I material from dumping site to the site of erection.	50	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	40 50 25	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper one for 05 days	06 03	No. No.	Rs.450/- Rs 300/-		
6	Carriage of material from Anantnag to Chandanwari by M.T. including loading, unloading complete.	01	Trip	RTQ		
7	Head load of MS fitting items & PVC Pipes and fittings from Chandanwari to Sheshnag i.M.S. fittings ii. PVC pipes & fittings	10 05	Kg No.	RTQ RTQ		
8	Head load of toilets and Baths from wavbal store to MG Top (12 No. Toilets and 02 No. Baths)	1916	Kg	RTQ		
9	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. (5 pits)	18.12	Cum	Rs.240.45/-		
9	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the all pits with CGI sheets with earthen cushion and head load of all material from store to works site for pits size8'x4'x4' Mazdoor	64	No.	Rs.300/-		

Part (B)						
11	Dismantling of toilets/ baths at erection sites including carriage of all material with proper stacking at store sites after conclusion of Yatra	50	No.	RTQ		
12	Carriage of Toilets Baths from MG Top to Wavbal and stacking of material	1916	Kg	RTQ		
13	Retrieval of C.G.I. sheets from earthen pits with head load of material from MG Top to Wavbal store including stacking of material etc complete.	15	pits	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (48 nos.) including fixing of P.V.C. pipes with minor repairs and cleaning / excavation of earthen disposal pits and its dismantling/ stacking enroute from M.G Top to Dard-kote

S.No. as per NIT : 10

Adv.Cost: 1.50 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
Part (A)						
1	Engagement of labour for Repair toilets/baths: Blacksmith 1 st class Blacksmith 2 nd class	06 06	No. No.	Rs.450/- Rs.400/-		
2	Supplying of nuts & bolts for erection of toilets.	10	Kg	Rs.75/-		
3	Erection of toilets/baths at different Camps (Poshpathri, Kelnar upto Dardkote) including enroute where ever required with head load of I material from dumping site to the site of erection.	48	No.	RTQ		
4	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) ii. PVC Bends (110mm) iii. PVC coupler (110mm)	40 50 25	Rm No. No.	Rs. 160/- Rs. 114/- Rs. 85/-		
5	Engagement of labours for fixing of P.V.C pipes to toilets and baths. i. Fitter(Grade 1) ii. Helper one for 05 days	03 03	No. No.	Rs.450/- Rs 300/-		
6	Carriage of material from Anantnag to Chandanwari by M.T. including loading, unloading complete.	01	Trip	RTQ		
7	Head load of MS fitting items & PVC Pipes and fittings from Chandanwari to Sheshnag i.M.S. fittings ii. PVC pipes & fittings	10 05	Kg No.	RTQ RTQ		
8	Head load of toilets and Baths from wavbal store to MG Top (12 No. Toilets and 02 No. Baths)	2192	Kg	RTQ		
9	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. (5 pits)	18.12	Cum	Rs.240.45/-		
9	Cleansing of the existing disposal pit manually and disposing the decomposed debris at appropriate site including covering the all pits with CGI sheets with earthen cushion and head load of all material from store to works site for pits size8'x4'x4'					

	Mazdoor	84	No.	Rs.300/-		
Part (B)						
11	Dismantling of toilets/ baths at erection sites including carriage of all material with proper stacking at store sites after conclusion of Yatra	48	No.	RTQ		
12	Carriage of Toilets Baths from MG Top to Wavbal and stacking of material	2192	Kg	RTQ		
13	Retrieval of C.G.I. sheets from earthen pits with head load of material from MG Top to Wavbal store including stacking of material etc complete.	25	pits	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of (02 no.) sheds with attached kitchen and waiting shed for free Medical Camp at Chandanwari..

S.No. as per NIT : 11

Adv.Cost: 1.10 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing roofing and sides with CGI Sheets with J or L hooks, bitumen and limpet washers complete . i. Available sheets ii. New sheets 0.63mm thick	237.51 26.39	Sqm sqm	Rs.219.80/- Rs.757/-		
2	Fixing of Door/Window at appropriate position Material available at site i. Blacksmith 1st class ii. Black smith(2 nd class) iii. carpenter	04 04 04	No. No. No.	Rs.450/- Rs.400/- Rs.500/-		
3	Hire charges of welding set with gen- set including welding rods, P.O.L with all carriages.	03	days	RTQ		
4	Carriage of material from SASB store to works site by M.T. including loading and unloading of material	02	Trip	RTQ		
5	Carriage of material from Anantnag to Chandanwari works site by M.T. including loading and unloading of material	01	Trip	RTQ		
6	Dismantling of sheds after conclusion of yatra with all leads, lifts & stacking of material at store.	263.90	sqm	Rs.62.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Prefabricated Huts (08 nos.) Adm. Block with minor repairs including dismantling and stacking of material after Yatra at Sheshnag Camp

S.No. as per NIT : 12

Adv.Cost: 4.16 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Engagement of labors for repairs the steel structure of 08 No. huts. i. Blacksmith ii. Helpers	64 64	No. No.	Rs 450/- Rs 300/-		
2	Fixing of PUF Panels in MS channels of huts including tightening leveling and fixed up at appropriate position for side walls and roofing etc with all needs and lifts from store to erection site complete job.	8928	Sft	RTQ.		
3	Providing Wood work for ceiling and partition with available material at site with head load of material from store to hut site.	0.80	cum	Rs 12755.75/--		
4	Fixing of three layer particle boards 6mm thick available at site for partition and ceiling of huts	4096.00	Sft	RTQ		
5	Painting with synthetic enamel paint of approved brand and manufacture two or more coats with two or more coats on old work with all shades to give an even shade.	841.6	Sqm	Rs 45.60/-		
6	Fixing of Sanitary items to attached toilets / baths to make ready for use including internal water supply complete job.	08	No.	RTQ		
7	Dismantling of huts and stacking of material at SASB store with head load of material all complete for 08 No. huts	08	Huts	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Prefabricated Huts (08 nos.) outsourced hut area with minor repairs at Sheshnag Camp including dismantling and stacking of material after Yatra.

S.No. as per NIT : 13

Adv.Cost: 3.20 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Engagement of labours for repairs the steel structure of damaged old Hut frame including fabrication where ever required etc. for 08 No. Huts. i. Blacksmith ii. Helpers iii. Hire charges of welding set, Genset with POL and rods etc.	06 08 08	No. No. Days	Rs.450/- Rs.300/- RTQ		
2	Fixing of PUF Panels with aluminum channels with cutting and straightening etc. Complete including fixing of doors and windows at appropriate position excluding the cost for wood work with head load of material from store to works site	5472	Sft	RTQ		
3	Fixing of CGI sheets on roofing of huts fixed with J and L hooks bitumen and limpet washers etc complete	267.6	Sqm	Rs.219.80/-		
4	Fixing of sanitary items for attached toilets /baths including internal G.I. fittings for providing of water supply complete job. for 08 No. huts	08	No.	RTQ		
5	Providing wood work for fixing of doors frames window frames etc = 2.83 cft or 0.08 cum (available material)	0.64	Cum	Rs.12755.75/-		
6	Dismantling of huts and stacking of material at SASB store with head load of material all complete for 08 No. huts	08	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths including dismantling and stacking of material after Yatra at Chandanwari Camp.

S.No. as per NIT : 14

Adv. Cost = 0.80 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Laying and fitting of G.I pipes complete excluding cost of pipes and earth work. 15 mm Toilets/Baths and installation of water coolers and standing posts etc. i. New pipe ii. Available pipe	90 360	Rm Rm	Rs.115/- Rs.12.80/-		
2	P/F of G.I unions complete in G.I pipes including cutting and threading the pipe and matching long screws' etc 15 mm & N.B	36	No.	Rs.174.40/-		
3	P/F brass P/F brass bib cock & stop cock of approved brand quality. 15mm dia i. Bib cock ii. Stopcock	100 25	No. No.	Rs.124.05/- Rs. 124.05/-		
4	Supply of G.I fittings for available proper 15 mm i. Socket. ii. Elbow iii. Tee iv. Nipple	50 100 60 64	No. No. No. No.	Rs.18/- Rs. 26/- Rs. 38/- Rs. 20/-		
5	Installation of water cooler tanks with water purifiers at appropriate places connecting with water supply pipe line etc complete job. i. Plumbers no. ii. Helper	04 02	No. No	Rs.450/- Rs. 300/-		
6	Carriage of material by mech. transport from Anantnag to Chandanwari.of LMV	01	Trip	RTQ		
7	Maintenance of water supply during Yatra period. i. Plumber for two months ii. Helper for two months	01 01	No. No.	RTQ RTQ.		
8	Dismantling of pipe line after conclusion of yatra.	450	Rm	Rs.12.80/-		
9	Head load of pipes from installation site upto store with stacking of material etc. complete	08	No.	Rs.300/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths including dismantling and stacking of material after Yatra at Pissu Top.

S.No. as per NIT : 15

Adv. Cost = 0.70 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing and fixing G.I. Pipes complete with G.I fittings complete excluding trenching and rifling complete. (15 mm dia) medium .	272	Rm	Rs.115/-		
2	P/F of G.I unions complete in G.I pipes including cutting and threading the pipe and matching long screws' etc	12	No.	Rs.174.40/-		
3	P/F of bib cock & stop cock of approved brand and quality. 15mm dia (N.b) i. Bib cock ii. Stop cock	70 10	No. No.	Rs.124.05/- Rs.124.05/-		
4	Carriage of material by mech. transport from Anantnag to Chandanwari.	01	Trip	RTQ		
5	Head load of pipes from Chandanwari upto Pissu Top for GI Pipes & GI Fittings by pittoos i. Pittoos	24	No.	RTQ		
6	Dismantling of pipe line after conclusion of yatra from installation sites .	272	Rm	Rs. 12.80/-		
7	Head load of pipes beyond 50 mtr from erection site upto store including stacking of material at store complete.	06	No.	Rs.300/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths including dismantling and stacking of material after Yatra at Zojibal Camp.

S.No. as per NIT : 16

Adv. Cost = 0.80 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing and fixing G.I. Pipes complete with G.I fittings complete excluding trenching and rifling complete. (15 mm dia) medium .	288	Rm	Rs.115/-		
2	P/F of G.I unions complete in G.I pipes including cutting and threading the pipe and matching long screws' etc	15	No.	Rs.174.40/-		
3	P/F of bib cock & stop cock of approved brand and quality. 15mm dia (N.b) i. Bib cock ii. Stop cock	64 10	No. No.	Rs.124.05/- Rs.124.05/-		
4	Carriage of material by mech. transport from Anantnag to Chandanwari.	01	Trip	RTQ		
5	Head load of pipes from Chandanwari upto Pissu Top for GI Pipes & GI Fittings by pittoos i. Pittoos	26	No.	RTQ		
6	Dismantling of pipe line after conclusion of yatra from installation sites .	288	Rm	Rs. 12.80/-		
7	Head load of pipes beyond 50 mtr from erection site upto store including stacking of material at store complete.	04	No.	Rs.300/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths and prefabricated huts including dismantling and stacking of material after Yatra at Sheshnag Camp.

S.No. as per NIT : 17

Adv. Cost = 1.25 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Laying and fitting of G I pipes complete Excluding Cost of pipes and earth work 15mm N. Bore. Medium i. Available GI pipe ii. New pipe required	995.46 175.67	Rm Rm	Rs.12.80/- Rs.115/-		
2	Supply of various fitting items for repairs the pipe line of required dia(15 mm) medium i. 15mm GI Elbow. ii. 15mm GI Tee iii. 15mm GI socket	160 72 72	No. No. No.	Rs.26/- Rs.38/- Rs.18/-		
3	Providing and fixing of GI unions in GI pipes including cutting and threading etc.15 mm dia. a) New GI Unions required b) Available GI Unions	30 25	No. No	Rs.106.80/- Rs.174.80/-		
4	Providing and fixing of Brass Stop cock of approved make 15mm i. Brass Stop cock ii. Brass Bib cock	20 100	No. No	Rs.124.05/- Rs.124.05/-		
5	Carriage of Material by M. T. From Anantnag to Chandanwari- of LMV	01	Trip	RTQ		
6	Head load of Material from Chandanwari to Sheshnag camp by pithoos i. Pithoos	18	Pithos	RTQ		
7	Dismantling of GI pipe line after conclusion of Yatra with head load of material up to 50m and stacking of material, Qty vide item No. 1	1171.14	Rm	Rs.12.80/-		
8	Head load of material beyond 50m up to 750m Avg. by engaging Labors	10	No.	Rs. 300/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Improvement/ Cleaning of Kacha drains including removal of vegetation and grassing on side of drains at Nunwan Camp.

S.No. as per NIT : 18

Adv. Cost : 0.50 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in. All kinds of soil. For digging of Kacha drains inside camp area.	156.30	cum	Rs.240.45/-		
2	Engagement of labors for cleaning of mallaba from existing drains including of removal of grassing from the side of drains with disposal of mallaba and rubbish at appropriate place	32	No.	Rs.300/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting / distempering to Administrative Huts at Nunwan.

S.No. as per NIT : 19

Adv. Cost : 0.50 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Distempering with 1 st class acrylic distemper (Ready mixed) of approved manufacture and colour complete one or two coats on old work. (a) For Administrative huts 07 nos.	1457.95	Sqm	Rs.28.16/-		
2	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old work: For door and window sills, borders of huts etc	150	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of dry stone masonry (RRM) soak pits well type for 60 no. toilets behind Langars at Chandanwari Camp.

S.No. as per NIT : 20

Adv. Cost : 1.50 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavating by manual means over areas for foundations, drains, pipes cables etc and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth, upto 1.5 mtr including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	126	Cum	Rs.240.45/-		
2	Dry random rubble Masonry with hard stone in foundation and plinth by using quarry stone with bond stone .	47.16	Cum	Rs.1454.50/-		
3	Supply and fixing of CGI sheets and wooden struts etc for covering of the pit i. CGI sheets ii. Wooden struts iii. Labour for covering 16 Nos.	192 5.83 16	Sft Kg No.	Rs.60/- Rs.650/- Rs.300/-		
4	Carriage of material by mechanical transport from Anantnag to Chandanwari including loading and unloading of material i. CGI sheets and wooden struts ii. Quarry stone for donipowa to Chandanwari average distance 65 kms	01 47.16	Trip Cum	RTQ Rs. 449.91/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of dry stone masonry (RRM) soak pits well type for B- block toilets at Sheshnag Camp.

S.No. as per NIT : 21

Adv. Cost : 4.50 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavating by manual means over areas for foundations, drains, pipes cables etc and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth, upto 1.5 mtr including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	115.50	Cum	Rs.240.45/-		
2	Dry random rubble Masonry with hard stone in foundation and plinth by using quarry stone with bond stone .	43.56	Cum	Rs.1454.50/-		
3	Supply and fixing of CGI sheets upon steel members available at site for covering of pits with earth cushion etc complete i. CGI sheets 0.63 mm thick (16 sheets) ii. Labour for covering the pit and correction steel members for covering.	192 15	Kg No.	Rs.60/- Rs.300/-		
4	Carriage of material by mechanical transport from Anantnag to Chandanwari including loading and unloading of material	01	Trip	RTQ		
5	Head load of material from Chandanwari to Sheshnag for CGI sheets and had load of stones from nearest source lower camp Sheshnag average distance 1.5 km i. CGI sheets from Chandanwari to Sheshnag . ii. Quarry stone	192 1538.10	Kg Cft	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting of toilet/ baths at Pissu Top and Zojibal (100 nos.)

S.No. as per NIT : 22

Adv. Cost : 1.50 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc (complete)	10.38	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works..	20.76	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work (one or more coat)	20.76	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Stage contract for snow clearance (with frost) from paths to toilets and toilet area at Wavbal & M.G. Top.

S.No. 23

Adv. Cost : 0.50 Lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)/Cum	Amount
I	II	III	IV	V	VI	VII
1	Clearing of snow with frost and Gulla cutting in compressed snow from paths approach to toilets area, for erection of toilets baths at Wavbal and M.G.Top.	To be identified at site	Cum	Rs.2.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of sub distribution G. I. pipe line 15 mm dia for providing water supply to Toilets/ Baths at Nunwan Camp and dismantling/storage of same as at Nunwan Camp after conclusion of Yatra.

S.No. as per NIT : 24

Adv. Cost = 0.60 Lac

S. No.	Particulars of Items	Unit	Rate to be quoted by the Bidder
I	II	III	IV
1	Laying and fitting of G.I pipes complete excluding cost of pipes and earth work.15 mm Toilets/Baths and installation of water coolers and standing posts etc. i. New pipe 15 mm dia (medium)	Rm	
	ii. Available pipe 15 mm dia (medium)	Rm	
2	P/F of G.I unions complete in G.I pipes including cutting and threading the pipe and matching long screws' etc 15 mm & N. Bore	No.	
3	P/F brass P/F brass bib cock & stop cock of approved brand quality. 15mm dia i. Bib cock .	No.	
	ii. Stopcock	No.	
4	Supply of G.I fittings for available proper 15 mm i. Socket.	No.	
	ii. Elbow	No.	
	iii. Tee	No.	
	iv. Nipple	No.	
5	Installation of water cooler tanks with water purifiers at appropriate places connecting with water supply pipe line etc complete job. i. Plumbers no.	No.	
	ii. Helper	No.	
6	Maintenance of water supply during Yatra period. i. Plumber for two months	No.	
	ii. Helper for two months	No.	
7	Dismantling of pipe line after conclusion of yatra its carriage and proper storage at Nunwan Camp.	Rm	

Note: Any

topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (W) Pgm.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of barbed wire fencing around the Medical Camps from Chandawari to Kelnar and dismantling/ storage of same at designated stores after conclusion of Yatra.

S.No. 25

Adv.Cost: 0.90 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.50cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	250	No.	Rs 24.90/-		
2	1.8m high fencing with 2.5 m Sal bali posts, 30cms girth (min) placed every 2.5 m apart embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 6 horizontal lines and two diagonals of barbed wire 9.38 Kg per 100m (Min) between two posts filled and fixed with G.I staples driven into the posts, including two coats of coal tarring of ballies complete. (Cost of posts, struts, earthwork and concrete to be paid for separately). With G.I barbed wire.	487	Rm	Rs.39.94/-		
3	Carriage of material from SASB store to site of work. i. Labour	30	Day	Rs.300/-		
4	Dismantling of barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 meters lead.	487	Kg.	Rs. 12.30/-		
5	Dismantling of wooden ballies in parts and struts including stacks within 50 meters lead	533	Rm	Rs. 7.05/-		
6	Engagement of labour for additional head load beyond 50 meters upto storage site i.e from Km point 2 to Chandanwari, Km 5.5 to Pissu Top M.G. Top to Wavbal & Kelnard to Poshalthri (complete job) i. Labour	44	Day	Rs.300/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 2012**.

DGM (W) Pahalgam

Signature of the Bidder

