

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2017

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no. _____ dated _____)

S. NO.	CONTENT	PAGE (S)
1	Notice Inviting Tender (NIT) for advertisement	2-4
2	Eligibility criteria	5
3	Documents establishing Bidder's eligibility	5
4	Instructions to Bidders	6-8
5	Scope of work	8-9
6	Terms and Conditions of Contract	9-12
7	Schedule – A (Technical Bid)	13-14
8	Schedule – B (Financial Bid)	15



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov-April)

Tele: 0191-2555662. Telefax: 0191-2503399

NOTICE INVITING TENDER

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2017

On behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** whose Registration Certificates are valid for Financial Year 2017 - 2018, for the execution of various Works mentioned below, at the Baltal, enroute and Holy Cave. These bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **28.02.2017** up to 1400 hours.

S. No.	Name of work	Approx. Cost (in Lac)	Earnest Money Deposit (in Rs)	Class of Contractor	Time of Completion	Cost of bid document
1	Mounting of water storage tank on existing stages, water supply fitting, fixing of 02 nos. motor pump and fixing of chain link fencing and minor repair to tile work including cost of its dismantling/stacking after culmination of Yatra at Neelgrath for Yatra-2017.	0.85	1700	D	10 Days	Rs.200
2	Construction of (02 no.) fuel depot including cost of its dismantling/stacking after culmination of Yatra at Neelgrath for Yatra-2017.	0.35	700	D	7 Days	Rs.100/-
3	Assembling of Toilet/ Baths (500 nos.)and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2017 at Baltal Camp.	4.50	9000	D	25 Days	Rs.1000/-
4	Assembling of Toilet/ Baths (330 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enroute Rang morh to for Yatra-2017.	3.50	7000	D	25 Days	Rs.700/-
5	Construction of partition between newly constructed Huts and also raising / repair of existing partition between CRPF and newly constructed huts at Baltal for Yatra-2017	2.00	4000	D	15 Days	Rs.400/-
6	Repairs to Prefab Huts (113 Rooms) (4 No. dormitories size 64' x 16' + 2 No. stores size 32' x16') VVIP Hut, Hut No. 81-95, Bank Hut, Chowkidar Hut and maintenance of 93 No. Pacca toilets during for Yatra-2017.	6.00	12000	D	15 Days	Rs 1000/-
7	Construction of shed (20'x12') 02 Nos. for food department, (30'x10') 03 Nos. for langar gas store, (10'x30') 01 No. for frisking, (12'x12') 01 No. for Medical at Domel, (12'x12') for PDD shed and (12'x12') for PHE kitchen at Baltal. for Yatra-2017.	7.14	14200	D	25 Days	Rs 1000/-
8	Re-roofing and Painting of Hangar, 4 No. Prefab Hut and Kitchen for Medical department including dismantling/stacking of roofing after the conclusion of yatra at Baltal (Yatra-2017).	3.92	7800	D	15 Days	Rs 800/-
9	Repair/Re-erection of barbed wire fencing at Baltal camp, including fencing of Helipad area, STP, PDD area and Medical at Domel and SASB store at Baltal for Yatra-2017	4.50	9000	D	20 Days	Rs 1000/-
10	Improvement/Clearance of drains inside Baltal Camp and old Helipad area including its reconstruction with dry random rubble masonry stone at Baltal Camp 1500 Rm for Yatra-2017.	1.50	3000	D	15 Days	Rs 300/-

11	Erection of C.G.I Sheet for partition between STP and Langars including providing and fixing of agro-net partition in front of ladies Toilet/Bath at Baltal Base Camp for Yatra-2017 .	0.60	1200	D	10 Days	Rs.100/-
12	Repair/Re-roofing of Pacca toilets at Baltal for Yatra-2017	1.50	3000	D	15 Days	Rs.300/-
13	Construction of Soakage pits (28 Nos.) in Baltal Camp and Ranga Morh to Domel for Yatra-2017	3.50	7000	D	25 Days	Rs.700/-
14	Construction of Additional soakage pit and laying of PVC pipe line oxidation Chamber to soakage pit at Baltal for Yatra-2017 .	1.00	2000	D	10 Days	Rs.200/-
15	Levelling of parking area including removal of slips, slides, debris and providing of RBM in slushy portions where ever required (subject to actual cross section) at Baltal for Yatra-2017.	3.00	6000	D	15 Days	Rs.600/-
16	Painting to Prefabricated Toilets/Baths at Baltal and enroute Rangh Morh to Domel (300 No.) for Yatra-2017.	2.40	4800	D	25 Days	Rs.500/-
17	Repairs/Painting of Pre-fabricated Huts (40 nos) and 04 Nos. Dormitories(size 16'x64') for Yatra-2017 at Baltal	1.55	3100	D	20 Days	Rs.400/-
18	Laying of pacca path in front Prefabricated toilet/baths on back side of langar No. 07 towards pacca toilet on pacca side Hut No. 81- 86 at Baltal for Yatra-2017.	3.00	6000	D	25 Days	Rs.600/-
19	Improvement to Brarimarg store by way of providing CGI sheet roofing to one apartment of store and pucca flooring to both apartments of store for Yatra-2017.	1.00	2000	D	20 Days	Rs.200/-
20	Erection/assembly of prefabricated toilets/baths (140 Nos.) including cost of its dismantling during or after Yatra at enroute Domel to Sangam for Yatra-2017.	1.96	3900	D	20 Days	Rs 400/-
21	Erection and carriage of Sign Boards, RD Boards, Informatory Boards (51 Boards) before Yatra including cost of its dismantling and proper stacking in nearby SASB store after Yatra at Panjtarni and enroute Domel to Holy Cave for Yatra-2017.	0.35	700	D	10 Days	Rs 100/-
22	Construction of dry stone soakage pits in Random Rubble masonry (15 Nos.) for Toilet/Baths at enroute Domel to Sangam for Yatra-2017	3.00	6000	D	20 Days	Rs 600/-
23	Erection of barbed wire fencing to medical camps at enroute Domel to Sangam and near entrance gate of Holy Cave (06 No. of size 25'x 50') including cost of its dismantling and stacking after the culmination of Yatra at near by SASB Camp for Yatra-2017.	0.60	1200	D	15 Days	Rs200 /-
24	Painting to Prefabricated Toilets/Baths enroute Domail to Holy Cave (75 No.) for Yatra – 2017	0.97	1900	D	15 Days	Rs 200/-
25	Erection/assembly of prefabricated toilets/baths including cost of its dismantling during or after Yatra at Holy Cave for Yatra-2017	2.90	5800	D	20 Days	Rs 600/-
26	Assembling of Oxygen shed and Morchary shed before Yatra and dismantling the same after Yatra at Holy Cave (02 No. shed of size 10' x10') for Yatra-2017.	0.45	900	D	10 Days	Rs 100/-
27	Erection & dismantling of railing along the stairs, erection and dismantling of entrance gate at Holy Cave for Yatra-2017.	0.90	1800	D	10 Days	Rs 200/-
28	Erection of BSNL Staff Shed, Labour shed, SASB staff shed and Store for SASB material including dismantling of the same at Holy Cave for Yatra-2017	0.80	1600	D	10 Days	Rs 200/-

29	Assembling of Shoe rack shed (15'x15'), 01 No. frisking shed (size 8'x8') before Yatra and including cost of dismantling after Yatra at Holy Cave for yatra-2017	0.50	1000	D	10 Days	Rs 100/-
30	Assembling of Cloak Room (14'x14') before Yatra and including cost of dismantling after Yatra at Holy Cave for yatra-2017.	0.50	1000	D	10 days	Rs 100/-
31	Painting and repair to grill and counting hall at Holy Cave for Yatra-2017.	0.25	500	D	05 Days	Rs 100/-
32	Painting to Prefabricated Toilets/Baths at Holy Cave (100 No.) Yatra – 2017.	1.30	2600	D	15 Days	Rs 300/-
33	Clearance of snow (with frost) from Helipad and track from helipad to upstairs at Holy Cave for Yatra – 2017.	1.80	3600	D	15 Days	Rs 400/-
34	Clearance of snow (with frost) from Pandal at Holy Cave for Yatra – 2017.	1.63	3200	D	15 Days	Rs 400/-
35	Clearance of snow (with frost) from entry stairs and exit stairs at Holy Cave for Yatra – 2017.	2.73	5400	D	15 Days	Rs 600/-

2. Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from 9.30 AM to 5.00 PM, on any working day (Monday-Saturday) up to **25.02.2017** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
3. The Tender, duly completed, along with Earnest Money Deposit in the form of CDR in favour of Chief Accounts Officer, Shri Amarnathji Shrine Board payable at Jammu / Srinagar, must reach latest by **1400 hours on 28.02.2017**. The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through courier/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reason.
4. The Technical bid shall be opened at **10 am on 01.03.2017** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the Agencies/ Bidders who may wish to be present on the occasion.
5. Not more than two Bid documents shall be issued to a single bidder.
6. In case the last date of receipt of Bid happens to be a holiday, the Bid shall be received on the next working day up to 1400 hours.
7. The successful bidder is bound to enter into an Agreement with General Manager (Works) SASB, within fifteen days from the date of the issue of Letter of Allotment of Work.

No: SASB/NIT/2017/ 10
Dated: 01.02 .2017

Sd/-
General Manager (works)
Shri Amarnathji Shrine Board

ELIGIBILITY CRITERIA

The Bidder must be a Contractor (registered with PWD J&K) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process;

- 2.1 The Bidder must possess at-least three year's experience (experience from Calendar Year 2012 to 2016 shall only be considered) in the field of Civil Construction in hilly region.
- 2.2 The Bidder should possess the experience of completion of at least 03 works of similar nature to those mentioned in the DNIT in High altitude area of which at least one work should be of cost not less than fifty percent of the amount of the tendered work with SASB.
- 2.3 The Bidder should have an average Annual Turnover of at least Rs. 3.00 lakh during at least one of the financial year from Financial Year 2014-15 to Financial Year 2015-16.
- 2.4 The Bidder should not have been blacklisted on an earlier occasion by any of the State Government Organizations, State Autonomous Bodies or Local Bodies/ Municipalities.

III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

- 3.1 Registration Certificate authenticating the same.
- 3.2 Certified copies of Annual Turnover from Bank.
- 3.3 Certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works, for fulfilling the eligibility criteria.
- 3.4 Certified copy of PAN Card.
- 3.5 Certified copy of TIN Registration Certificate.
- 3.6 General Profile of the Bidder
- 3.7 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect at any time, the Security Deposit shall stand forfeited.

IV. **INSTRUCTIONS TO BIDDERS**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from 9.30 AM to 5.00 PM on any working day (Monday-Saturday) till **28.02.2017** on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft drawn in favour of Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), J&K.
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** - strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of _____ Yatra 2017**” and “**Financial Bid for the work of _____ Yatra 2017**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of _____ (Yatra 2017)**” mentioning **NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B** are liable to be rejected.
- 4.3 The Bids, duly completed, along with an Earnest Money Deposit (EMD) of amount prescribed in the DNIT (Rs. _____) only in the form of Demand Draft drawn in favour of Financial Advisor / Chief Accounts Officer “Shri Amarnathji Shrine Board” payable at Jammu, must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, or sent by Registered Post/ Courier to FA/ Chief Accounts Officer at the aforesaid address, so as to reach by **1400 hours 28.02.2017 latest**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by courier/ post. The technical Bids shall be opened at **10 a.m. on 01.03.2017** in the office of General Manager (Works), (at Jammu office) in presence of the Contractors/ Bidders.
- In case last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day up to 1400 hours and shall be opened on the same day at 1500 hours.
- 4.4 Bids not accompanied by EMD shall be summarily rejected. The EMD and cost of DNIT should be placed inside the envelope containing the Technical Bid. The EMD shall be forfeited if the Bidder withdraws his bid during Bid Validity Period.
- 4.5 It would be deemed that by submitting the Bid, the Bidder has made complete examination of the DNIT, received all information requested from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each Bidder can submit only one Bid in response to a work in the DNIT. Any Bidder who submits more than one Bid shall be disqualified.
- 4.8 The Bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of

Bid not substantially responsive to the DNIT in every respect will be at Bidder's risk and may result in the rejection of the bid.

- 4.9 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures. The corrections, if any, must be attested by the Bidder. Amounts shall be indicated in words as well as in figures. Where there is a difference between amount mentioned in figures and words, the amount quoted in words shall be taken as authentic.
- 4.10 The Bidder must satisfy himself that it fulfils all the prescribed eligibility conditions to avoid rejection of his Bid.
- 4.11 Each paper of the Bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.12 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The Chief Executive Officer may, at his discretion, extend the deadline for submission of Bids. Any Bid received after the last date/ time for submission of Bids, as stipulated above, shall not be considered and will be returned.
- 4.13 Clarifications, if any, may be sought by the Bidders so as to reach GM (Works) at least seven days before last date prescribed for submission of Bids. Except for any written clarification by Chief Executive Officer, SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on our website (www.shriamarnathjishrine.com) and NOT in newspaper (s). The Bidders should keep themselves updated on this account.
- 4.14 The Technical Bid shall be opened at **10 a.m. on 01.03.2017** in the office of General Manager (works) in the presence of the authorized representatives of the Bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.15 The Chief Executive Officer, SASB is not bound to accept the lowest or any Bid and may, at any time by notice in writing to the Bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.16 The Bid should remain valid and open for acceptance for a period (i.e. Bid Validity Period) of 60 days from the last date prescribed for its receipt.
- 4.17 To facilitate evaluation of Bids, the GM (Works) may, at his sole discretion, seek clarification in writing from any Bidder regarding the Bid. The request for such clarification or substantiation and the response shall

be in writing or by facsimile or email. No material change in the substance of the Bid would be permitted by way of such clarification/ substantiation.

- 4.18 The GM (Works) may award the Contract to the Bidder whose Bid has been evaluated to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The GM (Works), SASB will send to such eligible Bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible Bidder in consideration of work/ services to be executed by the eligible Bidder as prescribed in the Contract.
- 4.19 The eligible Bidder will have to enter into an Agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the fifteen days of the issue of Letter of Intent.
- 4.20 Chief Executive Officer, SASB reserves the right to reject all or any Bid in whole, or in part, without assigning any reason. Any enquiry after the submission of tender will not be entertained.
- 4.21 Shri Amarnathji Shrine Board shall not be responsible for release of any CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the CDR's of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

V. **SCOPE OF WORK**

5.1 **The Board and the Yatra:**

- a) Shri Amarnathji Shrine Board (SASB) was established in 2001 under a statute with a view to providing better management of the Shri Amarnathji Yatra, upgradation of facilities for the pilgrims, etc. Hon'ble Governor, J&K is the ex-officio Chairman of the Board.
- b) The pilgrimage (Yatra) is undertaken during the period specified in the months of July-August, through two different routes:
- i) Pahalgam (7500 ft.)- Panjtarni (12729 ft.) - Holy Cave (13500 ft.). This route is 32 km long from Chandanwari to Holy Cave; and,
- ii) Baltal (9500 ft.), Domel (9577 ft.)- Brarimarg (13120 ft.)- Holy Cave (13500 ft.). This route is 14 km long from Baltal to Holy Cave.
- c) During the Yatra, over 3.5 lakh persons (this number may be exceeded this year) undertake the pilgrimage to the Holy Cave Shrine of Shri Amarnathji, situated at an altitude of 13,500 feet, in District Anantnag, J&K. Baltal (near Sonamarg) and Nunwan (Pahalgam) are the two Base Camps where the Yatris congregate before embarking on the pilgrimage. Other Camps en-route are Sheshnag, Panjtarni and Holy Cave.

5.2 **Site Overview**

- a) The Camps are located at varying altitudes ranging from 7500 ft to 13500 ft above MSL.
- b) Temperature ranges from (-10⁰C to +25⁰C) during Yatra period.
- c) Baltal/ Domel is connected through a motorable road on Srinagar- Leh National Highway and is 110 km away from Srinagar. Pahalgam (Nunwan) is located at a distance of 90 km from Srinagar. It is located at a distance of 38 km from Khanabal which is at 250 km on Jammu - Srinagar National Highway.
- d) The journey to Holy Cave from Baltal involves trekking a distance of 14 km. From Chandanwari (Pahalgam route), the visit to the Holy Cave involves a trek of 32 km.
- e) Average weight that can be carried manually by a *pittoo* is 20 kg and by a pony is 60 kg.
- f) The Bidders will need to acquaint themselves of the nature and quantum of work involved, preferably by undertaking site visits of the Camp locations. Considering the present weather conditions, it would be possible for a bidder to visit Baltal and Holy Cave any day, whereas other locations can be visited only after the snow melts.

VI. **TERMS AND CONDITIONS OF THE CONTRACT**

- 6.1 The bidders are required to quote rate above/ below percentage on SSR of 2012 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. However, where it has been mentioned in column V that the 'Rate to be quoted', the bidder should quote rate in Rupees per unit. All rates/ percentages should be quoted in figures and words. The bidders are also to calculate and mention total cost of his bid in last row of the table of Schedule B, both in figures and words.
- 6.2 Bids shall have to be submitted separately for each Work as indicated in the NIT.
- 6.3 The Security Deposit/ Earnest Money of the unsuccessful bidders shall be released immediately after the work is awarded to successful bidder.

Imbalanced bids :

- 6.4 All Bids (received from bidders) valuing less than 80% of the tendered cost shall be treated as imbalanced bids.
- 6.5 Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money) in the shape of CDR with his bid. This Additional Earnest Money should be equal to the difference between the bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.

- 6.6 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- (i) First 3 days of delay Penalty 1% of contract value.
 - (ii) 4th day upto 10th day 2% of contract value.
 - (iii) Beyond 10 days Earnest Money shall be forfeited and the contract shall automatically stands cancelled. The General Manager Works, GM (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm.
- 6.7 Not with standing Clause - 6.6 above in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 6.8 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Work Allotment Letter.
- 6.9 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.
- 6.10 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.
- 6.11 The Contractor shall submit pictorial evidence (Photographs) of execution of work (post execution, during execution and after completion of work) with his claim.
- 6.12 The Contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 6.13 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the Contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the contractor.
- 6.14 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the state or Central Government or local authority and any other labour law (including rules), regulation, byelaws that may be passed or notification that may be issued under any labour law in future either by

the state or the Central Government or the local authority. The Contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.

- 6.15 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract shall be the sole responsibility of the contractor.
- 6.16 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 6.17 The employees hired/ employed for the execution of work of the contractor shall in no case whatsoever, be treated as the employees of SASB.
- 6.18 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the law.
- 6.19 The Contractor is bound to draw an agreement with GM (Works), SASB within fifteen days from the date of issuance of Allotment Order.
- 6.20 GM (Works), SASB shall be at liberty to suspend the agreement due to any *Force Majeure* conditions such as Government regulations, **court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.**
- 6.21 All disputes and differences between the parties arising out and relating to the agreement to be signed between the GM (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 6.22 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the State of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 6.23 The rates quoted by the contractor shall be inclusive of all taxes e.g. (sales tax, service tax etc) that are in vogue.
- 6.24 If during the period of three months from the date of completion, the work - defects which have been caused by bad workmanship, use of inferior materials on the work, the Contractors shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General

Manager (works), Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the cost thereof shall be recoverable from the security deposit of the contractor or from payments due to him.

VII Payment Clause:

- 7.1 Payment shall be made to the Contractor for complete item of the work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 7.2 The payment to the bidder shall be made after successful completion of work within the stipulated time (with specification as per the allotment of Contract and subsequent drawal of agreement) after satisfactory use/function of the work during complete Yatra Period

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND EARNEST MONEY

#	Item	Details
1	Amount and details of payment towards the cost of DNIT	Rs. <i>(in words)</i> :
		Receipt No./Cheque No:
		Date:
2	Amount and details of Earnest Money Deposit submitted	Rs. <u>(in words)</u> :
		DD No.
		Dated:
		In favour of
		Date of issue:
		Issuing Authority:

PART – B: BASIC DETAILS ABOUT THE AGENCY.

i) Name and address of : Name: _____
the Agency.

Address: _____

Phone: _____

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:

(please attach separate sheets where necessary):

1. Registration No. / Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

#	Financial Year	Turnover (Rs.)
1	2012-13	
2	2013-14	
3	2014-15	
4	2015-16	

3. Documents to show that the contractor possesses relevant experience in past three years. The Bidder must furnish certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/No)

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*)
5. Certified copy of TIN Registration Certificate – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*)
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*)
7. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder. Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility .*

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Mounting of water storage tank on existing stages, water supply fitting, fixing of 02 nos. motor pump and fixing of chain link fencing and minor repair to tile work including cost of its dismantling/stacking after culmination of Yatra at Neelgrath Yatra-2017

S.No.: 01

Adv.Cost: 0.85 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Providing and fixing of G.I. pipes complete work G.I fittings including trenching and refilling etc. 15 mm dia, nominal bore, medium	300	Rm	Rs.12.80/-		
2	Providing and fixing of GI fittings. (i) 20mm to 15mm Sockets (ii) 15mm dia GI Tee (iii) 15mm dia GI Union	50 50 30	No. No. No.	Rs 18/- Rs 38/- Rs.174.80/-		
3	Providing and fixing of brass stop cock of approved quality(15mm nominal bore)	05	No.	Rs.224.05/-		
4	Providing and fixing of PTMT Bib cock of approved quality	30	No.	Rs 154.35/		
5	Supply of PVC fittings B Grade : i. PVC pipe 110mm dia ii. PVC Tee iii. PVC Socket iv. PVC bend	130 10 15 10	Mtr No. No. No.	RTQ/- RTQ RTQ RTQ		
6	a. Mounting of 02 No. water storage tanks of 1000 ltr capacity on existing staging, 02 No. Motors including fixing of 15 mm dia pipe 150 meters (available in store) complete with fittings from over head tank to toilet/baths in Departure lounge and 04 No. prefab huts. (complete job) including its dismantling after culmination of Yatra. b. Fixing of chain link fencing including cost of nuts& bolts Complete job (material available in SASB store)	02 1180	No. Sft	RTQ RTQ		
7	Repair to tile work of existing foot path from Departure Lounge to level –third (i.e. Pawan Hans Heli Service and in Departure Lounge	500	Sft	RTQ		
8	Cleaning, washing of Departure Lounge 04 No. Pre fab Huts including bathrooms (complete)	5656	Sft	RTQ		
9	Supply of plumber for maintenance of water supply during Yatra for 20 Day and Night	20	Day	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 2012.**

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of (02 no.) fuel depot including cost of its dismantling/stacking after culmination of Yatra at Neelgrath Yatra-2017

S.No. : 02

Adv.Cost: 0.35 lac

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	16	No.	Rs 24.90/-		
2	Providing Wood work in frames of false ceiling, partitions etc. sawn and fixed in position. Budloo/ Fire wood.	36.96	Cft	RTQ		
3	Providing corrugated P.P.G.I sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	40.613	Sqm.	RTQ		
4	Filling empty cement bag with sand/ earth including cost of sewing and strings: excluding cost of bag and earth/ sand	400	No.	Rs 3.70/-		
5	Supply of empty cement bags	400	No.	RTQ		
6	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 metres height including stacking the material within 50 metres lead of sectional area below 40 square centimetres	136.58	Rm	Rs.7.05/-		
7	Dismantling of PPGI roofing including ridges, hips, valleys and gutters etc. and stacking the material within 50 metres lead .	40.613	Sqm	RTQ		

**Total cost of bid (to be quoted both in figures and words)
of 2012**

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (500 nos.)and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2017 at Baltal Camp.

S.No. : 03

Adv. Cost: 4.50 lac

S. N o.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	<p>Assembling of toilets/baths at designated site (before commence of Yatra) including:-</p> <p>i. Carriage of prefabricated panels and other parts from store to site of installation by head load.</p> <p>ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc.</p> <p>iii. Supply of nuts & bolts etc of required size.</p> <p>iv. Fixing of disposal PVC pipe, bends, tee etc</p> <p>v. Maintenance of toilet/baths including replacing the damage sewer line if any during Yatra</p> <p>(Complete Job)</p>	500	No.	RTQ		
2	<p>Supply of PVC pipes and other fittings items to toilets/baths and laying under pipe 45 cm in ground;</p> <p>I. PVC pipes(110mm)</p> <p>II. PVC bends(110mm)</p> <p>III. PVC sockets(110mm)</p> <p>IV. PVC Tee(110mm)</p> <p>V. PVC door tee (110mm)</p>	360 200 150 150 15	Rm No. No. No. No.	RTQ RTQ RTQ RTQ RTQ		
3	<p>Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from</p>	51	Cum	Rs.240.45/-		

	cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.					
4	Filling the available earth in proper layers by ramming each layer with heavy blows within the lead of 50 meters.	51	Cum	Rs.102.20/-		
5	Dismantling of toilets/baths at erection site including plugging of inlets of sewer line with gunny bags and filling of exposed pipe fitting with earth upto 30 cm height to avoid damages in winter season/theft and carriage of material from erection site to store with proper stacking after conclusion of Yatra.	500	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (330 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enrout Rang morh to Domel and Neelgrath Helipad area Yatra-2017

S.No.: 04

Adv.Cost: 3.50 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply iii. Supply of nuts & bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc v. Maintenance of toilet/baths during yatra. vi. Excavation/ repair to the cess pits including covering of the same with the available material in SASB store. (Complete Job)	330	No.	RTQ		
2	Supply and fixing of PVC pipes and other fittings items to toilets/baths and laying of pipe 45 cm in ground I. PVC pipes(110mm) II. PVC bends(110mm) i. PVC sockets(110mm) ii. PVC Tee	450 150 100 150	Rm No. No. No.	RTQ RTQ RTQ RTQ		
3	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	330	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of partition between newly constructed Huts and also raising / repair of existing partition between CRPF and newly constructed huts at Baltal.

S.No.: 05

Adv.Cost: 2.00 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Providing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	148.69	Sqm	Rs.757/-		
2	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	67.92	M ³	Rs. 150/-		
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. Layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and fit upto 1.5m.	67.92	M ³	Rs 102.20/-		
4	Turfing of area with supply of good earth and turf and watering complete.	1750	Sft	RTQ		

5	Raising of partition toward CRPF and outsource huts area (250 Rft x 6')	1500	Sft	RTQ		
6	Carriage of material from Ganderbal to Baltal (LMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

3	Repair to damaged roofs / truss of 113 No. huts damaged in winter season including re-fixing of conopy of inspection hut. a. Steel work b. Roofing	1500 8035	Kg Sft	RTQ RTQ		
4	Providing and fixing white vitreous China pedestal type (European type /wash down type) water closet pan.	10	No.	Rs.1407.10/-		
5	Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete.	25	No.	Rs.898.70/-		
6	Providing and fixing solid plastic seat with lid for pedestal type W.C. Pan complete.	37	No.	Rs.431.40/-		
7	Providing and fixing White Vitreous China wash basin including making all connections but excluding cost of fitting (flat back wash basin size 550 x 400 mm) .	15	No.	Rs.738.85/-		
8	Providing and fixing unplasticised PVC connection pipe with brass union. (15 mm nominal board)	92	No.	Rs.83.20/-		
9	Providing and fixing CP brass bib cock of approved quality confirming to IS : 8931 (15 mm nominal board)	35	No.	Rs.406.50/-		
10	Providing and fixing CP brass angle Valve for wash basin mixer and geyser of approved make conforming to IS:8931 (15 mm nominal bore)	35	No.	Rs.394.90/-		
11	Supply of CP Jets	25	No.	RTQ		
12	Supply and fixing of PVC waste pipe for sink or wash basin including PVC waste fitting complete. 32mm dia	77	No.	Rs.72.53/-		
13	Providing wood work in frames of false ceiling partitions etc Sawn and fixed in position (popular wood)	25.60	Cft	RTQ		
14	Supply of ply wood 5 ply with commercial ply on both faces 6 mm thick (panels).	62.45	M ²	Rs.450/-		
15	Providing and fixing flat pressed 3 layer particle board medium density exterior grade (grade 1) or graded wood particle board IS: 3087 marked to frame, backing or studding with screws etc. complete (frames, backing or studding to be paid separately) 18 mm thick	59.72	M ²	Rs.665.60/-		
16	Providing and fixing wooden moulded beading	1000	Rft	RTQ		
17	Providing and fixing wooden cornices	700	Rft	RTQ		
18	Renewal of glass pans with putty and nails wherever necessary, float glass	20.6	Sqm	Rs.684.50/-		

	pans of thickness 4 mm.					
19	Applying priming coat with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood)	130.85	M ²	Rs.34.45/-		
20	Painting with synthetic enamel paint of approved brand and manufacturer to give an even shade two or more coats on new work.	130.85	M ²	Rs.67.10/-		
21	Supply of mirror of superior make glass 60 x45 cm	15	No.	Rs.350/-		
22	Providing and fixing PTMT bib cock of approved quality and colour 15 mm nominal bore and 86 mm long weighing not less than 88 gm (huts and pacca toilets)	170	No.	Rs.154.35 /-		
23	Supply of 125 mm handles	42.	No	Rs.8.50/-		
24	Supply of tower bolt 150 mm x 10 mm	35	No.	Rs.35/-		
25	Supply of locks	80	No.	RTQ		
26	Supply of fixing of geysers (20ltr capacity) of approved quality such as anchor, bajaj, recold etc complete job	02	No.	RTQ		
27	Supply and fixing of monolithic European type seat including jet spray heavy duty including cost of fitting (complete job)	02	No.	RTQ		
28	Laying of G.I. Pipe complete with fittings including trenching and refilling between outsource hut	300	mtrs	Rs.45.75/ -		
29	Supply of G.I. fitting i. 20mm to 15 mm sockets ii. 15 mm elbow iii. 15 mm Tee iv. 15mm union v. Stop cock	200 100 100 50 10	No. no. no. no. no.	Rs.18/- Rs .26/- Rs. 38/- Rs.174.80/- Rs.224.85/-.		
30	Supply of plumber with helper for maintenance of water supply in Baltal Camp, Domel, outsource huts, new helipad, pacca toilets	Full Yatra period		RTQ		
31	Supply of 01 No. electrician for maintenance of electricity in camp outsource hut, pacca toilet, helipad area & Domel	Full Yatra period		RTQ		
32	Carriage of material from Ganderbal to Baltal (HMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of shed (20'x12') 02 Nos. for food department, (30'x10') 03 Nos. for langar gas store, (10'x30') 01 No. for frisking, (12'x12') 01 No. for Medical at Domel, (12'x12') for PDD shed and (12'x12') for PHE kitchen at Baltal. (Yatra-2017).

S.No. : 07

Adv.Cost: 7.14 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth Work in excavation by manual means over areas (exceeding 30 cm and upto 1.5 cm in depth 1.5 mt in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in (all Kinds of soil) Excavation of Holes Food shed : 2x10 = 20 Nos. Gass shed : 3x10 = 30 Nos. Frisking shed : 2x5 = 10 Nos. PHE shed : 2x4 = 08 Nos. PDD shed : 2x4 = 08 Nos. Medical Shed : 2x3 = 06 Nos. 82 Nos.	10.44	M ³	Rs. 240.45/-		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shutting all work upto plinth level. 1:3:6 (1 cement: 3 coarse sand :6 graded stone aggregate 40 mm nominal size)	10.44	M ³	Rs.3707.40/ -		
3	Steel work in built up tubular round, square or rectangular including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including welding and bolting with special shaped washers etc (complete).	3865	kg	Rs. 108.25/-		

	10-16-1 (100 mm dia x 4 mm thick)					
4	Providing corrugated PPGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm, diameter with bitumen and G-I Limpet washers or with G-I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal vertical or curved surface) excluding the cost of Purlins, rafters. (old sheet)labour work	516	M ²	Rs. 218.75/-		
5	Structural steel work in single fixed with connecting plate including cutting hoisting fixing in position and applying a priming coat of approved steel primer all complete M.S. Angle 35x35x6 mm	1368	kg	Rs. 70.55/-		
6	Providing wood work in frame of false ceiling partition etc sawn and fixed in position: Budloo/Fir wood (labour work)	1.4	M ³	Rs. 12755/-		
7	Carriage of sand and Bajree from 5 km lead by M.T.	14.09	M ³	Rs. 127.08/-		
8	Carriage of material from Srinagar to Baltal by M.T. (LMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Re-roofing and Painting of Hangar, 04 Nos. Pre-fab huts and kitchen for Medical Department including Dismantling/stacking of roofing after the conclusion of yatra at Baltal. (Yatra-2017)

S.No. : 08

Adv. Cost: 3.92 lac

S. N o.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Repairs to steel trusses of Hangar including strengthening of truss by way of welding including erection of two no. room 8'x12' in OPD at Baltal a. Steel work b. CGI sheet Roofing	700 750	Kg Sft	RTQ RTQ		
2	a. Dismantling of CGI sheet walls, roofing prefab huts vertical curved side including opening of doors, windows etc (complete in all respect). b. Front Wall	200	M ²	Rs.62.25/-		
3	a. Providing corrugated PPGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only) b. Providing corrugated PPGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved	176.00 148.69	M ² M ²	RTQ Rs.757/ -		

	surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² .					
4	Providing ridges or hips of width 60 cm overall width overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mmdia G.Ilimpet and bitumen washers complete 0.63mm thick with zinc coating not less than 275gm/m ² .	15.24	M	Rs.490.40/-		
5	Structural steel work in single section fixed with connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. M.S. Angle 50x50x6 mm	810	kg	Rs.69.60/-		
6	Providing PVC sheet 2mm thick to partition walls	145.72	Sqm	Rs.376/-		
7	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	375	M ²	Rs. 8.80/-		
8	Distemping with Oil bound washable distemper of approved brand and manufacture to give an even shade. Old work (one or more coats)	812.64	sqm	Rs.31.55/-		
9	a. Refixing of ceiling in the rooms of hanger with serviceable ply received by dismantling of existing ceiling and refixing of same including cost of new ply (if required) and all other items such as nails, beddings, cornice etc (complete job) b. CGI sheet roofing	1600 1005	Sft Sft	RTQ RTQ		
10	Providing 5 mm thick with commercial ply on both faces 6mm thick (panels)	62.44	sqm	Rs.450/-		
11	(Dismantling after Yatra-2017) a. Dismantling of CGI sheet walls, roofing prefab huts vertical curved side including opening of doors, windows etc (complete including carriage of material to SASB store)	148.69	M ²	Rs.62.25/-		

12	Refixing of corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only) (front wall of hanger)	52	M ²	RTQ		
13	Carriage of material from Ganderbal to Baltal (LMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair/Re-erection of barbed wire fencing at Baltal camp, including fencing of Helipad area, STP, PDD area and Medical at Domel and SASB store at Baltal (Yatra - 2017)

S.No. : 09

4.50 lac

Adv. Cost:

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	200	Posts	Rs.124.90/-		
2	Supplying of steel angle iron posts and struts of required size including bottom to be split/bent at right angle in opposite direction for 10cm length and drilling holes upto 10mm dia etc. complete.	2000	Kg	Rs.69.60/-		
3	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete (labour only)	1804	Rm	Rs.64.30/-		
4	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 th post, last but one	700	Rm	Rs.153.90/-		

	end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete, (Cost of posts, struts, earth work and concrete to be paid for separately). With GI barbed wire.					
5	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works upto plinth level. 1:2:4 (1 cement: 2 course sand:4 graded stone aggregate 40mm nominal size) Crushed	9.55	M ³	Rs.4575.50/-		
6	Centring and shuttering including strutting, propping etc. removal of frame work for foundations, footings, bases of columns etc. for mass concrete .	83.64	Sqm	Rs.179.25/-		
7	Strengthening of damaged angles and tightening existing fencing	1000	Kg	RTQ		
8	a. Carriage of material (sand and bajree) by mechanical means avg. lead 55km. b. Carriage of cement barbed wire and angle posts from Srinagar to Baltal (HMT)	12.89 01	M ³ Trip	Rs.447.93/- RTQ		
9	Dismantling of barbed wire fencing and angle iron post including carriage and stacking in SASB store after culmination of Yatra	2800	Kg	Rs.12.30/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 2012.**

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Improvement/Clearance of drains inside Baltal Camp and old Helipad area including its reconstruction with dry random rubble masonry stone at Baltal Camp (1500 Rm) (Yatra-2017)

S.No. : 10

lac

Adv.Cost: 1.50

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Slip Clearance in soils mixed with moorum / Kankar / shingle / boulders; disposal lead upto 50 metre and lift upto 1.5 mtr	270	Cum	Rs.158.95/-		
2	Earth work in excavation by manual means over areas (exceeding 30 cm and upto 1.5m in depth, 1.5 m in width as well as 10 sqm on Plan) including disposal of excavated earth upto 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil for lead of 01 Km (within camp for filling of Old Ciss pits) as directed by the engineer site incharge (cutting from Rd 600-1000)	108.00	Cum	Rs.342.74/-		
3	Dry random rubble masonry with hard stone in foundation and plinth using nallah stone without bond stone for a lead of 1 Km by MT.	54.00	M ³	Rs.1404.48/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of C.G.I Sheet for partition between STP and Langars including providing and fixing of agro-net partition in front of ladies Toilet/Bath at Baltal Base Camp. (Yatra-2017)

S.No. : 11

Adv.Cost: 0.60 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	12.234	cum	Rs. 240.45/-		
2	Providing corrugated CG sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	233	Sqm	RTQ		
3	Providing Wood work in frames of false ceiling, partitions etc. sawn and fixed in position. Budloo/ Fire wood. i. Labour work ii. Supply of local wood	1.49 31.68	Cum Cft	Rs.12755.75/- RTQ		
4	Supply and fixing of Agro-net around partition in front of LadiesToilets/Baths complete	4400	Sft	RTQ		
5	Carriage of wood from Ganderbal to site of work at Baltal (LMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair/Re-roofing of Pacca toilets at Baltal (Yatra-2017)

S.No. : 12

Adv.Cost: 1.50 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Repairs to steel structure by way of strengthening of roofing including replacing of doors of pacca toilet in Block – A, doors available in SASB store. i. Steel Work ii. Replacing of doors	450 05	kg Nos.	RTQ RTQ		
2	Providing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	97.02	sqm	Rs.219.82/-		
3	White washing with lime to give an even shade. old work(three or more coats)	579.64	sqm	Rs. 9.40/-		
4	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade. Old steel work (one or more coats)	393.58	sqm	Rs.45.65/-		
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50m lead	38.232	cum	Rs. 813.85/-		
6	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works upto plinth level. 1:4:8 (1 cement: 4 course sand:8 graded stone aggregate 40mm nominal size) Nallah	2.124	cum	Rs.3061.30/-		
7	Cement concrete flooring 1:2:4 (1 cement: 2 course sand:4	27.881	sqm	Rs.314.20/-		

	graded stone aggregate) finished with floated coat of neat cement including cement slurry but excluding cost of nosing of steos etc. complete 40mm thick with 20mm nominal size stone aggregate) Nallah					
8	Providing and fixing white vitreous china water closet squatting (Indian type) long pattern W.C pan of size 580mm.	20.00	No.	Rs.1210.80/-		
9	Supply and fixing of PVC pipes B-grade and other fitting items to toilets/ baths PVC pipes PVC Bends PVC socket PVC Tee	60 25 20 20	no no. no. no	RTQ RTQ RTQ RTQ		
10	Carriage of material from Srinagar (Factory) to Baltal (110km lead)	0.834	tonne	Rs.683.10/-		
11	Carriage of material (sand and bajree) by mechanical means avg. lead 5.00km.	4.372	cum	Rs.127.08/-		
12	Carriage of material from Ganderbal to Baltal (LMV)	01	trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of Soakage pits (28 Nos.) in Baltal Camp and Ranga Morh to Domel for Yatra-2017

S.No.: 13

Adv.Cost: 3.50 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by mechanical means (Hydraulic excavation) in foundation trenches, drains, pipes and cables etc. (not exceeding 1.5 mtr in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 mtr including getting out excavated soil and disposal of surplus soil as directed, within a lead of 50 mtr.	40.43	M ³	Rs.150/ M ³ -		
2	Dry random rubble masonry with hard stone in foundation and plinth using nallah stone without bond stone for a lead of 1 Km	167	M ³	Rs.1304.45/-		
3	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and sturts etc. upto floor five level excluding cost of centring, shuttering, finishing and reinforcement. 1:2:4 (1 cement: 2 coarse sand : 4 graded crushed stone aggregate 20 mm nominal size)	10.95	M ³	Rs.5587.45/-		
4	Centring and shuttering including strutting, propping etc. removal of form suspended floors, roofs, landings, balconies and access platform..	44.64	M ²	Rs.372.40/-		
5	Reinforcement for R.C.C. work including straightening, cutting, bending, placing, in position and binding all complete, hot rolled deformed bars.	1.56	kg	Rs.71/-		
6	Carriage of sand bajree 55 km lead.	21.28	M ³	Rs.447.93/-		
7	Carriage of cement from Ganderbal to Baltal (HMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of Additional soakage pit and laying of PVC pipe line oxidation Chamber to soakage pit at Baltal– Yatra- 2017

S.No.: 14

Adv.Cost: 1.00 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by mechanical means (Hydraulic excavation) in foundation trenches, drains, pipes and vables etc. (not exceeding 1.5 mtr in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 mtr including getting out excavated soil and disposal of surplus soil as directed, within a lead of 50 mtr.	90.22	M ³	Rs.150/ M ³ -		
2	Dry random rubble masonry with hard stone in foundation and plinth using nallah stone without bond stone for a lead of 1 Km.	26.68	M ³	Rs.1304.45/-		
3	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and sturts etc. upto floor five level excluding cost of centring, shuttering, finishing and reinforcement. 1:2:4 (1 cement: 2 coarse sand : 4 graded crushed stone aggregate 20 mm nominal size).	1.11	M ³	Rs.5587.45/-		
4	Centring and shuttering including strutting, propping etc. removal of form suspended floors, roofs, landings, balconies and access platform.	7.29	M ²	Rs.372.40/-		
5	Reinforcement for R.C.C. work including straightening, cutting, bending, placing, in position and binding all complete, hot rolled deformed bars.	1.50	kg	Rs.71/-		
6	Carriage of sand bajree by MT for a lead of 55 km	1.5	Cum	Rs.447.93/-		
7	Providing and laying of a. PVC pipes 110 mm dia from STP to soakage pit. b. PVC Tee c. PVC socket	122 04 16	Rm No. No.	RTQ RTQ RTQ		

8	Carriage of stone through mechanical transport for a lead of 5 kms.	26.68	M ³	Rs.149.51/-		
9	Carriage of cement and PVC pipes from Ganderbal to Baltal (86 kms) (LMV)	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Levelling of parking area including removal of slips, slides, debris and providing of RBM in slushy portions where ever required (subject to actual cross section) at Baltal.

S.No. : 15

Adv.Cost: 3.00 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish lead upto 50 m and lift upto 1.5 m in all kinds of soil.	25209	sqm	Rs -1135.95/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting to Prefabricated Toilets/Baths at Baltal and enroute Rangh Morh to Domel (300 No.) Yatra - 2017

S.No. 16

Adv.Cost: 2.40 lac

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc (10%)	510.6	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works. (10%)	510.6	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work including carriage of paint (one or more coat) (100%)	5106	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						
<u>of 2012.</u>						

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repairs/Painting of Pre-fabricated Huts (40 nos) and 04 Nos. Dormitories (size 16'x64') Yatra-2017 at Baltal.

S.No.: 17

Adv.Cost: 1.55 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth, including necessary repairs to scratches etc. complete.	998.20	sqm	Rs 8.80/-		
2	Distempering with Oil bound washable distemper of approved brand and manufacture to give an even shade.	3327	sqm	Rs 31.55/-		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old wood work	694	sqm.	Rs 45.65/-		
4	Painting (one or more coats) with black Japan paint of approved brand and manufacture to give an even shade	83.92	sqm	Rs 41.20/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of pacca path in front Prefabricated toilet/baths on back side of langar No. 07 towards pacca toilet on pacca side Hut No. 81- 86 at Baltal for Yatra-2017.

S.No. 18

Adv.Cost: 3.00 lac

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish lead upto 50 m and lift upto 1.5 m in all kinds of soil	408.92	100 Sqm	Rs.1135.95/-		
2	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works upto plinth level. 1:3:6 (1 cement: 3 course sand:6 graded stone aggregate 20mm nominal size) Nallah	31.13	Cum	Rs.3552.50/-		
3	Cement concrete flooring 1:2:4 including finishing with the floating coat of neat cement 40 mm thick	408.92	Sqm	Rs.314.20/-		
4	Supply of glass strips for the flooring of path including supply upto Baltal.	2994	Rft	RTQ		
5	Carriage of sand and bajree by MT for a lead of 65 Km	64.44	Cum	Rs.506.23/-		
6	Carriage of cement by MT from Srinagar to Baltal (110 km lead)	12.11	MT	Rs.683.10/-		
Total cost of bid (to be quoted both in figures and words)						

of 2012.

Signature of the Bidder

DGM (W) Baltal

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Improvement to Brarimarg store by way of providing CGI sheet roofing to one apartment of store and pucca flooring to both apartments of store for Yatra-2017

S.No.: 19

Adv.Cost: 1.00 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Providing and fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required including repair if any 0.63 mm thick with zinc coating not less than 275gm/m ²	26.60	Sqm	Rs.757/-		
2	Providing and laying in position a specified grade cement concrete excluding the cost of centring and shuttering all work upto plinth level in 1:4:8 by using 40 mm nominal size aggregates.	3.36	Cum	Rs.3061.30/-		
3	Providing and laying cement concrete flooring 1:2:4 finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc complete with 50 mm thick and 20 mm nominal size nallah aggregates.	42	Sqm	Rs.370.20/-		
4	Carriage of cement and CGI sheets by M.T. from Ganderbal to Baltal (LMV)	01	Trip	RTQ		
5	Carriage of material by head load from Baltal to Brarimarg; Ponies	18	No.	RTQ		

6	Carriage of sand and bajree by head load from nearby nallah (average lead 5 km)	7.71	Cum	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/assembling of prefabricated toilets/baths (140 Nos.) including cost of its dismantling during or after Yatra at enroute Domel to Sangam (Yatra-2017)

S.No. : 20

Adv.Cost :1.96 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load from near by SASB store ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc. iii. Supply of nuts & bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc (Complete Job)	140	No.	RTQ		
2	Supply of PVC pipes, bends ,tee, sockets of 110 mm dia b- grade (subject to the actual measurement at site) including carriage upto site of laying a. PVC pipe b. PVC bend c. PVC tee	100 100 100	Rm No. No.	RTQ RTQ RTQ		
4	Dismantling of toilet/baths during or after Yatra (on the instruction of site engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	140	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection and carriage of Sign Boards, RD Boards, Informatory Boards (51 Boards) before Yatra including cost of its dismantling and proper stacking in nearby SASB store after Yatra at Panjtarni and enroute Domel to Holy Cave (Yatra-2017)

S.No. : 21

Adv.Cost : 0.35

lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavation of holes for Boards and erection of boards at designated site including carriage from store to site of installation and brought back after dismantling to nearby SASB store at Panjtarni .	21	No.	RTQ		
2	Excavation of holes for Boards and erection of boards at designated site including carriage from store to site of installation and brought back after dismantling to nearby SASB store at enroute Domel to Railpathri .	10	No.	RTQ		
3	Excavation of holes for Boards and erection of boards at designated site including carriage from store to site of installation and brought back after dismantling to nearby SASB store at enroute Lower Brarimarg to Holy Cave via Both tracks (via kali Mata track and via Lower Sangam)	20	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of dry stone soakage pits in Random Rubble masonry (15 Nos.) for Toilet/Baths at enroute Domel to Sangam for Yatra-2017

S.No.: 22

Adv.Cost: 3.00 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil. For soakage pit of size 7' (dia)x8' (depth)	130.65	Cum	Rs.240.45/-		
2	Dry random rubble masonry with hard stone in foundation and plinth by using quarry stone with bond stone with 50% available stone (thickness of wall = 1'-6")	88.05	Cum	Rs.1454.50/-		
3	Providing and laying in position a specified grade cement concrete excluding the cost of centring and shuttering all work upto plinth level in 1:2:4 by using 20 mm nominal size aggregates.(for slab)	5.4	Cum	Rs.4575.50/-		
4	Providing reinforcement for slab including straightening, cutting, bending, placing in position and bonding all complete 10mm dia cold twisted bars.	300	Kg	Rs.71/-		
5	Centring and shuttering including propping strutting and removal of formwork from pedestals/ bases of toilets.	17.55	Sqm	Rs.179.25/-		
6	Carriage of cement and reinforcement from; i. Ganderbal to Baltal by M.T. ii. Baltal to enroute camps by head load a. Ponies b. Porters	01 22 15	Trip No. No.	RTQ RTQ RTQ		

7	Carriage of stone by head load for a lead of 1000 meters	43.5	Cum	RTQ		
8	Carriage of sand and bajree by head load from nearby nallah (average lead 5 km)	7.35	Cum	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of barbed wire fencing to medical camps at enroute Domel to Sangam and near entrance gate of Holy Cave (06 No. of size 25'x 50') including cost of its dismantling and stacking after the culmination of Yatra at nearby SASB Camp for yatra-2017

S.No. 23

Adv.Cost: 0.60 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.50cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	120	Posts	Rs 24.90/-		
2	Providing wood work in frames of false ceiling, partitions etc sawn and fixed in position including carriage upto site of erection. Local wood I. Available Material II. 'New Material (supply also)	1.5 13.2	Cum Cft	RTQ RTQ		
3	1.8m high fencing with 2.5 m Sal bali posts, 30cms girth (min) placed every 2.5 m apart embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 9 horizontal lines and two diagonals of barbed wire 9.38 Kg per 100m (Min) between two posts filled and fixed with G.I staples driven into the posts, including two coats of coal tarring of ballies complete. (Cost of posts, struts, earthwork and concrete to be paid for separately). With G.I barbed wire. I. Available Material II. New Material (supply and carriage also)	228.60 45.72	Rm Rm	Rs.64.30/- RTQ		
4	Dismantling of barbed wire fencing and wooden posts including carriage and stacking at nearest SASB store (Medical Camps of size 25'x50')	05	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting to Prefabricated Toilets/Baths enroute Domail to Holy Cave (75 No.)Yatra - 2017

S.No. 24

Adv.Cost: 0.97 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc	1276	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	1276	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work including carriage of paint (one or more coat)	1276	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/assembling of prefabricated toilets/baths including cost of its dismantling during or after Yatra at Holy Cave (Yatra-2017)

S.No. : 25

Adv.Cost : 2.90 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- vi. Carriage of prefabricated panels and other parts from store to site of installation by head load. vii. Minor repairs such as denting, welding & fixing of aldrops and handles etc. viii. Supply of nuts & bolts etc of required size. ix. Fixing of disposal PVC pipe, bends, tee etc x. Repair / excavation and covering the pits with available material in SASB store (Complete Job)	220	No.	RTQ		
2	Supply of PVC pipes, bends ,tee, sockets of 110 mm dia B-grade. (subject to the actual measurement at site) including carriage upto Holy Cave. a. PVC pipe b. PVC bend c. PVC tee d. PVC socket	100 100 40 40	Rm No. No. No.	RTQ RTQ RTQ RTQ		
4	Dismantling of toilet/baths during or after Yatra (on the instruction of site engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	220	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Oxygen shed and Mortuary shed before Yatra and dismantling the same after Yatra at Holy Cave (02 No. shed of size 10' x10') for Yatra-2017.

S.No. : 26

Adv.Cost: 0.45 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 10.0 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means	20	No.	Rs.24.90/-		
2	Fixing wood work in frames of false ceiling, partitions etc sawn and fixed in position and carriage. Budloo/Fir wood.(in the shape of truss)	1.34	Cum	Rs.12775.5/-		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required including carriage from near by store. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	90	Sqm	Rs.219.82/-		
4	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet.	170	Rm	Rs.7.05/-		
5	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking/ carriage of material within 50 meter lead of G.S. sheet.	90	Sqm	Rs.62.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection & dismantling of railing along the stairs, erection and dismantling of entrance gate at Holy Cave. (Yatra-2017)

S.No. : 27

Adv.Cost: 0.90 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Carriage from store and laying of G.I pipes 40mm dia and posts complete excluding the cost of pipes and posts(for railing along the stairs)	1620	Rm	Rs.27.40/-		
2	Carriage and erection e of Mild Steel entrance gate before Yatra including cost of its dismantling and proper stacking in store after Yatra.	01	No.	RTQ		
3	Dismantling and carriage of G.I pipes from stairs to SASB store.	1620	Rm	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of BSNL Staff Shed, Labour shed, SASB staff shed and Store for SASB material including dismantling of the same at Holy Cave for Yatra-2017.

S.No. : 28

Adv.Cost: 0.80 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.10 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	46	Nos.	Rs.24.90/-		
2	Fixing and carriage of available steel structure and wood frame for sheds before Yatra and dismantling the same after Yatra .	0.47	Cum	RTQ		
3	Fixing and carriage of corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	259	Sqm	Rs.219.82/-		
4	Taking of door, windows and celestary window shetters including stacking within 50 meter lead.	08	No.	Rs. 55/-		
5	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet.	259	Sqm	Rs. 62.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Shoe rack shed (15'x15'), 01 No. frisking shed (size 8'x8') before Yatra and including cost of dismantling after Yatra at Holy Cave (for yatra-2017)

S.No. : 29

Adv.Cost: 0.50 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 10.0 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	18	Nos.	Rs 24.40/-		
2	Fixing wood work in frames of false ceiling, partitions etc sawn and fixed in position. Old wood New wood (carriage upto Holy cave)	0.94 12.6	Cum Cft	Rs.12755.75/ RTQ		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required including carriage also. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	70	Sqm	Rs.219.82/-		
4	Supply and carriage of ply wood (upto Holy Cave) 6mm thick for making the racks for keeping shoes. (8'x4').	160	Sft	RTQ		
5	Dismantling wood work in frames, trusses, purlins and rafters upto 10 m span and 5 meter height including stacking material within 50 meter lead of sectional area below 40 sqm.	130	Rm	Rs.7.05/-		
6	Dismantling roofing including ridges, hips, valleys and gutters etc and	70	Sqm	Rs.62.25/-		

	stacking stacking / carriage of material within 50 meter lead of G.S. sheet.					
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Cloak Room (14'x14') before Yatra and including cost of dismantling after Yatra at Holy Cave (for yatra-2017)

S.No. : 30

Adv.Cost: 0.50 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes upto 10.0 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mm and lift upto 1.5 mtr in all kinds of soil. By manual means.	12	Nos.	Rs 24.40/		
2	Fixing wood work in frames of false ceiling, partitions etc sawn and fixed in position. Old wood New wood (carriage upto Holy Cave)	0.94 10	Cum Cft	Rs.12755.75/ RTQ		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required including carriage also. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	57.80	Sqm	Rs.219.82/-		
4	Fixing of available material for preparing the luggage racks including carriage (on 3 walls of size 14'x 8')	01	No.	RTQ		
5	Supply and carriage (upto Holy cave) of ply wood 8 mm thick (8'x4') for luggage racks	192	Sft	RTQ		
6	Dismantling wood work in frames, trusses, purlins and rafters upto 10 m span and 5 meter height including stacking material within 50 meter lead of sectional area below 40 sqm	120	Rm	Rs.7.05/-		
7	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking/ carriage of material within 50 meter lead of G.S. sheet.	57.80	Sqm	Rs.62.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting and repair to grill and counting hall at Holy Cave for Yatra-2017

S.No. : 31

Adv.Cost: 0.25 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scraping and sand papering and preparing the surface smooth including necessary repairs to scratches etc complete.	190	Sqm	Rs 6.75/-		
2	Painting of grill with synthetic enamel paint of approved brand & manufacture of required colour to give an even shade(one or more coats on old work).	130	Sqm	Rs 45.60/-		
3	Painting of wall below the grill with epoxy paint of all locations prepared and applied as per manufacture specifications including appropriate priming coat, preparation of surface etc. complete on concrete work.	60	Sqm	Rs.128.95/-		
4	Painting to the counting hall with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade (one or more coats on old wall).	60	Sqm	Rs.45.65/-		
5	Carriage of Paint from Domel Holy Cave by head load. (Porters)	01	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting to Prefabricated Toilets/Baths at Holy Cave (100 No.) Yatra - 2017

S.No. 32

Adv.Cost: 1.30 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc	1702	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	1702	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work including carriage of paint (one or more coat)	1702	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Clearance of snow (with frost) from Helipad and track from helipad to upstairs at Holy Cave for Yatra – 2017.

S.No. : 33

Adv.Cost: 1.80 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Cutting/Clearing snow (with frost) from tracks, manually using picks and shovels including carriage upto dump site for a lead of 100 meter (subject to actual measurement at site)					
	i. Helipad	1872	Cum	RTQ		
	ii. Track from Helipad to upstairs	240	Cum	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Clearance of snow (with frost) from Pandal at Holy Cave for Yatra – 2017.

S.No. : 34

Adv.Cost: 1.63 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Cutting/Clearing snow (with frost) from tracks, manually using picks and shovels including carriage upto dump site for lead of 100 meters (subject to actual measurement at site)	1920	Cum	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Clearance of snow (with frost) from entry stairs and exit stairs at Holy Cave for Yatra – 2017.

S.No. : 35

Adv.Cost: 2.73 lac

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Cutting/Clearing snow (with frost) from tracks, manually using picks and shovels including carriage upto dump site for lead of 100 meters (subject to actual measurement at site.	3212	Cum	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder