

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2018

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no. _____ dated _____)

S. NO.	CONTENT	PAGE (S)
1	Notice Inviting Tender (NIT) for advertisement	2-4
2	Eligibility criteria	5
3	Documents establishing Bidder's eligibility	5
4	Instructions to Bidders	6-8
5	Terms and Conditions of the Contract	8-11
6	Schedule – A (Technical Bid)	12-13
7	Schedule – B (Financial Bid)	14-58



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov-April)

Tele: 0191-2555662. Telefax: 0191-2503399

NOTICE INVITING TENDER

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2018

On behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** having a valid registration, for the execution of various Works mentioned below, at the Baltal, enroute and Holy Cave. These bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **03.03.2018** up to 1400 hours.

S. No.	Name of work	Approx. Cost (in Lac)	Earnest Money Deposit (in Rs)	Class of Contractor	Time of Completion	Cost of bid document
1	Hosting of 02 No. water tank on its existing stages 02 No. motor pumps fixing of chain link fencing sign boards water supply to Pre-fab toilet bathroom and 04 No. pre-fab huts departure lounge and dismantling of same after Yatra-2018.	1.30	2600	D	15 Days	Rs.400/-
2	Restoration work of 02 No. fuel Depot by way of wood work and CGi sheet roofing (complete job) including cost of dismantling/ stacking in store after culmination of Yatra at Neelgrath (2018).	0.35	700	D	7 Days	Rs.100/-
3	Construction of pacca platforms in tentage area for security force tents at level 1 st at Neelgrath Yatra-2018.	1.75	3500	D	15 Days	Rs.500 /-
4	Painting of Prefabricated toilet/ baths at Baltal Base Camp and Rangamoh to Domel including Helipad at Neelgrath (300 nos.) for Yatra-2018	3.00	6000	D	25 Days	Rs.800 /-
5	Repairs/Painting of Pre-fabricated Huts (1- 80 nos), hut No. 81-86 and 87-95, store 2 No. ,bank hut 01 no. chowkidar hut 01 No. ,newly constructed camp directors huts 04 no. at Baltal Yatra-2018.	1.55	3000	D	20 Days	Rs.400/-
6	Agro net partition between Langars and prefabricated Toilets/ baths and partition for ladies toilets/baths at Baltal Base Camp. (Yatra-2018).	0.70	1400	D	15 Days	Rs.200/-
7	Improvement/Clearance of drains inside Baltal Camp and old Helipad area including its reconstruction of damaged dry random rubble stone masonry at Baltal Camp (1500 Rm) Yatra-2018.	0.80	1600	D	15 Days	Rs.200 /-
8	Re-roofing and painting of hanger including 04 No. Prefab hut and Kitchen for Medical Department and dismantling the same after Yatra and carriage of same to safe storage in SASB store at Baltal Camp 2018.	4.15	8300	D	30 Days	Rs.1100/-
9	Construction of shed of size 16'x16' for PDD, 16'x16' for PHE and strengthening of existing cloakroom and labour shed at Baltal (Yatra-2018)	2.25	4500	D	20 Days	Rs.700/-
10	Repair/Re-erection of barbed wire fencing at Baltal Camp, including fencing of Helipad area, STP, PDD area and Medical Camp at Domel SASB store and around 25 No. toilet block in langar stores at Baltal (Yatra - 2018)	4.25	8100	D	30 Days	Rs.1100 /-
11	Assembling of Toilet/ Baths (500 nos.) and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2018 at Baltal Camp.	4.55	9000	D	30 Days	Rs.1100 /-

12	Assembling of Toilet/ Baths (375 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enroute Rang morh to Domel and Neelgrath Helipad area Yatra-2018.	4.35	8700	D	20 Days	Rs.900 /-
13	Levelling of parking area including removal of slips, slides, debris and providing of RBM in slushy portions where ever required (subject to actual cross section) at Baltal. (2018)	2.50	5000	D	15 Days	Rs.1200/-
14	Agronet fencing around hanger 04 No. Prefab huts and medical kitchen for medical department at Helipad area at Baltal (Yatra - 2018).	2.00	4000	D	15 Days	Rs.700 /-
15	Construction of kacha drain on back side of STP and Langars at Baltal (Yatra -2018.	1.00	2000	D	10 Days	Rs.500/-
16	Construction of fire gaps by way of earth work in excavation of Kacha drain on both sides of path at Baltal. (2018)	0.50	1000	D	10 Days	Rs.300 /-
17	Repair/Re-roofing of Pacca toilets at Baltal (Yatra-2018)	1.50	3000	D	15 Days	Rs.200 /-
18	Fixing of Sign Boards in Baltal Camp, Rangh Morh to Domel and Railpathri and dismantling, carriage back to SASB store and stacking properly after Yatra(Yatra-2018)	0.80	1600	D	15 Days	Rs.400 /-
19	Repairs/maintenance of prefab Huts(118 Rooms) 43 No. outsource huts (1No. store size 64' x 16') VVIP hut, hut no. 81-95 ,bank hut, Chowkidar hut 4 No. newly constructed at Baltal for Camp Director & 5 rooms in Camp Director office at Domel. (Yatra-2018)	4.50	9000	D	30 Days	Rs.1100/-
20	Plastering to the R-walls at Holy Cave. (Yatra 2018)	2.84	5700	D	20 Days	Rs.700/-
21	Erection of railing along the stairs erection of Nandi Point railing and painting to the railing including cost of its dismantling after the culmination of Yatra (Yatra - 2018)	1.75	3500	D	15 Days	Rs.400/-
22	Construction of approaches to toilers blocks by way of providing steps in plumb concrete at Holy Cave. (Yatra - 2018)	2.20	4400	D	20 Days	Rs.600 /-
23	Construction of the plinth of 04 Nos. huts at Holy Cave (Yatra - 2018)	1.29	2600	D	15 Days	Rs300 /-
24	Erection of fencing around the Medical Camp by way of MS angle posts and agronet along track from Domel to Holy Cave 05 No. (size 24'.00" x24'.00") at enroute Domel to Holy Cave (Yatra - 2018)	2.75	5500	D	20 Days	Rs.700 /-
25	Erection and carriage of Sign Boards, RD Boards, Informatory Boards (42 Boards) before Yatra including cost of its dismantling and proper stacking in nearby SASB store after Yatra at Panjtarni and enroute Brarimarg to Holy Cave (Yatra-2018)	0.30	600	D	10 Days	Rs.100/-
26	Fabrication, Supply and erection of urinal blocks (02 No.) including cost of its carriage upto site at Holy Cave for Yatra-2018	0.90	1800	D	20 Days	Rs.200/-
27	Carriage of 86 No. toilets/ baths by head load from Baltal to Holy Cave (Yatra - 2018)	4.80	9600	D	20 Days	Rs.1200/-
28	Carriage of 06 No. blocks of Indian Toilets (05 No. toilet in each block) by head load from Baltal to Holy Cave (Yatra - 2018)	1.47	3000	D	10 Days	Rs.400/-
29	Carriage of 86 No. toilets/ baths by head load from Baltal to Panjtarni (Yatra - 2018)	3.10	6200	D	15 Days	Rs.800/-

30	Carriage of 17 No. toilets/ baths by head load from Baltal to Brarimarg and Sangam (Yatra - 2018)	0.75	1500	D	10 Days	Rs.200/-
31	Stage contract for the snow clearance (with frost) from entry stairs and exit stairs before the commencement of Yatra at Holy Cave. (Yatra - 2018)	-	5000	D	20 Days	Rs.500/-
32	Stage contract for the snow clearance (with frost) from Pandal, huts site, shed site, cloak room, EAC and other required sites before the commencement of Yatra at Holy Cave. (Yatra - 2018)	-	5000	D	20 Days	Rs.500/-

2. Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from 9.30 AM to 5.00 PM, on any working day (Monday-Saturday) up to **28.02.2018** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
3. The Tender, duly completed, along with Earnest Money Deposit in the form of CDR in favour of Chief Accounts Officer, Shri Amarnathji Shrine Board payable at Jammu / Srinagar, must reach latest by **1400 hours on 03.03.2018** The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through courier/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reason.
4. The Technical bid shall be opened at **10 am on 05.03.2018** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the Agencies/ Bidders who may wish to be present on the occasion.
5. Not more than three Bid documents shall be issued to a single bidder.
6. In case the last date of receipt of Bid happens to be a holiday, the Bid shall be received on the next working day up to 1400 hours.
7. The successful bidder is bound to enter into an Agreement with General Manager (Works) SASB, within fifteen days from the date of the issue of Letter of Allotment of Work.

No: SASB/NIT/2018/2016/11
Dated: 05.02.2018

Sd/-
General Manager (works)
Shri Amarnathji Shrine Board

II ELIGIBILITY CRITERIA

The Bidder must be a Contractor (registered with PWD J&K) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process:

- 2.1 Average Annual Turnover during the last three years, ending 31st March of the previous financial year (i.e. 2014-15, 2015-16, 2016-17), should be 30% of the advertised cost.
- 2.2 The bidder should have an experience of having successfully completed similar works during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-
 - a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or
 - b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or
 - c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.
- 2.3 The Bidder should not have been blacklisted on an earlier occasion by any of the State Government Organizations, State Autonomous Bodies or Local Bodies/ Municipalities.

III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

- 3.1 Registration Certificate authenticating the same.
- 3.2 Certified copies of Annual Turnover from Bank
- 3.3 Certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works, for fulfilling the eligibility criteria.
- 3.4 Certified copy of PAN Card.
- 3.5 Certified copy of GSTIN.
- 3.6 General Profile of the Bidder.
- 3.7 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect at any time, the Earnest Money Deposit shall stand forfeited.

IV. **INSTRUCTIONS TO BIDDERS:**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from 9.30 AM to 5.00 PM on any working day (Monday-Saturday) till 28.02.2018 on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), J&K.
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of _____ Yatra 2018**” and “**Financial Bid for the work of _____ Yatra 2018**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of _____ (Yatra 2018)**” mentioning **NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The bids, duly completed, along with an Earnest Money Deposit (EMD) of amount prescribed in the DNIT (Rs. _____ only) in form of Demand Draft drawn in favour of FA/ Chief Accounts Officer “Shri Amarnathji Shrine Board” payable at Jammu, must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered Post/ Courier to FA/ Chief Accounts Officer at the aforesaid address, so as to reach latest by **1400 hours 03.03.2018**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by courier/ post.
- 4.4 Bids not accompanied by EMD shall be summarily rejected. The EMD and cost of DNIT should be placed inside the envelope containing the Technical bid. The EMD shall be forfeited if the bidder withdraws his bid during Bid Validity Period (BVP).
- 4.5 It would be deemed that by submitting the bid, the bidder has made complete examination of the DNIT, received all information requested from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 4.8 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid not substantially responsive to the DNIT in every respect will be at bidder’s risk and may result in the rejection of the bid.

- 4.9 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be indicated in words as well as in figures. In case of any variation between amount in figures and words, amount quoted in words shall be taken as authentic.
- 4.10 The rate quoted by the Contractor in item tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.11 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the bidder. The bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.12 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The Chief Executive Officer may, at his discretion, extend the deadline for submission of bids. Any bid received after the last date/ time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.13 Clarifications, if any, may be sought by the bidders so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by Chief Executive Officer, SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on SASB website (www.shriamarnathjishrine.com) and NOT in newspaper(s). The bidders should keep themselves updated on this account.
- 4.14 The Technical Bid shall be opened at **1000 hrs. on 05.03.2018** in the office of General Manager (works) in the presence of the authorized representatives of the bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.15 The Chief Executive Officer, SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.16 The bid should remain valid and open for acceptance for a period (i.e. Bid Validity Period) of 90 days from the last date prescribed for its receipt.
- 4.17 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.

- 4.18 The General Manager (Works) may award the Contract to the bidder whose bid has been evaluated to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible bidder in consideration of work/ services to be executed by the eligible bidder as prescribed in the Contract.
- 4.19 The eligible bidder will have to enter into an Agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the fifteen days of the receipt of Letter of Intent.
- 4.20 Chief Executive Officer, SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reason. Any enquiry after the submission of tender will not be entertained.
- 4.21 Shri Amarnathji Shrine Board shall not be responsible for release of any DD pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the DD's of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

V. TERMS AND CONDITIONS OF THE CONTRACT:

- 5.1 The bidders are required to quote rate above/ below percentage on SSR of 2012 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. However, where it has been mentioned in column V that the 'Rate to be quoted (RTQ)', the bidder should quote rate in Rupees per unit. All rates/ percentages should be quoted in figures and words. The bidders are also to calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 5.2 Bids shall have to be submitted separately for each Work as indicated in the NIT.
- 5.3 The Earnest Money Deposit of the unsuccessful bidders shall be released immediately after the work is awarded to successful bidder.

Imbalanced bids:

- 5.4 All bids (received from bidders) valuing less than 80% of the tendered cost shall be treated as imbalanced bids.
- 5.5 Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money Deposit) in the shape of Demand Draft in favour of FA/ Chief Accounts Officer, SASB with his bid. This Additional Earnest Money Deposit should be equal to the difference between the

bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.

- 5.6 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- | | | |
|-------|---|--|
| (i) | First 3 days of delay | Penalty 1% of contract value. |
| (ii) | 4 th day upto 10 th day | 2% of contract value |
| (iii) | Beyond 10 days | Earnest Money Deposit shall be forfeited and the contract shall automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm. |
- 5.7 Not with standing Clause 5.6 above in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 5.8 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).
- 5.9 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.
- 5.10 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.
- 5.11 The Contractor shall submit pictorial evidence (Photographs) of execution of work (post execution, during execution and after completion of work) with his claim.
- 5.12 The contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 5.13 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.

- 5.14 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the state or Central Government or Local Authority and any other labour law (including rules), regulation, byelaws that may be passed or notification that may be issued under any labour law in future either by the state or the Central Government or the local authority. The contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.
- 5.15 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the contract shall be the sole responsibility of the contractor.
- 5.16 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 5.17 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 5.18 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the law.
- 5.19 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of Letter of Intent (LoI).
- 5.20 General Manager (Works), SASB shall be at liberty to suspend the agreement due to any Force Majeure conditions such as Government regulations, court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.
- 5.21 All disputes and differences between the parties arising out and relating to the agreement to be signed between the General Manager (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 5.22 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the State of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 5.23 The rates quoted by the contractor shall be inclusive of all taxes e.g. (GST etc) that are in vogue.
- 5.24 If during the period of three months from the date of completion, the work - defects which have been caused by bad workmanship, use of inferior materials on the work, the contractors shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General

Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the cost thereof shall be recoverable from the Earnest Money Deposit of the Contractor or from payments due to him.

- 5.25 The Earnest Money Deposit of the successful bidder shall be released after completion of work in full and issue of completion certificate by the DGM (B).

VI Payment Clause:

- 6.1 Payment shall be made to the contractor for complete item of the work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 6.2.1 The payment to the bidder shall be made after successful completion of work within the stipulated time (with specification as per the allotment of contract and subsequent drawl of agreement) after satisfactory use/function of the work during complete Yatra Period.

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND EARNEST MONEY DEPOSIT

S. No.	Particular of item	Details
1	Amount and details of payment towards the cost of DNIT	Rs. (in words):
		Receipt No./ Cheque No:
		Date:
2	Amount and details of Earnest Money Deposit submitted	Rs. (<u>in words</u>):
		DD No.
		Dated:
		In favour of
		Date of issue:
		Issuing Authority:

PART – B: BASIC DETAILS ABOUT THE AGENCY.

i) Name and address of :

Name:

the Agency.

Address:

Phone:

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:
(please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

#	Financial Year	Turnover (Rs.)
1	2013-14	
2	2014-15	
3	2015-16	
4	2016-17	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/ No)

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*
5. Certified copy of GSTIN – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*
7. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility*

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Hosting of 02 No. water tank on its existing stages 02 No. motor pumps, fixing of chain link fencing, sign boards, water supply to Pre-fab toilet bathroom and 04 No. pre-fab huts departure lounge and dismantling of same after at Neelgrath Yatra-2018

S.No.: 01

Adv.Cost: Rs. 1.30 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Mounting of 02 No. water storage tanks on existing stage and 02 No. motor pumps with complete fittings and 15 No. sign boards water purifiers , suggestion boxes etc Water tanks (1000 ltr) Motors pumps Sign boards Water purifier Suggestion box	02 02 15 02 02	No. No. No. No. No.	RTQ RTQ RTQ RTQ RTQ		
2	Fixing of chain link fencing including cost of nuts and bolts and repair to damaged angle posts complete job.	114.86	Sm	Rs.281/-		
3	Providing and fixing of G.I pipes complete work G.I. fittings including trenching and refilling etc. 15mm dia, nominal , bore, medium a. New pipe b. Old pipe available in store	150 150	Mtr Mtr	Rs.133.75/- Rs.12.80/-		
4	Providing and fixing of GI fittings i. 20mm to 15 mm sockets ii. 15mm dia GI Tee iii. 15mm dia Gi union	50 50 30	Each Each Each	Rs18/- Rs.38/- Rs.174/-		
5	Providing and fixing of brass stop cock of approved quality (15mm nominal bore)	05	No.	Rs.224.05/-		
6	Providing and fixing of PTMT Bib cock of approved quality	30	Each	154.35/-		
7	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work (one or more coat).	114.86	Sqm	Rs.45.60/-		
8	Supply and fixing of PVC pipe 100mm dia grade-B including laying and trenching 0.45 meter below ground a. Pipe from 04 No. prefab hut to septic tank (double layer) b. Bent pipe	103.65	mtr	Rs.160/-		

9	Supply of PVC fitting 100 mm dia a. PVC TEE b. PVC Socket c. PVC Bend	15 20 20	No. No. No.	Rs.152/- Rs.85/- Rs.114/-		
10	Cleaning/ washing of departure lounge including washroom and 04 No. Prefab huts including washroom (for two times)	5418	Sft	RTQ		
11	Temporary electrification out of available material in tentage area a. Electrification b. Helper	04 04	No. No.	RTQ RTQ		
12	Supply of plumber during Yatra period for	30	Days	Rs.450/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Restoration work of 02 No. fuel Depot by way of wood work and CGi sheet roofing (complete job) including cost of dismantling/ stacking in store after culmination of Yatra at Neelgrath (2018)

S.No.: 2
Lakh

Adv.Cost: Rs. 0.35

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	16	posts	Rs.124.40/-		
2	Providing Wood work in frames of false ceiling, partitions etc. sawn and fixed in position. Budloo/ Fire wood. a.Old wood b. New Wood	0.85 0.21	M ³ M ³	Rs.12755/- Rs.42755/-		
3	Providing corrugated P.P.G.I sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	81	Sqm	RTQ		
4	Filling empty cement bag with sand/ earth including cost of sewing and strings: excluding cost of bag and earth/ sand	400	Bags	Rs.3.70/-		
5	Supply of empty cement bags	400	No.	RTQ		

6	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 metres height including stacking the material within 50 metres lead of sectional area below 40 square centimetres	136.585	Rm	Rs.7.05/-		
7	Dismantling of PPGI roofing including ridges, hips, valleys and gutters etc. and stacking the material within 100 metres lead .	40.613	Sqm	Rs.62.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: **Construction of pacca platforms in tentage area for security force tents at level Ist at Neelgrath Yatra-2018.**

S.No.: 3

Adv.Cost: Rs.1.75 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	9.05	M ³	Rs.240.45/-		
2	Brick wok with selected F.P.S. Bricks of class designation 75 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12mm deep complete from ground level upto plinth level in cement mortar 1:6 (1 cement : 6 coarse sand).	12.73	M ³	Rs.4635.10/-		
3	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete 50 mm thick with 20mm nominal size stone aggregate Crushed	223	Sm	Rs.307.20/-		
4	15 mm thick plaster on rough side of wall in1:4 ratio (1 cement 4 sand)	29.73	Sm	Rs.183.90/-		
5	Carriage of material a. Bricks 100 km lead vide item No. 2 b. Sand and Bajree 50 km lead vide item No. 3	6072 45.15	1000 No. M ³ .	Rs.256.36/- Rs.418.78		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 20**

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting of Prefabricated toilet/ baths at Baltal Base Camp and Rangamohr to Domel including Helipad at Neelgrath (300 nos.) for Yatra-2018

S.No.: 4

Adv.Cost: Rs. 3.00 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc	62.10	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	62.10	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work (one or more coat)	621	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repairs/Painting of Pre-fabricated Huts (1- 80 nos), hut No. 81-86 and 87-95, store 2 No. ,bank hut 01 no. chowkidar hut 01 No. ,newly constructed camp directors huts 04 no. at Baltal Yatra-2018

S.No.: 5

Adv.Cost: 1.55 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Removing oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth, including necessary repairs to scratches etc. complete.	1952	sqm	Rs 8.80/-		
2	Distemping with Oil bound washable distemper of approved brand and manufacture to give an even shade.	3905	sqm	Rs 31.55/-		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old wood work	121.18	sqm.	Rs 45.65/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: **Agro net partition between Langars and prefabricated Toilets/ baths and partition for ladies toilets/baths at Baltal Base Camp. (Yatra-2018)**

S.No.: 6

Adv.Cost: Rs. 0.70 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil	9.55	Cum	Rs.240.45/-		
2	Supply of steel angle iron posts and struts of required size including bottom to be split/ bend to right angle in opposite direction for 100 cm length and drilling of holes upto 10mm dia complete. Angle size 45x45x6 mm.	731	Kg	Rs.69.60/-		
3	Supply and fixing of Agro-net partition and in front of Ladies Toilets /Baths complete.	3600	Sft	RTQ		
4	Carriage of wood from Ganderbal to site of work at Baltal.	01	trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Improvement/Clearance of drains inside Baltal Camp and old Helipad area including its reconstruction of damaged dry random rubble stone masonry at Baltal Camp (1500 Rm) Yatra-2018.

S.No.: 7

Adv.Cost: Rs. 0.80 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Slip Clearance in soils mixed with moorum / Kankar / shingle / boulders; disposal lead upto 50 metre and lift upto 1.5 mtr.	1500	RM	RTQ		
2	Dry random rubble masonry with hard stone in foundation and plinth using nallah stone without bond stone for a lead of 1 Km	22.50	M ³	Rs.1453.96/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Re-roofing and painting of hanger including 04 No. Prefab hut and Kitchen for Medical Department and dismantling the same after Yatra and carriage of same to safe storage in SASB store at Baltal Camp 2018.

S.No.: 8

Adv.Cost: Rs. 4.15Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Repairs to steel trusses of Hangar including strengthening of truss by way of welding.	700	Kg	RT Q		
2	Dismantling of CGI sheet walls, (front wall) I	52	M ²	Rs.62.25/-		
3	Providing corrugated CGI sheet 63 mm for roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required.	176	Sqm	Rs.757/-		
4	Providing ridges or hips of width 60 cm overall width overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mmdia G.Ilimpet and bitumen washers complete 0.63mm thick with zinc coating not less than 275gm/m ² .	15.24	Rm	Rs.490.90/-		
5	Structural steel work in single section fixed with connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. M.S. Angle 50x50x6 mm	810	Kg	Rs.69.60/-		

6	Providing PVC sheet 2mm thick to vertices.	145.72	Sqm	Rs.376/-		
7	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	375	M ²	Rs.8.80/-		
8	Distemping with Oil bound washable distemper of approved brand and manufacture to give an even shade. Old work (one or more coats)	812.64	Sft	Rs.31.55/-		
9	Painting with synthetic enamel paint of approved quality and manufacturer to give a even shade two or more coats.	428.25	M ²	Rs.67.10/-		
10	a. Refixing of ceiling of Hanger rooms and 04 No. pre-fab huts and medical kitchen damaged in winter with available material and new ply including cost of beading, cornics (complete job). b. Washing /cleaning of hanger and doctor rooms c.	340 340	Sm Sm	RTQ RTQ		
11	Providing 5 mm thick with commercial ply on both faces 6mm thick (panels).	62.44	Sqm	Rs.450/-		
12	(Dismantling after Yatra-2018) a. Dismantling of CGI sheet roofing vertical curved side including (complete including carriage of material to SASB store).	176	M ²	Rs.62.25/-		
13	Re-fixing of corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to	52	M ²	Rs.218.75/-		

	size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only) (front wall of hanger)					
--	---	--	--	--	--	--

Total cost of bid (to be quoted both in figures and words)

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of shed of size 16'x16' for PDD, 16'x16' for PHE and strengthening of existing cloakroom and labour shed at Baltal (Yatra-2018)

S.No.: 9

Adv.Cost: Rs. 2.25Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth Work in excavation by manual means over areas (exceeding 30 cm and upto 1.5 cm in depth 1.5 mt in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in (all Kinds of soil).	3.00	M ³	Rs.240.45/-		
2	Structural steel in single section fixed with connecting plates including cutting hoisting, fixing in position and applying a priming coat of approved steel primer (all complete) angle iron of size 45x45x6.	2400	Kg	Rs.69.60/-		
3	Providing corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm, diameter with bitumen and G-I Limpet washers or with G-I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal vertical or curved surface) excluding the cost of Purlins, rafters. (labour only)	190	Sm	Rs.218.75/-		
4	Repair to doors and windows of existing sheds such as cloakroom, food supply shed, gas stores, labour shed, PDD shed by way of minor repair to joinery work and fitting of fixtures.	20	No.	RTQ		

5	Carriage of material from Ganderbal to Baltal.	01	Trio	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair/Re-erection of barbed wire fencing at Baltal Camp, including fencing of Helipad area, STP, PDD area and Medical Camp at Domel SASB store and around 25 No. toilet block in langar stores at Baltal (Yatra - 2018)

S.No. : 10

Adv. Cost: 4.25

lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	14.00	M ³	Rs.240.45 /-		
2	Supplying of steel angle iron posts and struts of required size including bottom to be split/bent at right angle in opposite direction for 10cm length and drilling holes upto 10mm dia etc. complete.50x50x6.	1500	Kg	Rs.69.60/-		
3	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete (labour only)	1804	Rm	Rs.64.30/-		

4	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete, (Cost of posts, struts, earth work and concrete to be paid for separately). With GI barbed wire.	700	Rm	Rs.153.90/-		
5	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering all works upto plinth level. 1:3:6 (1 cement: 3 course sand:6 graded stone aggregate 40mm nominal size) Crushed	5.73	M ³	Rs.3 552.50/-		
6	Straightening of damaged angles and tightening existing fencing	1000	Kg	RTQ		
7	a. Carriage of material (sand and bajree) by mechanical means avg. lead 5km. b. Carriage of cement barbed wire and angle posts from Srinagar to Baltal (HMV)	7.73 01	M ³ Trip	Rs.127.08/- RTQ		
8	Dismantling of barbed wire fencing and angle iron post including carriage and stacking in SASB store after culmination of Yatra.	2800	Kg	Rs.12.30/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (500 nos.) and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2018 at Baltal Camp.

S.No. : 11

Adv. Cost: 4.55

lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	<p>Assembling of toilets/baths at designated site (before commencement of Yatra) including:-</p> <p>i. A. Indian type toilets: Carriage of pre-fabricated panels and other parts from store to installation site by head load complete including minor repairs such as denting , welding and fixing of aldrops, handles patching of holes and fixing of 04 No. I-type hooks 10mm dia by welding the base of steel commode with toilet base.</p> <p>B. English Type toilets: Carriage of pre-fabricated panels and other parts from store to installation site by head load complete including water supply fittings inside such as angle valves, Jet spray pvc connection, G.I fittings including minor repairs such as denting , welding and fixing of aldrops, handles patching of holes and fixing of 04 No. I-type hooks 10mm dia by welding the base of steel commode with toilet base.(seat cover, flushing cistern tank shall be issued from SASB store).</p> <p>ii. Providing and fixing nuts/ bolts etc of required size to the toilets/bath structure</p>	430	No.	RTQ		

	<p>Base = 16 No. Structure = 26 No. Total = 42 no./Each toilet/bath</p> <p>iii. Laying of disposal PVC pipes, bends, Tees etc outlets/ seats to nearest main sewage line leading to STP.</p> <p>a. English type toilets 70 No. b. Indian type toilets and bathroom 430 No. (Complete Job)</p>					
2	<p>Supply of PVC pipes and other fittings items to toilets/baths and laying under pipe 45 cm in ground;</p> <p>I. PVC pipes(110mm) II. PVC bends(110mm) III. PVC sockets(110mm) IV. PVC Tee(110mm) V. PVC door tee (110mm)</p>	<p>450 200 150 150 15</p>	<p>Rm No. No. No. No.</p>	<p>RTQ RTQ RTQ RTQ RTQ</p>		
3	<p>Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.</p>	51	Cum	Rs.240.45/-		
4	<p>Filling the available earth in proper layers by ramming each layer with heavy blows within the lead of 50 meters.</p>	51	Cum	Rs.102.20/-		
5	<p>Providing of one plumber around the clock basis for the repairs/maintenance of toilets/baths during Yatra period.</p>	60	Days	RTQ		
6	<p>Dismantling of toilets/baths at erection site including plugging of inlets of sewer line with gunny bags and filling of exposed pipe fitting with earth upto 30 cm height to avoid damages in winter season/theft and carriage of material from erection site to store with proper stacking after conclusion of Yatra.</p>	500	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of Toilet/ Baths (375 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enrout Rang morh to Domel and Neelgrath Helipad area Yatra-2018.

S.No.: 12

Adv.Cost: 4.35

lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	<p>Assembling of toilets/baths at designated site (before commencement of Yatra) including:-</p> <p>i. Carriage of prefabricated panels and other parts from store to installation site by M.T.</p> <p>ii. Minor repairs such as denting, welding, patching of holes & fixing of aldrops, tower bolt and handles including welding of seat with 4 No. I-type hook of 10 mm dia mild steel to the base of structure.</p> <p>iii. Providing and fixing nuts/ bolts etc of required size to the toilets/bath structure Base = 16 No. Structure = 26 No. Total = 42 no./Each toilet/bath</p> <p>iv. Laying of disposal PVC pipe, bends, tee etc from seat/outlet upto soakage pit.</p> <p>v. Excavation/ repair to the cess pits including covering of the same with the available material in SASB store.</p> <p>(Complete Job)</p>	375	No.	RTQ		
2	<p>Supply and fixing of PVC pipes and other fittings items to toilets/baths and laying of pipe 45 cm in ground</p> <p>I. PVC pipes(110mm)</p> <p>II. PVC bends(110mm)</p>	500 250	Rm No.	RTQ RTQ		

	III. PVC sockets(110mm IV. PVC Tee	200 150	No. No.	RTQ RTQ		
3	Construction of kacha drain around well type soakage pit by way of excavation of earthwork 1'x1' section as per the instruction o the site engineer.	450	Rm	RTQ		
4	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra.	375	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Levelling of parking area including removal of slips, slides, debris and providing of RBM in slushy portions where ever required (subject to actual cross section) at Baltal. (2018)

S.No. : 13

Adv.Cost: 2.50

lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Slip clearance in soils mixed with moorum kankar / Shingle /boulders, disposal lead upto 50 km lead upto 1.5 M.	800	M ³	Rs.158.95/-		
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 M and lift upto 1.5 M (in all kinds of soils)	14000	%M ²	Rs.1135.95		
3	Carriage of malba from parking to outsource huts 1 Km lead by Mechanical Transport.	250	M ³	Rs.106.29/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Agronet fencing around hanger 04 No. Prefab huts and medical kitchen for medical department at Helipad area at Baltal (Yatra - 2018)

S.No. : 14

Adv. Cost: 2.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	200	No.	Rs.124.90/-		
2	Supplying of steel angle iron posts and struts of required size including bottom to be split/bent at right angle in opposite direction for 10cm length and drilling holes upto 10mm dia etc. complete. Angle size 45x45x6	2000	Kg	Rs.69.60/-		
3	Supply and fixing of agronet of 6 feet height.	9000	Sft	RTQ		
4	Dismantling of fencing and angle iron post including carriage and stacking in SASB store after culmination of Yatra. Mazdoor	24	No.	Rs.300/-		
5	Carriage of material from Ganderbal to Baltal	01	Trip	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of kacha drain on back side of STP and Langars at Baltal (Yatra -2018)

S.No. : 15

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by mechanical means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	675	M ³	Rs.150/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of fire gaps by way of earth work in excavation of Kacha drain on both sides of path at Baltal. (2018)

S.No. : 16

Adv. Cost: 0.50

lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means over areas (exceeding 30 cm and upto 1.5m in depth, 1.5 m in width as well as 10 sqm on Plan) including disposal of excavated earth upto 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	198	Cum	Rs.240.45/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair/Re-roofing of Pacca toilets at Baltal (Yatra-2018)

S.No.: 17

Adv.Cost: Rs. 1.50Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Repairs to steel structure of roofing including replacing of doors of pacca toilet in Block – A, doors available in SASB store.	500	Kg	RTQ		
2	Providing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)	97.02	Sqm	Rs.219.82/-		
3	White washing with lime to give an even shade. New work(three or more coats)	579.64	Sqm	Rs.15.90/-		
4	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade. Old steel work (one or more coats).	182	Sqm	Rs.45.60/-		
5	Brick work with common burnt clay F.P.S. (non – modular) bricks of class designation 75 in foundation and plinth in cement mortar 1:6 (1 cement 6 fine sand)	10.6	M ³	Rs.4540.60/-		
6	15 mm thick cement plaster on the rough side of single or half brick wall of mix (1:4) (1 cement 4 sand).	93.68	Sm	Rs.183.90/-		
7	Supply and fixing of PVC pipes and other fitting items to toilets/ baths. i. PVC pipes	60 25	No. No.	Rs.160/- Rs.114/-		

	ii. PVC Bends	20	No.	Rs.85/-		
	iii. PVC socket	20	No.	Rs.152/-		
	iv. PVC Tee	04	No.	Rs.185/-		
	v. Door					
8	Carriage of material through M.T.					
	a. bricks 100 km lead	5099	No.	Rs.256.30/1000		
	b. Sand 5 km Lead	3.52	M ³	Rs.127.28/-		
9	Carriage of material from Ganderbal to Baltal	01	Trip	Rs.2500/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: **Fixing of Sign Boards in Baltal Camp, Rangh Morh to Domel and Railpathri and dismantling, carriage back to SASB store and stacking properly after Yatra(Yatra-2018)**

S.No.: 18

Adv.Cost: Rs. 0.80 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavating holes up to 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. in all kinds of soil, by manual means.	322	No.	Rs.124.40/-		
2	Carriage of Boards from Baltal to Rangh Morh and Domel before Yatra and after Yatra Tata mobile	02	Days	RTQ		
3	Carriage of Board from Domel to Railpathri Mazdoor	18	No.	RTQ		
4	Fixing of sign boards at proper location Mazdoor	28	No.	RTQ		
5	Dismantling of sign boards after Yatra and stacking in SASB store properly Mazdoor	20	No.	RTQ		
6	Carriage of sign boards from Brarimarg to Domel Mazdoor	18	No.	RTQ		
7	Carriage of boards from Domel and Rangha morh to Store by M.T. (tata mobile days)	02	Days	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repairs/maintenance of prefab Huts(118 Rooms) 43 No. outsource huts (1No. store size 64' x 16') VVIP hut, hut no. 81-95 ,bank hut, Chowkidar hut 4 No. newly constructed at Baltal for Camp Director & 5 rooms in Camp Director office at Domel. (Yatra-2018)

S.No.: 19

Adv.Cost: Rs. 4.50 Lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	<p>Dismantling of jack propping & C.G.I sheets from doors & windows of outsource huts & officers huts at baltal including dusting/cleaning of matting & refixing of canopy of reserve hut at baltal including cleaning the area & separation of bathroom</p> <p>(i)Details of Hut: Outsource hut; 40x2=80Rooms Officer VIP hut No.81-86; 3x2=06Rooms 87-95 =09huts Bank Hut =01hut Inspection Hut =02 Rooms Newly constructed Huts; 4x2 =08Rooms 88A+B =02 hut Store; 16x32 = 02No. Dolmentries Size; 64x16=01 No. Domel Camp Director office cum Residential complex =05 No. Heli Hut =01 No. Medical Store 32x12 =01 No.</p> <p>TOTAL =118Nos</p>	15900	Sft	RTQ		
2	Providing and fixing white vitreous china pedestal type (European type /wash down type)water closet pan.	10	No.	Rs.1407.10/-		
3	Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS:7231,with	15	No.	Rs.898.70/-		

	all fittings and fixtures complete.					
4	Providing and fixing of solid plastic seat cover with lid for pedestal type W.C. Pan complete.	37	No.	Rs.738.85/-		
5	Providing and fixing white vitreous china wash basin including making all connections but excluding cost of fitting (flat back wash basin size 550x400mm).	12	No.	Rs.738.85/-		
6	Providing and fixing unplasticised PVC connection pipe with brass union.(15mm nominal board)	92	No.	Rs. 83.20/-		
7	Providing and fixing CP brass bib cock of approved quality confirming to IS: 8931(15mm nominal bore)	20	No.	Rs.406.50/-		
8	Supply of jet	25	No.	Rs.500/-		
9	Supply and fixing of PVC waste pipe for sink or wash basin including PVC waste fitting complete 32mm dia	77	No.	Rs.72.53/-		
10	Repair to damaged roofs/truss of huts in winter season and ceiling with available ply and new ply, including wood for frame, moulding, bedding, cornics cost of nails and also filling of putty/M-seal to check the leakage etc (complete item)	24400	sft	RTQ		
11	Renewal of glass pans with putty and nails wherever necessary, Float glass pans of thickness 4mm	20.3	Sqm	Rs.684.50/-		
12	Applying priming coat with ready mixed pink or grey primer of approved brand and manufacture on wood work(hard and soft wood)	13382	Sqm	Rs.34.45/-		
13	Supply and fixing of PVC pipe4' dia grade B b. PVC Tee	106.75 35	Rm No.	Rs.160/- Rs.152/-		
14	Carriage/shifting of material from Neelgrath store to Baltal before start of Yatra and resifting of same at Neelgrath store after the culmination of Yatra.					

	a. Before start of Yatra labour with departmentally truck for shifting of material.	10	Trip	RTQ		
	b. Shifting of store from Baltal to Neelgrath after the culmination Yatra labour with departmentally truck for shifting of material.	10	Trip	RTQ		
15	Hand packed stone filling including supply of stone.	23	Cum	Rs.327.05/-		
16	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work up to plinth level. 1:3:6 (1 cement 3 sand 6 graded stone aggregate (nalaha).	5.66	M ³	Rs.3514.30/-		
17	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size stone aggregate					
	Nallah	103.47	M ²	Rs.314.20/-		
18	Carriage of material by M.T. a. Sand Bajree 5 km lead	31.47	M ³	Rs.127.28/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Plastering to the R-walls at Holy Cave. (Yatra - 2018)

S.No. :20

Adv. Cost: 2.84 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	20 mm cement plaster of mix 1:4, 1 cement : 4 coarse and including repair if any.	500	Sqm	Rs.222.90/-		
2	Carriage of cement by mechanical means from Ganderbal to Baltal	01	Trip	RTQ		
3	Carriage of cement by head load from Baltal to Holy Cave.	5950	Kg	RTQ		
4	Carriage of sand by head load for a lead of 6 km from Panjtarni to HolyCave.	12.5	Cum	Rs.2576.93/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of railing along the stairs erection of Nandi Point railing and painting to the railing including cost of its dismantling after the culmination of Yatra (Yatra - 2018)

S.No. :21

Adv. Cost: 1.75 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Laying and fitting of G.I. pipes complete excluding the cost of pipes of 40 mm.	1620	Rm	Rs.27.40/-		
2	Erection of detachable mild steel posts for railing pipes Blacksmith Helper	08 08	No. No.	Rs.450/- Rs.300/-		
3	Erection of Nandi point structure at Holy Cave Blacksmith Helper	02 02	No. No.	Rs.450/- Rs.300/-		
4	Carriage of materials (pipes, gates railing posts) from SASB store to site of work before commencement of Yatra and brought back to the store after the culmination of Yatra Mazdoor	16	No.	Rs.300/-		
5	Dismantling of railing posts and Nandi point structure Blacksmith Helper	03 03	No. No.	Rs.450/- Rs.300/-		
6	Dismantling of G.I. pipes complete excluding the cost of pipe 40 mm	1620	Rm	Rs.13.70/-		
Part :B (Finishing and painting)						
7	Removing of white or colored paint by way of sand papering/ scrapping to give a clear base/ surface.	405	Sqm	Rs.6.75/-		
8	Applying priming with rady mix primer to give an even surface /base	405	Sqm	Rs.27.80/-		

9	Painting with ready mix synthetic paint of approved shade to give an even surface.	405	Sqm	Rs.69.30/-		
10	Carriage of material by M.T. from Ganderbal to Baltal.	01	Trip of LMV	RTQ		
11	Carriage of material by head load from Baltal to Holy Cave.	03	Ponies	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of approaches to toilers blocks by way of providing steps in plumb concrete at Holy Cave. (Yatra - 2018)

S.No. :22

Adv. Cost: 2.20 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in all kinds of soil.	10.62	Cum	Rs.240.45/-		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:4:8 with 40mm nominal size stone).	7.78	Cum	Rs.3042.20/-		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level in 1:3:6 nallah stone.	6.40	Cum	Rs.2251.50/-		
4	Centring and shuttering including strutting, propping etc and removal of form work for foundations, footing and bases of columns.	5.27	Sqm	Rs.179.25/-		
5	Carriage of cement by mechanical transport from Ganderbal to Baltal	01	Trip of LMV	RTQ		
6	Carriage of cement by head load from Baltal to Holy Cave.	3000	Kg	RTQ		
7	Carriage of sand and bajri by head load from Panjtarni to Holy Cave (avg. Lead 6 km).	24.03	Cum	Rs.2543.53/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 2012.**

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of the plinth of 04 Nos. huts at Holy Cave (Yatra - 2018)

S.No. :23

Adv. Cost: 1.29

lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Providing and laying in position cement concrete of specified grade, excluding the const of centring and shuttering all works upto plinth level.	02	Cum	Rs.2143.12/-		
2	Stone filling hand packed in depressions.	3.562	Cum	Rs.327.05/-		
3	Providing and laying stone concrete 1:4:8, 40 mm stone aggregate in plinth.	2.37	Cum	Rs.3042.20/-		
4	Providing cement concrete flooring 1:2:4, 20 mm nominal size with a floating coat of neat cement (50 mm thick).	63.94	Sqm	Rs.370.20/-		
5	Carriage of sand, bajri by head load fo average lead of 6 km (from Panjtarni to Holy Cave)	8.72	Cum	Rs.2543.53/-		
6	Carriage of stones to site of work for 500 Mts avg. Distance.	4.362	Cum	Rs.329.07/-		
7	Carriage of cement by head load from Baltal to Holy Cave	1950	Kg	RTQ		
8	Carriage of cement from Ganderbal to Baltal by M.T.	01	Tripof LMV	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of fencing around the Medical Camp by way of MS angle posts and agronet along track from Domel to Holy Cave 05 No. (size 24'.00" x24'.00") at enroute Domel to Holy Cave (Yatra - 2018)

S.No. :24

Adv. Cost: 2.75 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation upto 0.50 cum including getting out the excavated soil, then returning the soil as requires in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming watering etc disposal of surplus excavated soil as directed within a lead of 50 mtr and lift upto 1.5 mtr in all kinds of soil, by manual means.	80	No.	Rs.24.90/-		
2	Supply of steel angle iron posts and struts of required size including bottom to be split/ bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia etc Complete.	1332	Kg	Rs.69.60/-		
3	Providing and laying in position cement concrete of specified grade excluding cost centring and shuttering in 1:2:4 concrete cement all works upto plinth level.	3.75	Cum	Rs.4397.80/-		
4	Centring and shuttering including strutting, propping, etc removal of from work for foundations, footings and bases of columns	49.35	Sqm	Rs.179.25		
5	Carriage of agronet, cement and angle iron by Mechanical transport from Ganderbal to Baltal.	01	Trip of LMV	RTQ		
6	Carriage of agronet cement and angle iron post by head load from Baltal to Medical Camps at enroute Domel to Holy Cave.	2600	Kg	RTQ		
7	Carriage of sand and bajri by head load for a lead of 6 Km (Avg.)	5.06	Cum	Rs.2543.53/-		

8	Supply and fixing of Agronet along the MS posts (both sides)	5760	Sft	RTQ		
9	Supply and fixing of nuts and bolts for MS posts	50	Kg	RTQ		
10	Dismantling of medical fencing including carriage MS posts the nearest SASB store and agronet to the Baltal store (05 No.Camp).	05	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection and carriage of Sign Boards, RD Boards, Informatory Boards (42 Boards) before Yatra including cost of its dismantling and proper stacking in nearby SASB store after Yatra at Panjtarni and enroute Brarimarg to Holy Cave (Yatra-2018)

S.No. : 25

Adv.Cost : 0.30 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Excavation of holes for Boards and erection of boards at designated site including carriage from store to site of installation and brought back after dismantling to nearby SASB store at Panjtarni .	22	No.	RTQ		
2	Excavation of holes for Boards and erection of boards at designated site including carriage from store to site of installation and brought back after dismantling to nearby SASB store at enroute Lower Brarimarg to Holy Cave via Both tracks (via kali Mata track and via Lower Sangam)	20	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Fabrication, Supply and erection of urinal blocks (02 No.) including cost of its carriage upto site at Holy Cave for Yatra-2018

S.No. : 26

Adv. Cost: 0.90 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Structural steel work welded in built up sections including cutting, hoisting etc. and fixing up in position including applying a priming coat of approved steel primer: (For fabrication of mild steel tubular panels)	660	Kg	RTQ		
2	Providing and fixing PPGI sheets 0.50 mm thick on panels for side walls and roofing etc.	158	Kg	RTQ		
3	Cost of Nuts and Bolts of required sizes for erection of structure.	20	Kg	RTQ		
4	Providing and fixing of white vitreous china flat back of wall corners type lipped front urinal basin of 430x260x350 mm .	08	No.	Rs.1173.10/-		
5	Supply and fitting of GI pipes including all GI fittings	10	Rm	Rs. 115/		
6	Supply and fitting of angle valves (PVC type)	10	No.	RTQ		
7	Supply and fitting of PVC waste pipe for sink or washbasin including PVC waste fitting complete (32 mm dia flexible pipe).	08	No	Rs.72.53/-		
8	Supply and fixing of wash basin with pedestal including one No.pillar tap	02	No.	Rs.1712/-		
9	Providing of BS pedestal from angle iron 25x25x3 mm and MS plate 200x200x4mm including one coat metal primer.	40	Kg	RTQ		
10	Providing base frame of size 66x33mm ms tube with approved quality including making of whole set appropriate/required holes for nuts and bolts.	55	Kg	RTQ		
11	Carriage of material from manufacturing site to Holy Cave and its proper installation at designated site.	02	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

**Name of Work: Carriage of 86 No. toilets/ baths by head load from Baltal to Holy Cave
(Yatra - 2018)**

S.No. :27

Adv. Cost: 4.80 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Carriage of toilets/baths (base, back panel., side panel, roof panel, front panel, nuts & bolts, water closet, cistern and other allied items) by head load from Baltal to Holy Cave and properly stack in piles at the site designated by the site incharge. Toilets/baths	86	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage of 06 No. blocks of Indian Toilets (05 No. toilet in each block) by head load from Baltal to Holy Cave (Yatra - 2018)

S.No. :28

Adv. Cost: 1.47 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Carriage of toilets (base, back panel., side panel, roof panel, front panel, nuts & bolts, water closet, cistern and other allied items) by head load from Baltal to Holy Cave and properly stack in piles at the site designated by the site incharge. Block (05 No. Toilets in each block)	06	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage of 86 No. toilets/ baths by head load from Baltal to Panjtarni (Yatra - 2018)

S.No. :29

Adv. Cost: 3.10 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Carriage of toilets/baths (base, back panel., side panel, roof panel, front panel, nuts & bolts, water closet, cistern and other allied items) by head load from Baltal to Panjtarni and properly stack in piles at the site designated by the site incharge. Toilets/baths	46	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage of 17 No. toilets/ baths by head load from Baltal to Brarimarg and Sangam (Yatra - 2018)

S.No. :30

Adv. Cost: 0.75 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Carriage of toilets/baths (base, back panel., side panel, roof panel, front panel, nuts & bolts, water closet, cistern and other allied items) by head load from Baltal to Brarimarg and properly stack in piles at the site designated by the site incharge. Toilets/baths	12	No.	RTQ		
2	Carriage of toilets/baths (base, back panel., side panel, roof panel, front panel, nuts & bolts, water closet, cistern and other allied items) by head load from Baltal to Sangam and properly stack in piles at the site designated by the site incharge. Toilets/baths	05	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Stage contract for the snow clearance (with frost) from entry stairs and exit stairs before the commencement of Yatra at Holy Cave. (Yatra - 2018)

S.No. :31

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Clearing of snow with frost and gulla cutting in compressed snow from entry stairs and exit stairs at Holy Cave and carriage upto the nearby disposal site.	To be identified at site	Cum	Rs.2.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Stage contract for the snow clearance (with frost) from Pandal, huts site, shed site, cloak room, EAC and other required sites before the commencement of Yatra at Holy Cave. (Yatra - 2018)

S.No. :32

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Clearing of snow with frost and gulla cutting in compressed snow from Pandal, huts site, shed site, cloak room, EAC and other required sites and carriage upto the nearby disposal site.	To be identified at site	Cum	Rs.2.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

