

Shri Amarnathji Shrine Board



Jammu and Kashmir

TENDER DOCUMENT

FOR

**Civil Works at
BALTAL & HOLY CAVE CAMP**

for

Yatra – 2019 (phase 2nd)

Dated 05 .02.2019

CIVIL WORKS AT BALTAL & HOLY CAVE CAMP (PHASE 2ND) FOR YATRA 2019

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no. SASB/Works/2019/ dated: 05.02.2019)

S. No.	CONTENT	PAGE(S)
1.	Notice Inviting Tender (NIT) for advertisement	3-4
2.	Eligibility Criteria	5
3.	Documents establishing Bidder's eligibility	5
4.	Instructions to Bidders	6-8
5.	Terms and Conditions of Contract	8-11
6.	Schedule – A (Technical Bid)	12-13
7.	Schedule – B (Financial Bid)	14



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov - April)

Tele: 0191-2555662, Telefax: 0191-2503399

NOTICE INVITING TENDER

CIVIL WORKS AT BALTAL & HOLY CAVE CAMP (PHASE 2ND) FOR

On behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** having a valid registration, for the execution of various Works mentioned below, at Baltal & Holy Cave Camp. These bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **27.02.2019** up to 1400 hours.

(Rs in lakh)

S. No.	Name of work	Approx. Cost	Earnest Money Deposit (in Rs)	Class of Contractor	Time of Completion	Cost of bid document
1	Construction of 02 no. deep soakage pits to soak the over ground water at Baltal Base Camp	0.70	Rs.1400/-	D	20 Days	Rs.200/-
2	Pre-casting 100 No. R.C.C. Collers/Rings for construction of soakage pits at Baltal.	0.98	Rs.2000/-	D	20 Days	Rs.200/-
3	Providing and fixing of colour coated PPGI sheets roofing to main entrance doors to Camp Director hut at Baltal	1.00	Rs.2000/-	D	20 Days	Rs.200/-
4	Construction of Crate Wall on back side of Camp Directors hut at Holy Cave before Yatra-2019.	1.42	Rs.2800/-	D	15 Days	Rs.300/-
5	Construction/ assembling 01 No. hut for bank staff deployed at Holy Cave including cost of its dismantling and stacking in SASB store at Holy Cave for Yatra-2019 (Room size 14' x 14' with attach washroom 8' x 4').	1.90	Rs.3800/-	D	10 Days	Rs.300 /-
6	Construction of the plinth of 01 No. hut for bank staff deployed at Holy Cave including cost of the dismantling and stacking of PPGI hut in SASB store at Holy Cave for Yatra-2019 (Room size 14' x 14' with attach washroom 8' x 4').	0.55	Rs.1100/-	D	10 Days	Rs.200/-
7	Assembling of 06 Nos. huts for SASB staff, Base Hospital, Officers of Police Department, Medical Officers and Meeting hall / Reserved Hut before Yatra including cost of its Dismantling after the culmination at Yatra-2019 (Holy Cave)	2.86	Rs.5700/-	D	20 Days	Rs.400/-
8	Erection/Assembling of SASB kitchen, SASB store, SASB staff shed, BSNL shed, labour shed, mortuary shed, oxygen shed, EAC shed, frisking shed at entry gate and gate no.2 before the commencement of Yatra including cost of its dismantling and proper stacking after the culmination of Yatra at Holy Cave for Yatra-2019 .	1.00	Rs.2000/-	D	10 Days	Rs.200/-
9	Erection/Assembling of cloak room and shoe rack shed before the commencement of Yatra including cost of its dismantling and proper stacking after the culmination of Yatra at Holy Cave for Yatra-2019 (02 sheds).	0.60	Rs.1200/-	D	10 Days	Rs.200/-
10	Assembling of 01 Nos. hut for Camp Director Lower Holy Cave along with 01 No. shed for kitchen before Yatra including cost of its Dismantling and proper stacking in SASB store after the culmination at Yatra-2019 at Lower Holy Cave	1.00	Rs.2000/-	D	10 Days	Rs.200/-
11	Erection /assembling, carriage and painting of MS Modular Bridge before Yatra and carriage dismantling and stacking after Yatra and erection of the panels as safety panelling to the counting hall after the culmination of Yatra including cost of the collection of the scrap near counting hall platforms and dispose it to the designative site before Yatra -2019	0.36	Rs.700/-	D	10 Days	Rs.100/-
12	Erection of fencing around medical camps before Yatra including cost of its dismantling after Yatra at enroute Domail to Sangam.	0.43	Rs.900/-	D	10 Days	Rs.100/-

13	Construction of big dry stone masonry soakage pit (01 no.) adjoining Pandal for soaking the sewage of all huts and toilets erected in nearby area at Holy Cave Camp.	1.90	Rs.3800/-	D	20 Days	Rs.300/-
14	Repair to the existing way side rest shelters and carriage, erection of PPGI sheet roofing before Yatra including dismantling of the same after Yatra and stacking in the nearby SASB store at enroute Domel to Sangam and S.S. Padi (10 Nos.)	3.20	Rs.6400/-	D	20 Days	Rs.600/-

- Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from 10.00 AM to 4.00 PM, on any working day (Monday-Saturday) upto **25.02.2019** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
- The Tender, duly completed, along with Earnest Money Deposit in the form of Demand Draft in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board payable at Jammu / Srinagar, must reach latest by **1400 hours on 27 .02.2019**. The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through courier/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reason.
- The Technical bid shall be opened at **11. 00 am 28 .02.2019** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the bidders who may wish to be present on the occasion.
- Not more than three bid documents shall be issued to a single bidder.
- In case the last date of receipt of bid happens to be a holiday, the bid shall be received on the next working day up to 1400 hours.
- The successful bidder is bound to enter into an Agreement with General Manager (Works), SASB, within fifteen days from the date of the receipt of Letter of intent.

No: SASB/NIT/W/1129/2019/72
Dated: 05.02.2019

sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

II ELIGIBILITY CRITERIA

The Bidder must be a Contractor (registered with PWD J&K) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process:

- 2.1 Average Annual Turnover during the last three years, ending 31st March of the previous financial year (i.e. 2015-16, 2016-17, 2017-18) should be 30% of the advertised cost.
- 2.2 The bidder should have an experience of having successfully completed similar works during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-
 - a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or
 - b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or
 - c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.
- 2.3 The Bidder should not have been blacklisted on an earlier occasion by any of the State Government Organizations, State Autonomous Bodies or Local Bodies/ Municipalities.

III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

- 3.1 Registration Certificate authenticating the same.
- 3.2 Certified copies of Annual Turnover from Bank
- 3.3 Certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works, for fulfilling the eligibility criteria.
- 3.4 Certified copy of PAN Card.
- 3.5 Certified copy of GSTIN.
- 3.6 General Profile of the Bidder
- 3.7 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect at any time, the Earnest Money Deposit shall stand forfeited.

IV. **INSTRUCTIONS TO BIDDERS:**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from 10.00 AM to 4.00 PM on any working day (Monday-Saturday) till 25.02.2019 on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), J&K.
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of _____ Yatra 2019**” and “**Financial Bid for the work of _____ Yatra 2019**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of _____ (Yatra 2019)**” **mentioning NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The bids, duly completed, along with an Earnest Money Deposit (EMD) of amount prescribed in the DNIT (Rs. _____ only) in form of Demand Draft drawn in favour of FA/ Chief Accounts Officer “Shri Amarnathji Shrine Board” payable at Jammu, must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered Post/ Courier to FA/ Chief Accounts Officer at the aforesaid address, so as to reach latest by **1400 hours 27.02.2019**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by courier/ post.
- 4.4 Bids not accompanied by EMD shall be summarily rejected. The EMD and cost of DNIT should be placed inside the envelope containing the Technical bid. The EMD shall be forfeited if the bidder withdraws his bid during Bid Validity Period (BVP).
- 4.5 It would be deemed that by submitting the bid, the bidder has made complete examination of the DNIT, received all information requested from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 4.8 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid

not substantially responsive to the DNIT in every respect will be at bidder's risk and may result in the rejection of the bid.

- 4.9 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be indicated in words as well as in figures. In case of any variation between amount in figures and words, amount quoted in words shall be taken as authentic.
- 4.10 The rate quoted by the Contractor in item tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.11 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the bidder. The bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.12 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The Chief Executive Officer may, at his discretion, extend the deadline for submission of bids. Any bid received after the last date/ time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.13 Clarifications, if any, may be sought by the bidders so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by Chief Executive Officer, SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on SASB website (www.shriamarnathjishrine.com) and NOT in newspaper(s). The bidders should keep themselves updated on this account.
- 4.14 The Technical Bid shall be opened at **1100 hrs. on 28.02.2019** in the office of General Manager (works) in the presence of the authorized representatives of the bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.15 The Chief Executive Officer, SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.16 The bid should remain valid and open for acceptance for a period (i.e. Bid Validity Period) of 90 days from the last date prescribed for its receipt.

- 4.17 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.
- 4.18 The General Manager (Works) may award the Contract to the bidder whose bid has been evaluated to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible bidder in consideration of work/ services to be executed by the eligible bidder as prescribed in the Contract.
- 4.19 The eligible bidder will have to enter into an Agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the fifteen days of the receipt of Letter of Intent.
- 4.20 Chief Executive Officer, SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reason. Any enquiry after the submission of tender will not be entertained.
- 4.21 Shri Amarnathji Shrine Board shall not be responsible for release of any DD/ CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the DDs/ CDRs of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

V. TERMS AND CONDITIONS OF THE CONTRACT:

- 5.1 The bidders are required to quote rate above/ below percentage on SSR of 2012 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. However, where it has been mentioned in column V that the 'Rate to be quoted (RTQ)', the bidder should quote rate in Rupees per unit. All rates/ percentages should be quoted in figures and words. The bidders are also to calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 5.2 Bids shall have to be submitted separately for each Work as indicated in the NIT.
- 5.3 The Earnest Money Deposit of the unsuccessful bidders shall be released immediately after the work is awarded to successful bidder.
- 5.4 **Imbalanced bids:**
- i. All bids (received from bidders) valuing less than 80% of the tendered cost shall be treated as imbalanced bids.

ii. Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money Deposit) in the shape of Demand Draft in favour of FA/ Chief Accounts Officer, SASB with his bid. This Additional Earnest Money Deposit should be equal to the difference between the bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.

5.5 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:

- | | | |
|-------|---|--|
| (i) | First 3 days of delay | Penalty 1% of contract value. |
| (ii) | 4 th day upto 10 th day | 2% of contract value |
| (iii) | Beyond 10 days | Earnest Money Deposit shall be forfeited and the contract shall automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm. |

5.6 Not with standing **Clause 5.5 above** in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.

5.7 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).

5.8 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.

5.9 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.

5.10 The Contractor shall submit pictorial evidence (Photographs) of execution of work (post execution, during execution and after completion of work) with his claim.

5.11 The contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.

- 5.12 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 5.13 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the state or Central Government or Local Authority and any other labour law (including rules), regulation, byelaws that may be passed or notification that may be issued under any labour law in future either by the state or the Central Government or the local authority. The contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.
- 5.14 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the contract shall be the sole responsibility of the contractor.
- 5.15 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 5.16 The agency shall be solely responsible for **Workmen's Compensation Act, 1923** for payment of **compensation** to **workmen** and their dependant in case of injury and accident (including certain occupational disease) arising out of and in the course of employment and resulting in disablement or death.
- 5.17 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 5.18 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the law.
- 5.19 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of Letter of Intent (LoI).
- 5.20 General Manager (Works), SASB shall be at liberty to suspend the agreement due to any Force Majeure conditions such as Government regulations, court **orders, wars, accidents creating disturbed conditions, terrorist activity**, strikes/riots, civil commotion etc.
- 5.21 All disputes and differences between the parties arising out and relating to the agreement to be signed between the General Manager (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 5.22 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in

the State of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.

- 5.23 The rates quoted by the contractor shall be inclusive of all taxes e.g. (GST etc) that are in vogue.
- 5.24 If during the period of three months from the date of completion, the work - defects which have been caused by bad workmanship, use of inferior materials on the work, the contractors shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the cost thereof shall be recoverable from the Earnest Money Deposit of the Contractor or from payments due to him.
- 5.25 The Earnest Money Deposit of the successful bidder shall be released after completion of work in full and issue of completion certificate by the DGM (P).

VI Payment Clause:

- 6.1 Payment shall be made to the contractor for complete item of the work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 6.2.1 The payment to the bidder shall be made after successful completion of work within the stipulated time (with specification as per the allotment of contract and subsequent drawl of agreement) after satisfactory use/ function of the work during complete Yatra Period.

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND EARNEST MONEY DEPOSIT

S. No.	Particular of item	Details
1	Amount and details of payment towards the cost of DNIT	Rs. (in words):
		Receipt No./ Cheque No:
		Date:
2	Amount and details of Earnest Money Deposit submitted	Rs. <u>(in words)</u> :
		DD/ CDR No.
		Dated:
		In favour of
		Date of issue:
		Issuing Authority:

PART – B: BASIC DETAILS ABOUT THE AGENCY.

- i) Name and address of :
the Agency.

Name: _____

Address: _____

Phone: _____

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:
(please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of 'Documents Establishing Bidder's Eligibility'*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of 'Documents Establishing Bidder's Eligibility'*

#	Financial Year	Turnover (Rs.)
1	2015-16	
2	2016-17	
3	2017-18	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder's Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (in Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/ No)

4. Certified copy of PAN Card - *Para 3.4 of 'Documents Establishing Bidder's Eligibility'*
5. Certified copy of GSTIN – *Para 3.5 of 'Documents Establishing Bidder's Eligibility'*
6. General Profile of the Bidder – *Para 3.6 of 'Documents Establishing Bidder's Eligibility'*
7. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder's Eligibility*

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of the work: Construction of 02 no. deep soakage pits to soak the over ground water at Baltal Base Camp.

Adv. Cost = Rs 0.70 lakh

S. No. 1

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Earth work excavation in foundation, trenches etc hard soil 70% ordinary soak 30% including disposal of material as directed.	42.70	Cum	Rs 300.00/-		
2	Extra for every additional lift of material 1.5 m or part thereof. i. 1 st lift ii. 2 nd lift iii. 3 rd lift	14.2 14.2 14.2	Cum	Rs 52.50/- Rs 105.00/- Rs 157.50/-		
3	RS masonry dry with hard stones of appropriate quantity.	16.00	M3	Rs 1440.50/-		
4	Providing and laying 1:2:4, 20mm nominal size aggregate.	0.70	M3	Rs 4428.90/-		
5	Reinforcement for RCC work by using 10 mm dia bans including straightening, cutting bending and placing in position.	70	Kg	Rs 71.00/-		
6	Providing centering, shuttering for RCC work.	2.30	M2	Rs 372.40/-		
7	Carriage of material by mechanical transport including loading and unloading of material (avg. distance 80 kms) i. Cement ii. Reinforcement	} 01	trip	RTQ		

8	Carriage of Stones from nearest source upto 5 Km	17	M3	RTQ		
	Total cost of bid (to be quoted both in figures and words)					

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

Signature of the Bidder

DGM (B)

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Pre-casting 100 No. R.C.C. Collers/Rings for construction of soakage pits at Baltal.

S. No. 02

Adv. Cost: 0.98 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering . All work upto plinth level.(1:1 ½:3) 1 cement, 1 ½: coarse sand and 3 graded stone aggregate 20 mm nominal size (crusher).	3.64	M ²	Rs 5268.95/-		
2	Centering and shuttering including propping and strutting & removal of same up to plinth level.	130.76	Sqm	Rs 179.25/-		
3	Reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete hot rolled deformed bars.	582	Kg	Rs.71/-		
4	Carriage of sand and bajri from Hariganiwan to Baltal upto 60 Km lead.	4.91	M ³	Rs.477.08/-		
5	Carriage of cement & steel from Kangan to Baltal.	01	Trip of LMV	RTQ		
	Total cost of bid (to be quoted both in figures and words)					

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Providing and fixing of colour coated PPGI sheets roofing to main entrance doors to Camp Director hut at Baltal.

S. No. 03

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Structural steel work welded in built up sections trusses and framed work including cutting, hoisting and fixed up in position and applying priming coat of approved steel primer all complete.	150	Kg	Rs 120.45/-		
2	Providing and fixing pre-coated galvanized iron profile sheets 0.50mm total coated thickness fixed using self drilling/set tapping nuts and bolts & J & L hooks, bolts and nuts of required size etc. complete.	13.94	Sqm	Rs 626/-		
3	Providing and laying in position specified grade cement concrete excluding cost for centering and strutting all work up to plinth level in 1:3:6 mix by using 20 mm N. size crushed aggregates. With all carriages.	3.75	Cum	Rs 4125/-		
4	Centering and shuttering including propping and strutting & removal of same up to plinth level.	9.55	Sqm	Rs 179.25/-		
5	Carriage of all material by mechanical transport from Srinagar to Baltal	01	Trip of LMV	RTQ		

	including loading and unloading of PPGI sheets, cement Sand & Aggregates.					
	Total cost of bid (to be quoted both in figures and words)					

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of Crate Wall on back side of Camp Directors hut at Holy Cave before Yatra-2019.

S.No. : 04

Adv.Cost : 1.42 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Demolishing stone rubble masonry or dry stone masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 mtrs lead	26.34	Cum	Rs.386.90/-		
2	Providing of M.S. crate of size 16'x16' fabricated/ Knitting with 4 mm dia round wire having mesh size 4inch x 4 inch of Indian standard specification.	08	No.	RTQ		
3	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	39	Cum	Rs.240.45/-		
4	Hand packing stone in wire crates excluding cost of crates and stones.	43.31	Cum	Rs.177.70/-		
5	Dry stone masonry (in front surface of wire crate) in hard stone without bond stone in nallah stone.	12.69	Cum	Rs.1304.95/-		
6	Supplying of stones laying in wire crates.	16.97	Cum	Rs.229/-		

7	Carriage of crates by mechanical transport from Ganderbal to Baltal	01	Trip of LMV	RTQ		
8	Carriage of crates by head load from Baltal to Holy Cave.	04	Ponies	RTQ		
9	Carriage of stone by Head load for a lead of 01 km.	25.21	Cum	Rs.571.17/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction/ assembling 01 No. hut for bank staff deployed at Holy Cave including cost of its dismantling and stacking in SASB store at Holy Cave for Yatra-2019 (Room size 14' x 14' with attach washroom 8' x 4').

S.No. : 05

Adv.Cost : 1.90 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Providing and fixing of wood work in frames of false ceiling, walls etc sawn and fixed in position with 2nd class kail wood.	1.50	Cum	Rs.42755.75/-		
2	Providing and fixing percoated galvanized iron profile sheets (size, shape & pitch of corrugation as approved by engineer-in-charge) 0.50mm+/-5% total coated thickness, zinc coating 120 gsm as per IS:277 of TATA, JSW, Jindal brand fixing with self driven /self drilling screws including cost of screws and overlaps/ wastage excluding the cost of purlins and truss etc. (colours to be approved by engineer-in-charge).	89.50	Sqm	Rs. 626/-		
3	Carriage of material by mechanical transport from Ganderbal to Baltal.	01	Trip of LMV	RTQ		

4	Carriage of material by head load from Baltal to Holy Cave. a. Ponies b. Porters	14 16	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of the plinth of 01 No. hut for bank staff deployed at Holy Cave including cost of the dismantling and stacking of PPGI hut in SASB store at Holy Cave for Yatra-2019 (Room size 14' x 14' with attach washroom 8' x 4').

S.No. : 06

Adv.Cost : 0.55 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in all kind of soil.	0.38	Cum	Rs.240.45/-		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:3:6 with 40mm nominal size stone).	1.15	Cum	Rs.3552.50/-		
3	Filling with the stones in the inner side (in between plinth walls) by ramming the layers not more than 50mm.	1.86	Cum	Rs.327.05/-		
4	Centring and shuttering including strutting, propping etc and removal of form work for foundations, footing and bases of columns.	10.45	Sqm	Rs.179.25/-		
5	Providing and laying of cement concrete flooring in 1:2:4 mix including neat coat of cement slurry.	18.50	Sqm	Rs.362.90/-		

6	Providing of 50 mm wide glass strips for flooring	40	Rm	Rs.14/-		
7	Fixing of sanitary items to the washroom of hut including supply of European commode, wash basin with pedestal seat cover with lid, flushing cistern, PVC connection, angle valve and jet spray etc.	01	No.	RTQ		
8	Carriage of material by head load from Baltal to Holy Cave. Ponies	04	No.	RTQ		
9	Carriage of sand and bajri by head load from Panjarni to Holy Cave (avg. Lead 6 km).	2.80	Cum	Rs.2543.53/-		
10	Carriage of stone by Head load for a lead of 0.5 km.	1.86	Cum	Rs.302.42/-		
11	Dismantling of the hut including carriage and stacking of material properly in SASB store after the conclusion of Yatra.	01	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of 06 Nos. huts for SASB staff, Base Hospital, Officers of Police Department, Medical Officers and Meeting hall / Reserved Hut before Yatra including cost of its Dismantling after the culmination at Yatra-2019 (Holy Cave).

S.No. :07

Adv. Cost: 2.86 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Fixing of puf panels/ CGI sheet/ PPGI sheet for the side walls of huts and roofing etc including fixing of doors windows, flooring etc in appropriate position with cost of carriage from the store to site of erection.	560	Sqm	RTQ		
2	Fixing of wood work in false ceiling, wall frames etc Sawn and fixed in position. (huts)	05	No.	RTQ		
3	Fixing of doors to its position of huts including cost of nails or screws	11	No.	RTQ		
4	Fixing of wooden teak ply to the false ceiling and walls (frame work to be paid separately)	3840	Sft	RTQ		
5	A . Providing and fixing white vitreous china pedestal type (European type) water closet pan. B. Fixing white vitreous china pedestal type (European type) water closet pan.	04 04	No. No.	Rs.1407.10/- RTQ		
6	Providing and fixing wash basin (including pedestals)) including	04	No.	Rs.1076.90		

	fittings and brackets, cutting and making good the walls wherever required.					
7	Providing and fixing PTMT/PVC angle Valve for wash basin of approved brand make conforming to As:8931 (15 mm nominal bore).	16	No.	RTQ		
8	Providing and fixing unplasticized PVC connection pipe with brass unions (45 cm length).	16	No.	Rs.83.2/-		
9	Providing and fixing of jet spray	08	No.	RTQ		
10	Providing and fixing of PVC low level flushing cistern with manually controlled device (hand lever) confirming to I.S.7231, with all fittings and fixtures complete. (10 litres capacity-white)	05	No.	Rs.898.70/-		
11	Providing and fixing of solid plastic seat with lid for pedestal type W.C.pan complete (white solid plastic seat with lid)	06	No.	Rs.431.40/-		
12	Providing and fixing of PVC waste pipe (flexible)	08	No.	Rs.72.53/-		
13	Providing and fixing of coupling 32 mm dia.	06	No.	Rs.126/-		
14	Supply of PVC fittings 100 mm dia grade B-pipe.					
	a. PVC pipe 110 mm dia	32	Mtr	RTQ		

	b. PVC socket 110 mm dia	10	No.	RTQ		
	c. PVC bend	10	No.	RTQ		
	d. PVC Tee	10	No.	RTQ		
15	Providing and fixing of G.I. pipes complete with G.I fittings excluding trenching and refilling on 15 mm dia nominal bor.	36	Rm	Rs.115/-		
16	Providing and fixing of hangers with 05 pegs.	12	No.	RTQ		
17	Providing and fixing of electrical items					
	a. Caping casing	120	Rft	RTQ		
	b. Switch 6 Amp	30	No.	RTQ		
	c. Wall Angle holder	12	No.	RTQ		
	d. 5 pin socket	12	No.	RTQ		
	e. Wire	04	No.	RTQ		
	f. Gang box for 3 switch & 01 socket	06	No.	RTQ		
	g. Gang box for 1 switch & 01 socket	06	No.	RTQ		
	h. LED lamp (15 Watt)	12	No..	RTQ		
18	Carriage of material by mechanical transport from Ganderbal to Baltal	01	Trip of LMV	RTQ		
19	Carriage of material by head load from Baltal to Holy Cave.					
	a. Ponies	03	No.	RTQ		
	b. Porters	08	No.	RTQ		
20	Dismantling of teak ply including dismantling of wooden frame of hut.	3840	Sft	RTQ		
21	Dismantling of the PPGI sheets or CGI sheets of huts including carriage and stacking in SASB store	560	Sqm	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/Assembling of SASB kitchen, SASB store, SASB staff shed, BSNL shed, labour shed, mortuary shed, oxygen shed, EAC shed, frisking shed at entry gate and gate no.2 before the commencement of Yatra including cost of its dismantling and proper stacking after the culmination of Yatra at Holy Cave for Yatra-2019.

S.No.08

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.10 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr and lift upto 1.5 mtr in all kinds of soil. By manual means.	70	No.	Rs.24.90/-		
2	Fixing of wood work in frames of false ceiling, partitions etc sawn and fixed in position including carriage upto site of erection from SASB store Budloo/Fir wood.(in the shape of Truss).	2.00	Cum	Rs. 12755.75/-		
3	Fixing of corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I	340	Sqm	RTQ		

	Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required including carriage upto site of erection from SASB store 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)					
4	Dismantling of wooden ballies in parts and struts including stacking and carriage upto SASB store	266	Rm	Rs. 7.05/-		
5	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking/ carriage of material upto nearest SASB store.	340	Sqm	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/Assembling of cloak room and shoe rack shed before the commencement of Yatra including cost of its dismantling and proper stacking after the culmination of Yatra at Holy Cave for Yatra-2019 (02 sheds).

S.No.09

Adv. Cost: 0.60 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Excavating holes upto 0.10 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc. disposal of surplus excavated soil as directed within a lead of 50 mtr and lift upto 1.5 mtr in all kinds of soil. By manual means.	33	No.	Rs.24.90/-		
2	Fixing of wood work in frames of false ceiling, partitions etc sawn and fixed in position including carriage upto site of erection from SASB store Budloo/Fir wood.(in the shape of Truss).	2.00	Cum	RTQ		
3	Fixing of corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets	150	Sqm	RTQ		

	complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required including carriage upto site of erection from SASB store 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only)					
4	Engagement of skilled and semi skilled labour for making the racks of cloakroom with available material including cost of supply if any, (subject to the actual measurement at site) carriage and dismantling (complete job).	01	No.	RTQ		
5	Engagement of skilled and semi skilled labour for making the racks of shoe rack with available material including cost of supply if any, (subject to the actual measurement at site) carriage and dismantling (complete job).	01	No.	RTQ		
6	Dismantling of wooden ballies in parts and struts including stacking and carriage upto SASB store	70	Rm	Rs. 7.05/-		
7	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking/ carriage of material upto nearest SASB store.	150	Sqm	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Assembling of 01 Nos. hut for Camp Director Lower Holy Cave along with 01 No. shed for kitchen before Yatra including cost of its Dismantling and proper stacking in SASB store after the culmination at Yatra-2019 at Lower Holy Cave.

S.No. :10

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Fixing of puf panels/ CGI sheet/ PPGI sheet for the side walls of huts and roofing etc including fixing of doors windows, flooring etc in appropriate position with cost of carriage from the store to site of erection.	140	Sqm	RTQ		
2	Fixing of wood work in false ceiling, wall frames etc Sawn and fixed in position. A. Hut B. Kitchen shed	01 01	No. No.	RTQ RTQ		
3	Fixing of doors to its position of huts including cost of nails or screws	03	No.	RTQ		
4	Providing and Fixing of wooden teak ply to the false ceiling and walls (frame work to be paid separately)	644	Sft	RTQ		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:3:6 with 40mm nominal size stone).	0.15	Cum	Rs.3552.50/-		
6	Filling with the stones in the inner side (in between plinth walls) by ramming the layers not more than 50mm.	0.23	Cum	Rs.327.05/-		
7	Providing and fixing of PVC floor matting to the washroom of hut.	32	Sft	RTQ		

8	Providing and fixing white vitreous china pedestal type (European type) water closet pan.	01	No.	Rs.1407.10/-		
9	Providing and fixing wash basin (including pedestals)) including fittings and brackets, cutting and making good the walls wherever required.	01	No.	Rs.1076.90/-		
10	Providing and fixing PTMT/PVC angle Valve for wash basin of approved brand make conforming to As:8931 (15 mm nominal bore).	02	No.	RTQ		
11	Providing and fixing unplasticized PVC connection pipe with brass unions (45 cm length).	02	No.	Rs.83.2/-		
12	Providing and fixing of jet spray	01	No.	RTQ		
13	Providing and fixing of PVC low level flushing cistern with manually controlled device (hand lever) confirming to I.S.7231, with all fittings and fixtures complete. (10 litres capacity- white)	01	No.	Rs.898.70/-		
14	Providing and fixing of solid plastic seat with lid for pedestal type W.C.pan complete (white solid plastic seat with lid)	01	No.	Rs.431.40/-		
15	Providing and fixing of PVC waste pipe (flexible)	01	No.	Rs.72.53/-		
16	Providing and fixing of coupling 32 mm dia.	01	No.	Rs.126/-		
17	Supply of PVC fittings 100 mm dia grade B-pipe.					

	a. PVC pipe 110 mm dia	03	Mtr	RTQ		
	b. PVC socket 110 mm dia	01	No.	RTQ		
	c. PVC bend	01	No.	RTQ		
18	Providing and fixing of G.I. pipes complete with G.I fittings excluding trenching and refilling on 15 mm dia nominal bor.	04	Rm	Rs.115/-		
19	Providing and fixing of hangers with 05 pegs.	02	No.	RTQ		
20	Carriage of material by mechanical transport from Ganderbal to Baltal	01	Trip of LMV	RTQ		
21	Carriage of material by head load from Baltal to Holy Cave. a. Ponies b. Porters	02 07	No. No.	RTQ RTQ		
22	Dismantling of hut and shed including carriage and stacking in SASB store at Holy Cave after Yatra. a. Hut b. Shed	01 01	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection /assembling, carriage and painting of MS Modular Bridge before Yatra and carriage dismantling and stacking after Yatra and erection of the panels as safety panelling to the counting hall after the culmination of Yatra including cost of the collection of the scrap near counting hall platforms and dispose it to the designative site before Yatra -2019

S.No. : 11

Adv.Cost : 0.36 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Engagement of skilled and semi skilled labour for the Erection /assembling, carriage and painting of MS Modular Bridge of span 5 meters (bridge).	01	No.	RTQ		
2	Providing and laying of cement concrete in 1:2:4 excluding cost of centring and shuttering all works up to plinth level.	0.21	Cum	Rs.4428.90/-		
3	Carriage of cement byn head from Baltal to Holy Cave. Ponies.	01	No.	RTQ		
4	Carriage of sand and Bajree by head load from Panjtarni to Holy Cave.	0.28	Cum	Rs.2543.53/-		
5	Fixing of the prefabricated panels composting with M.S. Tube 50x25x3 mm and PPGI sheet 1 mm thick manually with proper nuts and bolts (supply if required).	45	Sqm	RTQ		
6	Engagement of labour for carriage of safety panels for a lead of 50 meters and for the collection of scrap and dispose it to the site directed	20	No.	Rs.300/-		

	by the site engineer.					
7	Dismantling of the bridge including cost of its carriage up to store and proper stacking at Holy Cave after Yatra.	01	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of fencing around medical camps before Yatra including cost of its dismantling after Yatra at enroute Domail to Sangam.

S.No. : 12

Adv.Cost : 0.43 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder	Amount
I	II	III	IV	V	VI	VII
1	Erection of fencing with MS posts and agronet around the Medical Camps including supply of nuts & bolts and carriage of material from SASB store (Baltal/Brarimarg/ Holy Cave) to site of erection (complete job)	04	No.	RTQ		
2	Dismantling of fencing around the medical camp including carriage and stack proper in nearby store.	04	No.	RTQ		
3	Supply of superior quality agronet.	1920	Sft	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of the work: **Construction of big dry stone masonry soakage pit (01 no.) adjoining Pandal for soaking the sewage of all huts and toilets erected in nearby area at Holy Cave Camp.**

S. No. as per NIT: 13

Adv. Cost = Rs. 1.90 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means cover areas for foundation , drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	84.96	Cum	Rs 240.45/-		
2	a. Extra for lift of 1.5 mtrs. b. Extra for lift upto 3 mtrs	42.48 16.99	Cum Cum	Rs.42.40/- Rs.84.80/-		
3	Dry random rubble masonry with hard stone in foundation and plinth by using nallah stone without bond stone.	37.38	Cum	Rs 1304.45/-		
4	Random Rubble masonry with hard stone in foundation and plinth including levelling up cement concrete 1:6:12 (1 cement: 6 coarse sand :12 graded stone aggregate 20 mm nominal size) at plinth level with cement mortar 1:6 (1 cement : 6 coarse sand).	9.06	Cum	Rs.2583.50/-		

5	Providing and laying in position a specified grade cement concrete excluding the cost of centering and shuttering all work upto plinth level in 1:2:4 by using 20 mm nominal size aggregates.	0.78	Cum	Rs 4428.90/-		
6	Carriage of cement from Ganderbal to Baltal.	01	Trip of LMV	RTQ		
7	Carriage of sand and bajri by head load from Panjtarni to Holy Cave (6 km lead)	4.04	cum	Rs 2543.53/-		
8	Carriage of stones by head load from nearest source upto site of work (Avg. 500 M)	39.47	cum	Rs 329.07/-		
9	Carriage of cement by head load from Baltal to Holy Cave Camp. (02 bags /pony)	10	Ponies	RTQ		
10	Laying of scrap as frame work for covering the top of soakage pit and covering with partially damaged sheets along with laying of available soil on it. (pit of size 25'x12').	01	No.	RTQ		
	Total Amount					

DGM (Baltal)

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of the work: Repair to the existing way side rest shelters and carriage, erection of PPGI sheet roofing before Yatra including dismantling of the same after Yatra and stacking in the near by SASB store at enroute Domel to Sangam and S.S. Padi (10 Nos.)

S. No. as per NIT: 14

Adv. Cost = Rs. 3.20 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means cover areas for foundation , drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	3.40	Cum	Rs 240.45/-		
2	Providing and laying in position a specified grade cement concrete excluding the cost of centering and shuttering all work upto plinth level in 1:2:4 by using 20 mm nominal size aggregates.	9.20	Cum	Rs 4428.90/-		
3	Centering and shuttering including propping and strutting & removal of same up to plinth level.	44.60	sqm	Rs 179.25/-		
4	Carriage of cement from Ganderbal to Baltal.	01	Trip of LMV	RTQ		
5	Carriage of sand and bajri by head load for lead of 4 Km.	12.40	cum	Rs 1720.33/-		
6	Carriage of cement by head load from Baltal to Holy Cave Camp. (02 bags /pony)	29	Ponies	RTQ		

7	Installation of steel structure/ frame work of way side resting shelter along the track at designated sites from Railpathri to Kali Mata Track and st S.S. Padi including fixed up in positioning and tightening of nuts & bolts etc (complete job).	3050	Kg	RTQ		
8	Fixing of PPGI sheet roofing including levelling fix in position complete.	240	Sqm	RTQ		
9	Carriage of sheets and MS frame structure of resting shelter from Baltal to Enroute Railpathri, Brarimarg and S.S. Padi.	3990	Kg	RTQ		
10	Dismantling of the steel structure, PPGI sheet roofing of way side shelter sheds including carriage and stacking properly in nearby SASB store.	3990	Kg	RTQ		
Total Amount						

DGM (Baltal)

Signature of the Bidder

