

Shri Amarnathji Shrine Board

Jammu and Kashmir

TENDER DOCUMENT

FOR

Civil Works

along

Baltal Axis

for

Yatra - 2019

Dated 21.01.2019

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2019

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no.SASB/Works/ dated .01.2019)

S. NO.	CONTENT	PAGE (S)
1	Notice Inviting Tender (NIT) for advertisement	3-6
2	Eligibility criteria	7
3	Documents establishing Bidder's eligibility	7
4	Instructions to Bidders	8-10
5	Terms and Conditions of the Contract	10-13
6	Schedule – A (Technical Bid)	14-15
7	Schedule – B (Financial Bid)	16-93



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov-April)

Tele: 0191-2555662. Telefax: 0191-2503399

NOTICE INVITING TENDER

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2019

On behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** having a valid registration, for the execution of various Works mentioned below, at the **Neelgrath, Baltal, enroute and Holy Cave**. These bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **11.02.2019** up to 1400 hours.

(Rs in lakh)

S. No.	Name of work	Approx. Cost (in Lac)	Earnest Money Deposit (in Rs)	Class of Contractor	Time of Completion	Cost of bid document
1	Mounting of two no. water tank of 1000 ltrs. Capacity, two no. motor pumps, fixing of chain link fencing, restoration of fuel depot. Construction of ramp at level 1 st to level 2 nd , fixing of pre cast slabs on drains outside departure lounge flooring, restoration of water supply and other allied works at Neelgrath departure lounge including dismantling of same after conclusion of Yatra -2019.	3.50	7000/-	D	25 Days	Rs.600 \-
2	Dismantling of safety panel of departure lounge and re-fixing of panels to convert as temporary room to be utilized during Yatra-2019 Neelgrath.	0.82	1700/-	D	10 Days	Rs. 200 \-
3	Dismantling of CGI sheet rooms and re-fixing to Departure lounge as Safety Panel after Yatra-2019 Neelgrath.	1.00	2000/-	D	10 Days	Rs. 300 \-
4	Construction of fire gaps by way of earth work in excavation of Kacha drain on both sides of path at Baltal. (2019).	0.50	1000/-	D	10 Days	Rs.200 \-
5	Laying of RBM in fire gaps at Baltal base camp for Yatra -2019.	0.50	1000/-	D	10 Days	Rs. 200/-
6	Improvement/Clearance of drains inside Baltal Camp and old Helipad area at Baltal Camp (1500 Rm) (Yatra-2019).	0.49	1000/-	D	10 Days	Rs.100/-
7	Agronet fencing around Hanger, 04 No. Prefab huts and Kitchen for Medical Department at Helipad area including dismantling the same after Yatra at Baltal (Yatra - 2019).	0.43	900/-	D	10 Days	Rs100 \-
8	Agro net partition between Langars and Prefabricated Toilets/Baths at Baltal Camp for (Yatra -2019)	0.21	500/-	D	06 Days	Rs 100./-
9	Levelling of parking area by way of surface dressing at Baltal	1.00	2000/-	D	10 Days	Rs. 300 \-
10	Providing and fixing Vitrified Tile non skid type to 37 No. Bathrooms at Baltal Camp and Domel .	2.30	4600/-	D	20 Days	Rs.600 \-
11	Repair/Re-erection of barbed wire fencing at Baltal Camp, including fencing of Helipad area, STP and Langar stores Domel Grave yard in CRPF area and SASB store dismantling the same after (Yatra - 2019)	3.30	6600/-	D	20 Days	Rs.600 \-
12	Fixing of Sign Boards in Baltal Camp, Neelgrath Ranga Morh to Domel Railpathri and dismantling, carriage back to SASB store and stacking properly after Yatra(Yatra-2019)	1.00	2000/-	D	10 Days	Rs. 300 \-

13	Fixing of M.S Jacks and CGI sheets to doors and windows to all the Huts for 148 No. rooms from Neelrath to Domel (Baltal Camp)	0.99	2000/-	D	10 Days	Rs.200 /-
14	Providing one No. Plumber and one no. Electrician for maintenance of water supply and Electrification during yatra period at, Baltal and Domel for (Yatra-2019).	0.60	1200/-	D	45 Days	Rs.200 /-
15	Dismantling of Safety panels of Camp Director Huts before Yatra and construction of two rooms for Medical Department and two for security forces and dismantling after Yatra and refixing the same as safety panel to Camp Directors Huts at Domel.	1.05	2100/-	D	10 Days	Rs. 200 /-
16	Dismantling the Safety panel of 04 No. Camp Director Huts 01 No., Reserve Hut 05 No., Newly constructed Huts and re-fixing of same after conclusion after Yatra -2019. At Baltal	2.70	5400/-	D	15 Days	Rs. 600 /-
17	Erection /assembling of Toilet/ Baths (550 nos.)and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sewer line and cost of dismantling / stacking after culmination of Yatra – 2019 at Baltal Camp (including maintenance of sewer lines during Yatra)	4.90	9800/-	D	25 Days	Rs.600 /-
18	Erection/ Assembling and maintenance of Toilet/ Baths (450 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning of soakage pits excavation of earthen disposal pits including cost of dismantling/stacking of Toilets/Baths at enroute Rang morh to Domel and Neelgrath Helipad area Yatra-2019	5.50	11000/-	C,D	25 Days	Rs. 1200/-
19	Repairs/maintenance of Prefab 88 no. Huts consisting of 149 Rooms in Baltal Camp, Hanger, Domail and 39 no. Pucca Toilet during Yatra -2019.	7.20	14400/-	C,D	30 Days	Rs1200/-
20	Repairs/ Painting of Prefabricated Huts at Baltal for Yatra 2019.	1.05	2100/-	D	10 Days	Rs. 200 /-
21	Re-roofing and Painting of Hangar including Dismantling/stacking of roofing after the conclusion of yatra at Baltal. (Yatra-2019.	3.75	7500/-	D	25 Days	Rs.600/-
22	Electrification to outsource Huts, Camp Directors Huts and Reserve Hut by way of laying of cable (underground) at Baltal for (Yatra-2019)	1.50	3000/-	D	15 Days	Rs. 300/-
23	Painting of Prefabricated toilet/ baths at Baltal Base Camp, Rangamorph to Domel including Neelgrath Helipad (300 nos.) for Yatra-2019	3.00	6000/-	D	20 Days	Rs.400/-
24	Plastering to the R-walls at Holy Cave (Yatra - 2019)	3.25	6500/-	D	20 Days	Rs.600 /-
25	Construction of approaches to toilet blocks by way of providing steps and foot path in cement concrete at Upper Holy Cave. (Yatra - 2019)	3.20	6400/-	D	20 Days	Rs.600 /-
26	Erection of railing along the stairs, erection of Nandi Point railing and painting to the railing including cost of its dismantling and proper stacking after the culmination of Yatra (Yatra - 2019)	1.00	2000/-	D	10 Days	Rs. 200 /-

27	Construction of the plinth and flooring to 04 No. Huts for accommodating Medical Officers, Officers of J&K Police, Accounts and Works wing of SASB deployed at Holy Cave for Yatra-2019.	2.60	5200/-	D	15 Days	Rs. 400/-
28	Construction of the approaches to toilet blocks by way of providing steps and foot path in cement concrete at Lower Holy Cave. (Yatra - 2019)	1.85	3700/-	D	15 Days	Rs.300/-
29	Construction of PVC drainage system and inspection chambers for disposal of sewage in various spots at Upper Holy Cave. (Yatra - 2019).	0.96	2000/-	D	10 Days	Rs.200/-
30	Restoration/repairing to the R-wall at Holy Cave adjoining to the base/platform of JE, SASB & Accounts and staff deployed at Holy Cave which has been damaged at Holy Cave. (Yatra - 2019).	0.66	1400/-	D	10 Days	Rs.200/-
31	Repairing / rewriting of Information Boards/signage boards of different sizes including pasting of eco solvent flexes/vinyl on it as proposed by engineer – in-charge and erection, carriage of boards before Yatra and dismantling of boards after Yatra – 2019.	0.42	900/-	D	10 Days	Rs. 100 /-
32	Construction of steps at various places in between hut area and pandal area at Holy Cave.	1.30	2600/-	D	10 Days	Rs.300/-
33	Carriage, assembling and erection in position of PPGI sheet Pandal (16 Room each room size 3.45 x 3.45 mtr) before commencement of Yatra including cost of its dismantling, carriage upto SASB store near counting Hall and proper stacking after the culmination of Yatra- 2019 at Holy Cave.	1.78	3600/-	D	15 Days	Rs.300/-
34	Carriage, assembling and erection in position of PPGI sheet hut of size 3.00x3.00 m with attached washroom of size 1.50 x1.50 m before commencement of Yatra including cost of its dismantling, carriage upto SASB store near counting Hall and proper stacking after the culmination of Yatra- 2019 at Holy Cave.	0.20	400/-	D	07 Days	Rs.100/-
35	Carriage, assembling and erection in position of PPGI sheet hut of size 3.00x3.00 m with attached washroom of size 1.50 x1.50 m before commencement of Yatra including cost of its dismantling, carriage upto SASB store and proper stacking after the culmination of Yatra-2019 at Brarimarg.	0.21	500/-	D	07 Days	Rs.100/-
36	Erection/ assembling of prefabricated toilet/ baths (150 No.) in Upper Holy Cave before the commencement of Yatra including cost of its carriage from store and dismantling with proper stacking in SASB store after the conclusion of Yatra -2019.	2.75	5500/-	D	25 Days	Rs.400/-
37	Erection/ assembling of prefabricated toilet/ baths (150 No.) in Lower Holy Cave before the commencement of Yatra including cost of its carriage from store and dismantling with proper stacking in SASB store after the conclusion of Yatra 2019.	1.50	3000/-	D	20 Days	Rs.300/-

38	Erection/ assembling of prefabricated toilet/ baths (135 No.) at enroute Domel to Sangam before the commencement of Yatra including cost of its carriage and dismantling with proper stacking in SASB store after the conclusion of Yatra 2019.	1.38	2800/-	D	20 Days	Rs.300/-
39	Repair to the prefabricated toilets /baths at Upper and Lower Holy Cave for Yatra 2019. (150 Nos.)	0.60	1200/-	D	10 Days	Rs.200/-
40	Face lifting to the R-walls and grill at Holy Cave for Yatra - 2019	0.77	1600/-	D	10 Days	Rs.200/-
41	Carriage, assembling and erection in position of CR sheet Hut (04 Rooms of size 3.50x4.00meters with attach washroom of size 2.00x1.50 M)) before commencement of Yatra and laying of tile flooring in washrooms including cost of its dismantling, carriage upto SASB store near counting Hall and proper stacking after the culmination of Yatra- 2019 at Holy Cave.	2.75	5500/-	D	15 Days	Rs.600/-
42	Stage contract for the snow clearance (with frost) from entry stairs and exit stairs before the commencement of Yatra at Holy Cave. (Yatra - 2019)	-	5000/-	D	20 Days	Rs.400/-
43	Stage contract for the snow clearance (with frost) from Pandal, huts site, shed site, cloak room, EAC and other required sites before the commencement of Yatra at Holy Cave. (Yatra - 2019)	-	5000/-	D	20 Days	Rs.400/-

- Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from 10.00 AM to 4.30 PM, on any working day (Monday-Saturday) upto **09.02.2019** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
- The Tender, duly completed, along with Earnest Money Deposit in the form of Demand Draft in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board payable at Jammu / Srinagar, must reach latest by **1400 hours on 11.02.2019**. The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through courier/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reason.
- The Technical bid shall be opened at **10.00 am on 12.02.2019** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the bidders who may wish to be present on the occasion.
- Not more than three bid documents shall be issued to a single bidder.
- In case the last date of receipt of bid happens to be a holiday, the bid shall be received on the next working day up to 1400 hours.
- The successful bidder is bound to enter into an Agreement with General Manager (Works), SASB, within fifteen days from the date of the receipt of Letter of intent.

No: SASB/NIT/W/2019/1109/66
Dated: 21.01.2019

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

II ELIGIBILITY CRITERIA

The Bidder must be a Contractor (registered with PWD J&K) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process:

- 2.1 Average Annual Turnover during the last three years, ending 31st March of the previous financial year (i.e. 2015-16, 2016-17, 2017-18) should be 30% of the advertised cost.
- 2.2 The bidder should have an experience of having successfully completed similar works during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-
 - a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.
 - Or
 - b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.
 - Or
 - c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.
- 2.3 The Bidder should not have been blacklisted on an earlier occasion by any of the State Government Organizations, State Autonomous Bodies or Local Bodies/ Municipalities.

III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

- 3.1 Registration Certificate authenticating the same.
- 3.2 Certified copies of Annual Turnover from Bank
- 3.3 Certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works, for fulfilling the eligibility criteria.
- 3.4 Certified copy of PAN Card.
- 3.5 Certified copy of GSTIN.
- 3.6 General Profile of the Bidder
- 3.7 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect during technical evaluation or during execution of work, the following penalties are to be imposed;
 - i. in case the work is allotted to the agency, the contract shall be terminated and work executed through an alternate agency at the risk & cost of the allottee,
 - ii. the Earnest Money Deposit and Security Deposit (in case of imbalanced bid) shall be forfeited,
 - iii. the bidder/ allottee shall be debarred from tendering in SASB for next three years.

IV. **INSTRUCTIONS TO BIDDERS:**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from 10.00 AM to 4.30 PM on any working day (Monday-Saturday) till 09.02.2019 on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), J&K.
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of _____ Yatra 2019**” and “**Financial Bid for the work of _____ Yatra 2019**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of _____ (Yatra 2019)**” **mentioning NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The bids, duly completed, along with an Earnest Money Deposit (EMD) of amount prescribed in the DNIT (Rs. _____ only) in form of Demand Draft drawn in favour of FA/ Chief Accounts Officer “Shri Amarnathji Shrine Board” payable at Jammu, must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered Post/ Courier to FA/ Chief Accounts Officer at the aforesaid address, so as to reach latest by **1400 hours 11.02.2019**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by courier/ post.
- 4.4 Bids not accompanied by EMD shall be summarily rejected. The EMD and cost of DNIT should be placed inside the envelope containing the Technical bid. The EMD shall be forfeited if the bidder withdraws his bid during Bid Validity Period (BVP).
- 4.5 It would be deemed that by submitting the bid, the bidder has made complete examination of the DNIT, received all information requested from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 4.8 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid not substantially responsive to the DNIT in every respect will be at bidder’s risk and may result in the rejection of the bid.
- 4.9 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall

be indicated in words as well as in figures. In case of any variation between amount in figures and words, amount quoted in words shall be taken as authentic.

- 4.10 The rate quoted by the Contractor in item tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.11 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the bidder. The bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identifications. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.12 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The Chief Executive Officer may, at his discretion, extend the deadline for submission of bids. Any bid received after the last date/ time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.13 Clarifications, if any, may be sought by the bidders so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by Chief Executive Officer, SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hosted on SASB website (www.shriamarnathjishrine.com) and NOT in newspaper(s). The bidders should keep themselves updated on this account.
- 4.14 The Technical Bid shall be opened at **1000 hrs. on 12.02.2019** in the office of General Manager (works) in the presence of the authorized representatives of the bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.15 The Chief Executive Officer, SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.16 The bid should remain valid and open for acceptance for a period (i.e. Bid Validity Period) of 90 days from the last date prescribed for its receipt.
- 4.17 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.
- 4.18 The General Manager (Works) may award the Contract to the bidder whose bid has been evaluated to be responsive and who is eligible and qualified to

perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible bidder in consideration of work/ services to be executed by the eligible bidder as prescribed in the Contract.

- 4.19 The eligible bidder will have to enter into an Agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the fifteen days of the receipt of Letter of Intent.
- 4.20 Chief Executive Officer, SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reason. Any enquiry after the submission of tender will not be entertained.
- 4.21 Shri Amarnathji Shrine Board shall not be responsible for release of any DD/ CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the DDs/ CDRs of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

V. TERMS AND CONDITIONS OF THE CONTRACT:

- 5.1 The bidders are required to quote rate above/ below percentage on SSR of 2012 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. However, where it has been mentioned in column V that the 'Rate to be quoted (RTQ)', the bidder should quote rate in Rupees per unit. All rates/ percentages should be quoted in figures and words. The bidders are also to calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 5.2 Bids shall have to be submitted separately for each Work as indicated in the NIT.
- 5.3 The Earnest Money Deposit of the unsuccessful bidders shall be released immediately after the work is awarded to successful bidder.

5.4 Imbalanced bids:

- i. All bids (received from bidders) valuing less than 80% of the tendered cost shall be treated as imbalanced bids.
- ii. Bidders submitting imbalanced bids shall have to attach an additional guarantee (Earnest Money Deposit) in the shape of Demand Draft in favour of FA/ Chief Accounts Officer, SASB with his bid. This Additional Earnest Money Deposit should be equal to the difference between the bid amount quoted by bidder and the cost of the work mentioned in the Notice Inviting Bids.

- 5.5 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- | | | |
|-------|---|--|
| (i) | First 3 days of delay | Penalty 1% of contract value. |
| (ii) | 4 th day upto 10 th day | 2% of contract value |
| (iii) | Beyond 10 days | Earnest Money Deposit shall be forfeited and the contract shall automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm. |
- 5.6 Not with standing **Clause 5.5 above** in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 5.7 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).
- 5.8 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.
- 5.9 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.
- 5.10 The Contractor shall submit pictorial evidence (Photographs) of execution of work (post execution, during execution and after completion of work) with his claim.
- 5.11 The contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 5.12 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 5.13 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the state or Central Government or Local Authority and any other labour law

(including rules), regulation, byelaws that may be passed or notification that may be issued under any labour law in future either by the state or the Central Government or the local authority. The contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.

- 5.14 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the contract shall be the sole responsibility of the contractor.
- 5.15 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 5.16 The agency shall be solely responsible for **Workmen's Compensation Act, 1923** for payment of **compensation to workmen** and their dependant in case of injury and accident (including certain occupational disease) arising out of and in the course of employment and resulting in disablement or death.
- 5.17 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 5.18 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the law.
- 5.19 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of Letter of Intent (LoI).
- 5.20 General Manager (Works), SASB shall be at liberty to suspend the agreement due to any Force Majeure conditions such as Government regulations, court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.
- 5.21 All disputes and differences between the parties arising out and relating to the agreement to be signed between the General Manager (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 5.22 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the State of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 5.23 The rates quoted by the contractor shall be inclusive of all taxes e.g. (GST etc) that are in vogue.
- 5.24 If during the period of three months from the date of completion, the work - defects which have been caused by bad workmanship, use of inferior materials on the work, the contractors shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri

Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the cost thereof shall be recoverable from the Earnest Money Deposit of the Contractor or from payments due to him.

- 5.25 The Earnest Money Deposit of the successful bidder shall be released after completion of work in full and issue of completion certificate by the DGM (P).

VI Payment Clause:

- 6.1 Payment shall be made to the contractor for complete item of the work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 6.2.1 The payment to the bidder shall be made after successful completion of work within the stipulated time (with specification as per the allotment of contract and subsequent drawl of agreement) after satisfactory use/function of the work during complete Yatra Period.

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND EARNEST MONEY DEPOSIT

S. No.	Particular of item	Details
1	Amount and details of payment towards the cost of DNIT	Rs. (in words):
		Receipt No./ Cheque No:
		Date:
2	Amount and details of Earnest Money Deposit submitted	Rs. (in words):
		DD/ CDR No.
		Dated:
		In favour of
		Date of issue:
		Issuing Authority:

PART – B: BASIC DETAILS ABOUT THE AGENCY.

i) Name and address of :
the Agency.

Name: _____

Address: _____

Phone: _____

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:

(please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of 'Documents Establishing Bidder's Eligibility'*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of 'Documents Establishing Bidder's Eligibility'*

#	Financial Year	Turnover (Rs.)
1	2015-16	
2	2016-17	
3	2017-18	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Offer, Work Order, Contract Agreement, Certificate of Completion etc. indicating experience and execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder's Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (in Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/ No)

4. Certified copy of PAN Card - *Para 3.4 of 'Documents Establishing Bidder's Eligibility'*
5. Certified copy of GSTIN – *Para 3.5 of 'Documents Establishing Bidder's Eligibility'*
6. General Profile of the Bidder – *Para 3.6 of 'Documents Establishing Bidder's Eligibility'*
7. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder's Eligibility*

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Mounting of two no. water tank of 1000 ltrs. Capacity, two no. motor pumps, fixing of chain link fencing, restoration of fuel depot. Construction of ramp at level 1st to level 2nd fixing of pre cost slabs on drains outside departure lounge flooring restoration of water supply and other works at Neelgrath departure lounge for yatra – 2019 including dismantling of same after conclusion of Yatra -2019

S.No. :01

Adv. Cost: 3.50 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Mounting of two water tanks of 1000 ltrs. Capacity, two motors and restoration of water a. Plumber b. Black Smith c. Helper	02 days 02 days 02 days	Each Each Each	RTQ RTQ RTQ		
2	Providing and fixing of GI pipe complete with GI fitting excluding cost of pipe .	200	Mtr.	Rs.12.80/-		
3	Supply of GI fitting 15 mm dia. Socket Elbow Union Tee ½"	50 75 30 50	Each Each Each Each	Rs.18/- Rs.26/- Rs.174.80/- Rs.38/-		
4.	Supply and fixing of Stop Cock of approved quality.	05	Each	Rs.224.05/-		
5.	Supply and fixing of PTMT bib cock	40	Each	Rs.154/-		
6.	Providing and fixing of G.I chain link fabric fencing of required in mesh size 50x50mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per direction of engineer-in-charge. Made of G.I wire of dia 4 mm Labour					

	New	114.36 36	Sqm Sqm	RTQ Rs.571/-		
7	Supplying at site Angle Iron posts and struts of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia etc. complete.	45.50	Rm	Rs.73.50/-		
8	Earth work in excavation by manual means over areas (exceeding 30 cm and upto 1.5m in depth, 1.5 m in width as well as 10 sqm on Plan) including disposal of excavated earth upto 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	47.20	M ³	Rs.240.45/-		
9	Disposal of Excavated soil upto ½ km lead by M.T Qty. Vide item No. 9	47.20	M ³	Rs.106.25/-		
10	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shutting all work upto plinth level. 1:3:6 (1 cement: 3 coarse sand :6 graded stone aggregate 40 mm nominal	14.20	M ³	Rs.3552.5/-		
11	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand :4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete 50 mm thick with 20 mm nominal size stone aggregate	74.80	m ²	Rs.314.20/-		

12	Brick work with common burnt clay F.P.S. 9non-modular)bricks of class designation 75 in foundation and plinth in Cement lime mortar 1:1:6 (1 cement:1 lime putty:6 fine sand)	6.00	M ³	Rs.4835.05/-		
13	Extension of sheds of two prefab Huts with PPGI sheets and repair to Benches(Available material)	6	M ²	RTQ		
14	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)	169.60	Rm	Rs.334.40/-		
15	Painting with ready mixed synthetic enamel paint of approved brand and manufacture on wet or patchy portion of plastered surfaces	248.10	m ²	Rs.45.60/-		
16	Washing of departure lounge two times : 1x30mx15 = 450M	52	M ²	RTQ		
17	Providing corrugated P.P.G.I sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc	84.50	M ²	RTQ		

	coating not less than 275gm/m ²					
18	Filling of empty gunny bags with sand.	400	bags	Rs.3.70/-		
19	Supply of empty bags for sand	400	bags	RTQ		
20	Carriage of GI Pipe from Baltal store to Neelgrath including loading and unloading (complete job)	01	trip	RTQ		
21	Engagement of Electrician for lightening to tantage area with available material. a. Electrician b. Helper	04 04	Each Each	RTQ RTQ		
22	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all work upto plinth level 1:3:6 (1 cement 3 coarse sand 6 graded stone aggregate 20 mm nominal size)	1 .50	M ³	Rs.4810.70/-		
23	Reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete hot rolled deformed bars.	151	Kg	Rs.71/-		
24	Centring and shuttering including strutting, propping etc and removal of form for Foundation, footings bases of columns etc for mass concrete 60x2'.0"x3'.6"x3"	12.60	M ²	Rs.179.25/-		
25	Supply and fixing of PVC fitting items: a. PVC Pipe 110mm	60 No.	Each	Rs.160/-		

	b. PVC Bend c. PVC Tee d. PVC Socket	10 No. 10 No. 10 No.	Each Each Each	Rs.114/- Rs.152/- Rs. 85/-		
26	Providing and supply Jet Spray	05	No.	RTQ		
27	Providing and fixing PVC pipe connector.	15	No.	Rs.83.20/-		
28	Providing and fixing PTMT bottle trap for wash basin and sink Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260mm from the centre of the waste coupling 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms	06	No.	Rs.450/-		
29	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931	06.	No	Rs.406.50/-		
30	Supply and fixing of M. Seal to check leakage. Labour : 04 Mazdoor for 02 days =08 days	01 08	Kg Day	RTQ RTQ		
31	Engagement of Plumber for maintenance of Sanitary fitting during Yatra for 30 days	30	Days	RTQ		
32	Carriage of Sand/Bajri by M.T	23.10	Cum	Rs. 127.80/-		
33	Carriage of Bricks vide item no. 12 average lead 100Km =6.00M ³ @ 477/ M ³ =	2862	No.	Rs.1873.54/ 1000		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Dismantling of safety panel of departure lounge and re-fixing of panels to convert as temporary room to be utilized during Yatra-2019 Neelgrath

S.No. :02

Adv. Cost: 0.82 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Dismantling of safety panel of Mild steel and stacking properly.	3105	Kg	Rs.2/-		
2	Fixing of safety panel to convert as in temporary rooms for the use of officials during Yatra i. a.)Vertical wall b) Sides: c) Partition: ii.CGI sheet roofing	196.80 76.5	Sqm Sqm	Rs.220.85/- Rs.211.11		
3	Hire charges of welding set/ gen set including welding rods etc .	04	Each	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Dismantling of CGI sheet rooms and re-fixing to Departure lounge as Safety Panel after Yatra-2019 Neelgrath

S.No. :03

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Dismantling roofing including ridges, hips, valleys and gutters etc and stacking material within 50 meter lead of G.S. sheet..	272.36	Sqm	Rs.62.25		
2	Fixing of safety panel of Mild steel around the Departure Lounge vertically to avoid damages during winter (complete)	270	Sqm	Rs.220.85/-		
3	Fixing propping and bracing the structure for safety of the structure including welding wherever required. i. Blacksmith/carpenter ii. Helper iii. Hire charges of welding set, Genset, Welding rods and POL	 04 08 04	 No. No. No.	 RTQ RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of fire gaps by way of earth work in excavation of Kacha drain on both sides of path at Baltal. (2019)

S.No. :04

Adv. Cost: 0.50 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means over areas (exceeding 30 cm and upto 1.5m in depth, 1.5 m in width as well as 10 sqm on Plan) including disposal of excavated earth upto 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	198	M ³	Rs.240.45		

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Laying of RBM in fire gaps at Baltal base camp for Yatra -2019

S.No. :05

Adv. Cost: 0.50 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing and laying of RBM Nallah be material in fire gaps at Baltal Camp Avg. Lead of material 5Km.	75.64	M ³	Rs.571.28/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Improvement/Clearance of drains inside Baltal Camp and Old Helipad area at Baltal Camp (1500 Rm) (Yatra-2019)

S.No. :06

Adv. Cost: 0.49 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Slip Clearance in soils mixed with moorum / Kankar / shingle / boulders; disposal lead upto 50 metre and lift upto 1.5 mtr	1500	Rm	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Agronet fencing around hanger 04 No. Prefab huts and Kitchen for Medical Department at Helipad area including dismantling the same after Yatra at Baltal (Yatra - 2019)

S.No. :07

Adv. Cost: 0.43 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	19.10	cum	Rs.240.45/-		
2	Fixing of steel angle iron posts and struts 230 No. of required size Angle size 45x45x6 available in SASB store (Labour only)	425	RM	RTQ		
3	Supply and fixing of agro net of 6 feet height.	4800	Sft	RTQ		
4	Dismantling of fencing and angle iron post including carriage and stacking in SASB store after culmination of Yatra.	425	RM	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Agro net partition between Langers and prefabricated Toilets/ Baths and partition for Ladies Toilets/ Baths at Baltal Camp for (Yatra-2019)

S.No. :08

Adv. Cost: 0.21 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	9.55	(SSR)	Rs.240.45/-		
2	Fixing of iron angle posts and struts 110 Nos. of required size including available agro net in SASB store.	3000	Sft	RTQ		
3	Dismantling of fencing and angle iron posts including carriage and stacking in SASB store after yatra.	3000	Sft	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Levelling of parking area by way of surface dressing at Baltal (Yatra-2019)

S.No. :9

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish lead upto 50 m and lift upto 1.5 m in all kinds of soil.	7562	Sqm	Rs.1135.95/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Providing and fixing Vitrified Tile non skit type to 37 Nos. Bathrooms at Baltal Camp and Domel for Yatra-2019.

S.No. :10

Adv. Cost:2.30 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing and laying/ fixing Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1 st quality conforming to IS : 13755 or NITCO, ORIENT,KAJARIA, SOMANY or equivalent make in colour shades except white, Ivory, Grey, Fume red, Brown laid on 20 mm thick bed of cement Mortar 1:4 (1: cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc. including preparing base with cement concrete. (complete job)	154	Sqm	Rs.889.75/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair/Re-erection of barbed wire fencing at Baltal Camp, including fencing of Helipad area, STP and Langar stores Domel Grave yard CRPF area and SASB store dismantling the same after (Yatra - 2019).

S.No. :11

Adv. Cost: 3.30 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	9.55	Cum	Rs.240.45/-		
2	Supplying at site angle iron posts and struts of required size including bottom to be split/bent at right angle in opposite direction for 10cm length and drilling holes upto 10mm dia etc. complete.	823.17	Kg	Rs.69.60/-		
3	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall	1804	Rm	Rs.64.30/-		

	be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete, (Cost of posts, struts, earth work and concrete to be paid for separately). With GI barbed wire.					
4	1.8m high fencing with 2.4 m angle iron 50x50x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post on side only, provided with 12 horizontal lines and two diagonals inter woven with horizontal wires of barbed wire 9.38kg per 100m (min) between two posts fitted and fixed with GI staples, turn buckles etc. complete, (Cost of posts, struts, earth work and concrete to be paid for separately). With GI barbed wire.(for graveyard in CRPF).	120	M	Rs.153.90/-		
5	Providing and laying in position cement concrete of specified grade excluding cost of centring and shuttering all works up to plinth level. 1:2:4 (1 cement: 2 course sand:4 graded stone aggregate 40mm nominal size) Crushed.	9.55	Cum	Rs.4575.50/-		

6	Supply of labour for straightening of damaged angle iron posts and tightening / repair of existing fencing around VVIP Helipad at Baltal	945	Rm	RTQ		
7	Dismantling of barbed wire fencing and angle iron post including SASB store (after culmination of Yatra)	3000	Kg	Rs.12.20/-		
8	Carriage of material (sand and bajri) by mechanical means avg. lead 65 km.	12.89	Cum	Rs.506.23/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Fixing of Sign Boards in Baltal Camp, Ranga Morh to Domel Railpathri and Neelgrath and dismantling, carriage back to SASB store and stacking properly after Yatra(Yatra-2019)

S.No. :12

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Excavation of Holes up to 0.50 cum including getting out the excavated soil and then returning the same as required in layers not exceeding 20 cm depth, including consolidating each deposited layers by watering, ramming and disposal of surplus materials to 50M lead .	322	No.	Rs.124.40/-		
2	Carriage of Sign Boards from Baltal to Rangamorph and Domel.	02	Trip	RTQ		
3	Carriage of Board from Domel to Railpathri.	14	Each	RTQ		
4	Fixing of sign boards at proper location @ 2 mazdoor for 10 boards/day	31	No.	RTQ		
5	Dismantling of sign boards after yatra and stacking in SASB Store properly.	15	No.	RTQ		
6	Carriage of Sign Board from railpatyhri,Brarimarg to Domel	14	No.	RTQ		
7	Cariage of boards from Rangamorph and Domel to SASB store by MT	02	Trip	RTQ		

8	Labour charges for fixing of Water Purifiers at the locations, Steel Benches and Bridges over drains.	24	No.	RTQ		
9	Dismantling of Bridges, Water Purifiers and Steel benches and stacking in SASBstore after yatra -2019	12	No	RTQ		
10	Repair to Damaged Sign Boards by way of welding, Denting and fixing of 01 No. main gate of SASB at near frisking.	03	Day	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Fixing of M.S. Jacks and CGI Sheets to doors and windows to all the Huts for 148 No. rooms from Neelgrath to Domel.

S.No. :13

Adv. Cost: 0.99 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Fixing of M.S. Jacks to 148 No. Rooms from Neelgrath to Domel including greasing of jack, and fixing in position with wooden joist on Bottom And Top.	198	No.	RTQ		
2	Labour charges for fixing of CGI Sheets to Doors and Windows to safe guard from snow in winter.	706.00	M ²	RTQ		
3	Welding of Aldrops of pucca Toilets ,Sheds, Hanger, and Huts, Main Gate, stores and Domel (All structures).	02	Day	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Providing one No. Plumber and one no. Electrician for maintenance of water supply and Electrification during yatra period at Baltal and Domel for (Yatra-2019).

S.No. :14

Adv. Cost: 0.60 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Supply of one No. Plumber for Maintenance of water supply for Yatra Period.	45	Day	RTQ		
2	Supply of one No. Electrician for Maintenance of Electrification for Yatra Period.	45	Day	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Dismantling of Safety Panel of Camp Director Hut before Yatra and construction of two rooms for Medical Department and for security forces and dismantling after Yatra and re fixing the same as safety panel to Camp Directors Hut at Domel.

S.No. :15

Adv. Cost: 1.05 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Dismantling of Safety panel of mild steel and stacking properly of Camp Directors Hut/ Office at Domel.	1877.49	Sm	Rs 2.20/-		
2	Fixing of Safety panel to convert as rooms for security forces and for Medical Deptt. during Yatra period. 04 rooms	162.25	m ²	Rs 252.15/-		
3	Dismantling of roofing including ridges hips valleys and gutters etc. and stacking material with 50m lead.	162.25	m ²	Rs 68.45/-		
4	Fixing of Safety panel of Mild steel around camp director Office vertically to avoid damage.	162.25	m ²	Rs 252.15/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Detailed Estimate for Dismantling the Safety panel of 04 No. Camp Director Huts 01 No. Reserve Hut 05 No. Newly constructed Huts and re- fixing of same after conclusion after Yatra -2019. At Baltal.

S.No. :16

Adv. Cost: 2.70 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Dismantling of safety panel of Mild steel and stacking properly	870.62	Sqm	Rs.62.10/-		
2	Fixing of C.G.I sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead. overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ²	870.62	Sqm	Rs.218.82/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection /assembling of Toilet/ Baths (550 nos.)and fixing of P.V.C pipes with minor repairs (welding and denting) including aligning and clearance of choked sever line and cost of dismantling / stacking after culmination of Yatra – 2019 at Baltal Camp (including maintenance of sever lines during Yatra).

S.No. :17

Adv. Cost: 4.90 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	<p>Assembling of toilets/baths at designated site (before commence of Yatra) including:-</p> <p>I. A. Indian Type Toilets:</p> <p>Carriage of prefabricated panels and other parts from store to site of installation by head load complete including minor repairs such as denting, welding and fixing of a drops, handles patching of holes and fixing of 04 No. I-type hooks 10mm dia by welding of steel command with toilet base.</p> <p>B. European type Toilets:</p> <p>Carriage of prefabricated panels and other parts from store to site of installation by head load complete including water supply fittings inside such as angle valves, jet spray PVC connection, GI fittings</p>					

	<p>including minor repairs such as denting, welding and fixing of a drops, handles patching of holes and fixing of 04 No. I-type hooks 10mm dia by welding the base of steel command with toilet base (seat cover, flushing cistern tank shall be issued from SASB store). Providing and fixing nuts/ bolts etc. Of required size to the toilets/baths structure. Base = 16 No. Structure = <u>26 No.</u> Total=42No/Each Toilet/Bath (Complete Job)</p>					
	<p>a. Erection/dismantling of prefabricated toilet/baths (lying at site.)</p>	315	No.	RTQ		
	<p>b. Carriage of prefabricated toilets/baths from store to site including dismantling fixing and new roofs with nuts and bolts (available at site) and stacking the same after Yatra and binding of stacks with binding wire.</p>	175	No.	RTQ		
	<p>c. Carriage of New EWC from outer store at site including welding of base with seat and carriage back to store after yatra and complete filling such as (G.I.Pipe, jet spray, flush tank seat cover and tee etc) and other</p>	60	No.	RTQ		

	fitting (complete item)					
2	Supply of PVC pipes and other fittings items to toilets/baths and laying under pipe 45 cm in ground; I. PVC pipes(110mm) II. PVC bends(110mm) III. PVC sockets(110mm) IV. PVC Tee(110mm)	360 200 150 150	Rm No. No. No.	Rs.160/- Rs.114/- Rs.85/- Rs.152/-		
3	a. Dismantling of toilets/baths at erection site including plugging of inlets of sewer line with gunny bags and filling of exposed pipe fitting with earth upto 30 cm height to avoid damages in winter season/theft and stacking at site and binding of stacks with binding wire.(Indian Type) b. Dismantling of 60 Nos. EWC and carriage to SASB store and stacking properly.	490 90	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/ Assembling and maintenance of Toilet/ Baths (450 nos.) with minor repairs (welding and denting), fixing of P.V.C pipes, cleaning/ excavation of earthen disposal pits including cost of dismantling carriage of Toilets/Baths to SASB store and stacking properly at enroute Rang morh to Domel and Neelgrath Helipad area Yatra-2019 (and maintenance of sewer line/ cleaning of filled cess pits during Yatra period).

S.No. :18

Adv. Cost: 5.50 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- I. A. Indian Type Toilets: Carriage of prefabricated panels and other parts from store to site of installation by head load complete including minor repairs such as denting, welding and fixing of a drops, handles patching of holes and fixing of 04 No. I-type hooks 10mm dia by welding the base of steel command with toilet base. B. European type Toilets: Carriage of prefabricated panels and other parts from store to site of installation by MT complete including water supply fittings inside such as angle valves, jet spray PVC connection, GI fittings	400	No.	RTQ		

	<p>including minor repairs such as denting, welding and fixing of Al- drops, handles patching of holes and fixing of 04 No. I-hooks hooks 10mm dia by welding the command with toilet base (seat cover, flushing cistern tank shall be issued from SASB store).</p> <p>II. Providing and fixing nuts/ bolts etc. Of required size to the toilets/baths structure.</p> <p>Base = 16 No. Structure = <u>26 No.</u> Total =42No/EachToilet/Bath (Complete Job)</p>	<u>50</u> 450	No.	RTQ		
2	<p>Supply and fixing of PVC pipes and other fittings items to toilets/baths and laying of pipe 45 cm in ground</p> <p>i. PVC pipes(110mm)</p> <p>ii. PVC bends(110mm)</p> <p>iii. PVC sockets(110mm)</p> <p>iv. PVC Tee</p>	<p>450</p> <p>150</p> <p>100</p> <p>150.</p>	<p>Rm</p> <p>No.</p> <p>No.</p> <p>No.</p>	<p>Rs.160/-</p> <p>Rs.114/-</p> <p>Rs.85/-</p> <p>Rs.152/-</p>		
3	Dismantling of toilets/baths at erection site including carriage of material from erection site to store with proper stacking after conclusion of Yatra -2019	450.	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repairs/maintenance of Prefab 88 no. Huts consisting of 149 Rooms in Baltal Camp, Hanger, Domel and 39 no. Pucca Toilet during Yatra -2019.

S.No. :19

Adv. Cost: 7.20 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Dismantling of Jacks including binding(Jack and wood) with binding wire and CGI Sheets of Doors/Windows fixed as safety panels Re-fixing of Canopy of reserve Hut and Dismantling after yatra 2019, sweeping Dusting/ Matting all the Huts and refolding matting and collecting in store after yatra complete job.	139	No.	RTQ		
2	Carriage/shifting of material from Neelgrath store to Baltal before start of Yatra and resifting of same at Neelgrath store after the culmination of Yatra. a. Before start of Yatra labour with departmentally truck for shifting of material. b. Shifting of store from Baltal to Neelgrath after the culmination Yatra labour with departmentally truck for shifting of material.	10	Trip of LMV	RTQ		

3	Repair to damaged roofs / truss of huts in winter season including re-fixing of conopy with required water proofing material such as M.Seal etc of inspection hut including cost of ply for ceiling, beeding, wood, cornic and dismantling the conopy of inspection hut (all huts at Baltal complete item)	24400	Sft	RTQ		
4.	Providing and fixing white vitreous China pedestal type (European type /wash down type) water closet pan.	15.	No	Rs.1407.10/-		
5.	Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete.	15	No.	Rs.898.70/-		
6.	Providing and fixing solid plastic seat cover with lid for pedestal type W.C. Pan complete.	37	No.	Rs.431.40/-		
7	Providing and fixing White Vitreous China wash basin including making all connections but excluding cost of fitting (flat back wash basin size 550 x 400 mm) .	16	No.	Rs.738.85/-		
8	Providing and fixing un plasticised PVC connection pipe with brass union. (15 mm nominal board)	92	No.	Rs.83.20/-		
9	Providing and fixing CP brass bib cock of approved quality confirming to IS : 8931 (15 mm nominal board).	20	No.	Rs.406.50/-		

10	Supply of Jet	85	No.	Rs.500/-		
11	Supply and fixing of PVC waste pipe for sink or wash basin including PVC waste fitting complete. 32mm dia	77	No.	Rs.72.53/-		
12	Providing and fixing CP brass angle Valve for wash basin mixer and geyser of approved make conforming to AS:8931 (15 mm nominal bore).	35	No.	Rs.394.90		
13	Providing and fixing wooden cornices	500	Rft	Rs.17/-		
14	Providing and fixing flat pressed 3 layer particle board medium density exterior grade (grade 1) or graded wood particle board IS : 3087 marked to frame, backing or studding with screws etc complete (frames, backing or studding to be paid separately) 18 mm thick.	14.86	M ²	Rs.665.610		
15	Renewal of glass pans with putty and nails wherever necessary, float glass pans of thickness 4 mm. 80x1'.3"x4'.0 400.00 sft.	37.17	Sqm	Rs.684.50		
16	Painting with synthetic enamel paint of approved brand and manufacturer to give an even shade two or more coats on new work.	1597.00	M ²	Rs.67.10		
17	Supply of mirror of superior make glass 60 x45 cm	15	No.	Rs.350/-		
18	Providing and fixing PTMT bib cock of approved quality and colour 15 mm nominal bore and 86 mm long weighing not less than 88 gm.	170	No.	Rs.154.35		

19	Supply and fixing of a. PVC pipe 4" dia grade B(3mx25) b. PVC Tee	181.75 35.	M ² No	Rs.160/- Rs.152/-		
20	Supply of G.I fitting i. 20 mm to 15 mm sockets ii. 15mm elbow iii. 15mm Tee iv. 15mmUnion	200 100 100 50	No. No. No. No.	Rs.18/- Rs.26/- Rs.38/- Rs.174/-		
21	Engagement of Plumber and Helper for maintenance of water supply to overall Huts/Hangar at Baltal and Domel including fixing of geysers. I. Plumber II. Helper	 15 15	 Days Days	 Rs.450/- Rs.300/-		
22	Supply of locks superior quality (4 lever)	118	No.	Rs.70/-		
23	Hand packed stone filling including supply of stone.	18.80	M ³	Rs.327.05		
24	Removing of guard from Newly constructed 05 Huts 10 rooms	1845	Sft	RTQ		
25	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size stone aggregate Nallah	123.4	M ²	Rs.314.20		
26	Supply of PVC sheet for reserve hut.	20	Sqm	RTQ		
27	Carriage of material by M.T. a. Sand Bajri 5 km lead	31.47	M ³	Rs.127.28		

28	Carriage of material from Ganderbal to site of work	01	Trip of LMV	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised **SSR of 2012.**

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repairs/ Painting of Prefabricated Huts at Baltal for Yatra 2019.

S.No. :20

Adv. Cost: 1.05 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Removing dry Oil bound distemper, water proofing cement paints and the like by scraping the surface, smooth, including necessary repairs to scratches etc. Complete.	912	M ²	Rs 8.80/-		
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade.	2828M ²	sqm	Rs. 31.55/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Re-roofing and Painting of Hangar including Dismantling/stacking of roofing after the conclusion of yatra at Baltal. (Yatra-2019)

S.No. :21

Adv. Cost: 3.75 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Repairs to steel trusses of Hangar including strengthening of truss by way of welding including erection of two no. room 8'x12' in OPD at Baltal.	500	Kg	RTQ		
2	a. Dismantling of CGI sheet walls, roofing prefab huts vertical curved side including opening of doors, windows etc (complete in all respect) b. Front wall	52	M ²	Rs.62.25/-		
3	a. Providing corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to					

	size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only) (Full rate)	204.46	M ²	Rs.757/-		
4	Providing ridges or hips of width 60 cm overall width overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mmdia G.Ilimpet and bitumen washers complete 0.63mm thick with zinc coating not less than 275gm/m ² .	15.24	M	Rs.490.40/-		
5	Providing PVC sheet 2mm thick to vertices	145.72	Sqm	Rs.376/-		
6	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	303	Sqm.	8.800/-		
7	Distempering with Oil bound washable distemper of approved brand and manufacture to give an even shade. Old work (one or more coats)	607	Sqm.	Rs.31.55/-		
8	Painting with synthetic enamel paint of approved brand and manufacturer to give an even shade two or more coats on new work.	157	Sqm	Rs.67.10		
9	a. Refixing of ceiling of Hanger with old ply and cost of new ply including of beeding . cornic and filling of M.Seal to roofs to check the leakage (complete item).	158	Sm	RTQ		
	b. Washing /cleaning of hanger and doctor rooms .	290	Sm	RTQ		

10	Providing 5 mm thick with commercial ply on both faces 6mm thick for rooms.	62.44	Sqm	Rs.450/-		
11	(Dismantling after Yatra-2019) a. Dismantling of CGI sheet walls, roofing prefab huts vertical curved side including opening of doors, windows etc (complete including carriage of material to SASB store)	204.46	Sqm	Rs.62.25/-		
12	Refixing of corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick with zinc coating not less than 275gm/m ² (Labour only) (front wall of hanger)	52	M ²	Rs.219.82/-		
13	Carriage of material from Ganderbal to Baltal.	01	Trip of LMV	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Electrification to outsource Huts, Camp Directors Huts and Reserve Hut by way of laying of cable (underground) at Baltal for (Yatra-2019)

S.No. :22

Adv. Cost: 1.50 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Excavating trenches of required width for pipes, cables, etc. Including excavation for sockets and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming, watering, etc. And disposing of surplus excavated soil as directed, within a lead of 50m.	340	Rm	Rs.119.15/-		
2	i. Supply of two cores 35mm armed cable.	340	Rm	RTQ		
	ii. Bus Bar 100 Amp 4 poles	06	No.	RTQ		
	iii. Thimble.	100	Amp	RTQ		
3	Supply of electricians for electrification to all the huts at Baltal with available material in SASB store.					
	Electrician	10	No.	RTQ		
	Helper	10	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Painting of Prefabricated toilet/ baths at Baltal Base Camp, Rangamoh to Domel including Neelgrath Helipad (300 nos.) for Yatra-2019

S.No. :23

Adv. Cost: 3.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. (10%)	621	Sqm	Rs.6.75/-		
2	Applying priming coat with ready mixed red oxide Zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works. (10%)	621	Sqm	Rs.27.80/-		
3	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work (one or more coat) (100%)	6228	Sqm	Rs.45.60/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Plastering to the R-walls at Holy Cave. (Yatra - 2019)

S.No. :24

Adv. Cost: 3.25 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	20 mm cement plaster of mix 1:4, 1 cement : 4 fine sand and repair if any including neat coat of cement.	500	Sqm	Rs.266.60/-		
2	Carriage of cement by mechanical means from Ganderbal to Baltal	02	Trip	RTQ		
3	Carriage of cement by head load from Baltal to Holy Cave. (2 bags per pony)	43	Ponies	RTQ		
4	Carriage of sand by head load for a lead of 6 km from Panjtarni to Holy Cave.	12.5	Cum	Rs.2543.53		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of approaches to toilet blocks by way of providing steps and foot path in cement concrete at Upper Holy Cave. (Yatra - 2019)

S.No. :25

Adv. Cost: 3.20 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in all kinds of soil.	39.06	Cum	Rs.240.45		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:4:8 with 40mm nominal size stone).	11.72	Cum	Rs.3042.20		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level in 1:3:6 nallah stone.	11.72	Cum	Rs.3552.50		

4	Centring and shuttering including strutting, propping etc and removal of form work for foundations, footing and bases of columns.	58.5	Sqm	Rs.179.25		
5	Carriage of cement by mechanical transport from Ganderbal to Baltal	02	Trip of LMV	RTQ		
6	Carriage of cement by head load from Baltal to Holy Cave. (02 bags/pony)/	45	Ponies	RTQ		
7	Carriage of sand and bajri by head load from Panjtarni to Holy Cave (avg. Lead 6 km).	31.64	Cum	Rs.2543.53		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection of railing along the stairs, erection of Nandi Point railing and painting to the railing including cost of its dismantling and proper stacking after the culmination of Yatra (Yatra - 2019)

S.No. :26

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Laying and fitting of G.I. pipes complete excluding the cost of pipes of 40 mm.	900	Rm	Rs.27.40		
2	Erection of detachable mild steel posts for railing pipes Blacksmith Helper	04 04	No. No.	Rs.450/- Rs.300/-		
3	Erection of Nandi point structure at Holy Cave Blacksmith Helper	02 02	No. No.	Rs.450/- Rs.300/-		
4	Carriage of materials (pipes, gates railing posts) from SASB store to site of work before commencement of Yatra and brought back to the store after the culmination of Yatra Mazdoor	10	No.	Rs.300/-		
5	Dismantling of railing posts and Nandi point structure Blacksmith Helper	03 03	No. No.	Rs.450/- Rs.300/-		
6	Dismantling of G.I. pipes complete excluding the cost of pipe 40 mm	900	Rm	Rs.13.70/-		
Part :B (Finishing and painting)						
7	Removing of white or colored paint by way of sand papering/ scrapping to give a clear base/ surface.	290.23	Sqm	Rs.6.75		

8	Applying priming with ready mix primer to give an even surface /base	290.23	Sqm	Rs.27.80		
9	Painting with ready mix synthetic paint of approved shade to give an even surface.	290.23	Sqm	Rs.69.30		
10	Carriage of material by head load from Baltal to Holy Cave.	02	Ponies	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of the plinth and flooring to 04 No. Huts for accommodating Medical Officers, Officers of J&K Police, Accounts and Works wing of SASB deployed at Holy Cave for Yatra-2019.

S.No. :27

Adv. Cost: 2.60 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in ordinary rockl. (for 02 No. Huts)	0.88	Cum	Rs.441/-		
2	Demolishing of existing (constructed) PCC of thickness not more than 50mm. (for 03 No. Huts).	0.88	Cum	Rs.813/-		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:3:6 with 40mm nominal size stone). With 30% plumb.	6.44	Cum	Rs.2550.35/-		
4	Filling with the available material in the inner side (in between plinth walls) by ramming	21.66	Cum	Rs.327.05/-		

	the layers not more than 50mm.					
5	Centring and shuttering including strutting, propping etc and removal of form work for foundations, footing and bases of columns.	40.15	Sqm	Rs.179.25/-		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level in 1:4:8 nallah stone.	2.4	Cum	Rs.3061.30/-		
7	Providing and laying of cement concrete flooring in 1:2:4 mix including neat coat of cement slurry.	78.06	Sqm	Rs.362.90/-		
8	Providing and laying of ceramic glazed tiles conforming to IS : 1753 of minimum thickness 5 mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalent (Colour and design to be approved by engineer –in-charge) in skirting, rises of steps, floorings etc. in Mortar 1:3 and jointing with grey cement slurry.	20.81	Sqm	Rs.834.20/-		
9	Providing of 50 mm wide glass strips for flooring	219	Rm	Rs.14/-		
10	Carriage of cement by mechanical transport from Ganderbal to Baltal	02	Trip of LMV	RTQ		

11	Carriage of cement, tiles by head load from Baltal to Holy Cave. (02 bags/pony)/	33	Ponies	RTQ		
12	Carriage of sand and bajri by head load from Panjtarni to Holy Cave (avg. Lead 6 km).	14.59	Cum	Rs.2543.53/-		
13	Carriage of stone by Head load for a lead of 0.5 km.	23.60	Cum	Rs.302.42/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of the approaches to toilet blocks by way of providing steps and foot path in cement concrete at Lower Holy Cave. (Yatra - 2019)

S.No. :28

Adv. Cost: 1.85 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in ordinary rock.	18	Cum	Rs.240.45/-		
2	Providing and Laying of soling stone/kankar as sub grade for foot path.	6.75	Cum	Rs.317.75/-		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level in 1:4:8 nallah stone.	4.5	Cum	Rs.3061.30/-		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:3:6	4.5	Cum	Rs.3552.50/-		

	with 40mm nominal size stone).					
5	Dry stone masonry with hard stone in foundation and plinth level with nallah stone.	23.50	Cum	Rs.1305.75/-		
6	Providing and laying of cement concrete coping/DPC in 1:2:4 mix including neat coat of cement slurry.	1.156	Cum	Rs.4428.90/-		
7	Providing of 50 mm wide glass strips for flooring	23	Rm	Rs.14/-		
8	Carriage of cement by mechanical transport from Ganderbal to Baltal	01	Trip of LMV	RTQ		
9	Carriage of cement by head load from Baltal to Holy Cave. (02 bags/pony)/	21	Ponies	RTQ		
10	Carriage of sand and bajri by head load from Panjtarni to Holy Cave (avg. Lead 5 km).	13.71	Cum	Rs.2131.93/-/-		
11	Carriage of stone by Head load for a lead of 0.5 km.	30.25	Cum	Rs.329.07/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of PVC drainage system and inspection chambers for disposal of sewage in various spots at Upper Holy Cave. Yatra - 2019)

S.No. :29

Adv. Cost: 0.96 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in 50% ordinary rock & 50% all kinds of soil.	12	Cum	Rs.340.72/-		
2	Providing and Laying of 6 inch dia PVC pipe – B type (150 mm dia). a. Pipe b. Bend c. Tee d. Socket	82.29 10 05 82	Rm No. No. No.	RTQ RTQ RTQ RTQ		
3	Construction of inspection chambers of clear size 1'-6" x 1'-6"x 1'-6" with 0'-6" thick walls in cement concrete 1:2:4 mix including laying of slab (1'-6"x1'-6") and carriages by both MT	05	No.	RTQ		

	and Head Load upto site (complete job).					
4	Carriage of material by MT	01	Trip of LMV	RTQ		
5	Carriage of material by head load from Baltal to Holy Cave (only for PVC pipes and fittings) a. Porters b. Ponies	09 01	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Restoration/repairing to the R-wall at Holy Cave adjoining to the base/platform of JE, SASB & Accounts and staff deployed at Holy Cave which has been damaged at Holy Cave. (Yatra - 2019)

S.No. :30

Adv. Cost: 0.66 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Demolishing stone rubble masonry manually by Mechanical means including stacking of serviceable material and disposal of in serviceable material within 50 meters lead in cement mortar.	7.732	Cum	Rs.820.45/-		
2	Random Rubble masonry with hard stone in foundation and plinth including levelling up cement concrete 1:6:12 (1 cement: 6 coarse sand :12 graded stone aggregate 20 mm nominal size) at plinth level with cement mortar 1:6 (1 cement : 6 coarse sand). a. With 80% old stone b. With 20%new stone	6.186 1.546	Cum Cum	Rs.2354.50/- Rs.2583.50/-		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level in 1:2:4 nallah stone.	0.138	Cum	Rs.4397.80/-		

4	Carriage of stone by head load for a lead of 0.5 km	1.546	Cum	Rs.329.07/-		
5	Carriage of cement by Mechanical Transport from Ganderbal to Baltal.	01	Trip of LMV	RTQ		
6	Carriage of sand and bajri by head load for a lead of 6 km	3.632	Cum	Rs.2543.53/-		
7	Carriage of cement by head load from Baltal to Holy Cave	07	Ponies	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repairing / rewriting of Information Boards/signage boards of different sizes including pasting of eco solvent flexes/vinyl on it as proposed by engineer – in-charge and erection, carriage of boards before Yatra and dismantling of boards after Yatra - 2019

S.No. :31

Adv. Cost: 0.42 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Providing of vinyl with eco solvent printing with pasting on boards of different sizes on old boards with painting the legs and back properly.	101.5	Sft	RTQ		
2	Repair to the frame structure of available boards (partly damaged) available in store including welding, denting and applying coat of red oxide primer.	14	No.	RTQ		
3	Carriage of boards by head load including installation of boards at Holy Cave Camp (upper and lower) by excavating trenches etc.	14	No.	RTQ		
4	Carriage of boards by head load from store including cost of its installation at designated sites by excavating trenches and laying the leg in it and back filling of the same.	24	No.	RTQ		
5	Carriage of boards by head load from store including cost of its installation at enroute Brarimargn to Sangam.	12	No.	RTQ		

6	Carriage of boards by head load from store including cost of installation at enroute Domel to Railpathri	12	No.	RTQ		
7	Dismantling of boards and stack in store properly (nearby SASB store or direction of engineer-in-charge)	62	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Construction of steps at various places in between hut area and pandal area at Holy Cave.

S.No. :32

Adv. Cost: 1.30 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount
I	II	III	IV	V	VI	VII
1	Earthwork in excavation by manual means over areas (exceeding 30 cm and upto 1.5 mtr in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth to be levelled and neatly dressed in ordinary rock.	8.40	Cum	Rs.240.45/-		
2	Providing and Laying of soling stone/kankar as sub grade for steps/foot path.	4.20	Cum	Rs.317.75/-		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level in 1:4:8 nallah stone.	4.20	Cum	Rs.3061.30/-		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level (1:3:6 with 40mm nominal size stone).	4.20	Cum	Rs.3552.50/-		

5	Centring and shuttering including strutting, propping etc and removal of form work for foundations, footing and bases of columns.	46.20	Sqm	Rs.179.25/-		
6	Carriage of cement by mechanical transport from Ganderbal to Baltal	01	Trip of LMV	RTQ		
7	Carriage of cement by head load from Baltal to Holy Cave. (02 bags/pony)/	16	Ponies	RTQ		
8	Carriage of sand and bajri by head load from Panjtarni to Holy Cave (avg. Lead 5 km).	11.34	Cum	Rs.2131.93/-/-		
9	Carriage of stone by Head load for a lead of 0.5 km.	4.20	Cum	Rs.329.07/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage, assembling and erection in position of PPGI sheet Pandal (16 Room each room size 3.45 x 3.45 mtr) before commencement of Yatra including cost of its dismantling, carriage upto SASB store near counting Hall and proper stacking after the culmination of Yatra- 2019 at Holy Cave.

S.No. : 33

Adv. Cost: 1.78 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of the prefabricated PPGI sheet panels composited with MS tube 50x25x3mm and PPGI sheet 1 mm thick with proper nuts and bolts (supply of required bolts also) and repair of doors ,windows, providing and fixing of Al-drops and handles including cost of its carriage from SASB store to erection site before commencement of Yatra.	558.44	Sqm	RTQ		
2	Dismantling of the PPGI sheet panels and opening of ridges base frames etc including cost of its carriage and proper stacking in SASB store (as per the direction of site Engineer) near counting Hall after the conclusion of Yatra.	558.44	Sqm	RTQ		

3	Supply and fixing of water proofing poly ethylene sheet of silpaualin brand with ropes at roofing of 16 No.rooms Block	02	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage, assembling and erection in position of PPGI sheet hut of size 3.00x3.00 m with attached washroom of size 1.50 x1.50 m before commencement of Yatra including cost of its dismantling, carriage upto SASB store near counting Hall and proper stacking after the culmination of Yatra- 2019 at Holy Cave.

S.No. : 34

Adv. Cost: 0.20 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of the prefabricated PPGI sheet panels composited with MS tube 50x25x3mm and PPGI sheet 1 mm thick with proper nuts and bolts (supply of required bolts also) and repair of doors ,windows, providing and fixing of Al-drops and handles including cost of its carriage from SASB store to erection site before commencement of Yatra.	57.50	Sqm	RTQ		
2	Dismantling of the PPGI sheet panels and opening of ridges base frames etc including cost of its carriage and proper stacking in SASB store (as per the direction of site engineer) near counting Hall after the conclusion of Yatra.	57.50	Sqm	RTQ		

3	Fixing of sanitary items including providing of jet spray, cistern of 10 litres capacity, waste pipe PVC connection and other G.I. Fittings (complete job).	01	No.	RTQ		
4	Providing and fixing of PVC matting (superior quality) 1 mm thick with solvent to the flooring of wash room of the hut.	25	Sft	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage, assembling and erection in position of PPGI sheet hut of size 3.00x3.00 m with attached washroom of size 1.50 x1.50 m before commencement of Yatra including cost of its dismantling, carriage upto SASB store and proper stacking after the culmination of Yatra- 2019 at Brarimarg.

S.No. : 35

Adv. Cost: 0.21 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of the prefabricated PPGI sheet panels composited with MS tube 50x25x3mm and PPGI sheet 1 mm thick with proper nuts and bolts (supply of required bolts also) and repair of doors ,windows, providing and fixing of Al-drops and handles including cost of its carriage from SASB store to erection site before commencement of Yatra.	57.50	Sqm	RTQ		
2	Dismantling of the PPGI sheet panels and opening of ridges base frames etc including cost of its carriage and proper stacking in SASB store (as per the direction of site engineer) after the conclusion of Yatra.	57.50	Sqm	RTQ		
3	Fixing of sanitary items including providing of jet spray, cistern of 10 litres capacity, waste pipe PVC connection and other G.I. Fittings (complete job).	01	No.	RTQ		

4	Providing and fixing of PVC matting (superior quality) 1 mm thick with solvent to the flooring of wash room of the hut.	25	Sft	RTQ		
5	Providing and fixing of electrical items to the room and washroom of hut (3 points).	01	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/ assembling of prefabricated toilet/ baths (150 No.) in Upper Holy Cave before the commencement of Yatra including cost of its carriage from store and dismantling with proper stacking in SASB store after the conclusion of Yatra2019.

S.No. : 36

Adv.Cost : 2.75 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load. ii. Supply of nuts & bolts etc of required size. iii. Fixing of disposal PVC pipe, bends, tee etc and laying the pipes upto nearest sokage pit. (Complete Job)	150	No.	RTQ		
2	Supply of PVC pipes, bends ,tee, sockets of 110 mm dia (subject to the actual measurement at site) including carriage upto Holy Cave. a. PVC pipe b. PVC bend c. PVC tee d. PVC socket	 300 100 50 150	 Rm No. No. No.	 RTQ RTQ RTQ RTQ		

3	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in in 40% all kinds of soil and 60% ordinary rock including covering of the pits with available scrap in the SASB store.	27.18	Cum	RTQ		
4	Engagement of the semi skilled labour for the repair of the cess pits or construction of additional soak pits during Yatra and upkeeping of toilets/ baths or any other requirements in the camp for first 30 days. (labour)	60	No.	RTQ		
5	Dismantling of toilet/baths during or after Yatra (on the instruction of site engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	150	No.	RTQ		
6	Carriage of material by MT from Ganderbal to Baltal	01	Trip of LMV	RTQ		
7	Carriage of material by head load from baltal to Holy Cave.					

	a. Pony b. Porter	03 25	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/ assembling of prefabricated toilet/ baths (150 No.) in Lower Holy Cave before the commencement of Yatra including cost of its carriage from store and dismantling with proper stacking in SASB store after the conclusion of Yatra 2019.

S.No. : 37

Adv.Cost : 1.50 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load. ii. Supply of nuts & bolts etc of required size. iii. Fixing of disposal PVC pipe, bends, tee etc and laying the pipes upto nearest sokage pit. (Complete Job)	150	No.	RTQ		
2	Supply of PVC pipes, bends ,tee, sockets of 110 mm dia (subject to the actual measurement at site) including carriage upto Holy Cave. a. PVC pipe b. PVC bend c. PVC tee d. PVC socket	100 50 24 60	Rm No. No. No.	RTQ RTQ RTQ RTQ		

3	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in in 40% all kinds of soil and 60% ordinary rock including covering of the pits with available scrap in the SASB store.	27.18	Cum	RTQ		
4	Dismantling of toilet/baths during or after Yatra (on the instruction of site engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	150	No.	RTQ		
5	Carriage of material by MT from Ganderbal to Baltal	01	Trip of LMV	RTQ		
6	Carriage of material by head load from baltal to Holy Cave. c. Pony d. Porter	01 09	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Erection/ assembling of prefabricated toilet/ baths (135 No.) at enroute Domel to Sangam before the commencement of Yatra including cost of its carriage and dismantling with proper stacking in SASB store after the conclusion of Yatra 2019.

S.No. : 38

Adv.Cost : 1.38 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of toilets/baths at designated site (before commence of Yatra) including:- i. Carriage of prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding & fixing of aldrops and handles etc. iii. Supply of nuts & bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc and laying the pipes upto nearest sokage pit. v. Carriage of 08 No. New toilet/baths from Domel to Railpathri and 02 No. from Domel to Brarimarg. (Complete Job)	135	No.	RTQ		

2	Supply of PVC pipes, bends ,tee, sockets of 110 mm dia (subject to the actual measurement at site) including carriage upto Holy Cave. a. PVC pipe b. PVC bend c. PVC tee d. PVC socket	69 48 48 24	Rm No. No. No.	RTQ RTQ RTQ RTQ		
3	Dismantling of toilet/baths during or after Yatra (on the instruction of site engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job).	135	No.	RTQ		
4	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in in 40% all kinds of soil and 60% ordinary rock including covering of the pits with available scrap in the SASB store.	22.65	Cum	RTQ		
5	Carriage of material by head load from baltal to Holy Cave. Porter	08	No.	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Repair to the prefabricated toilets /baths at Upper and Lower Holy Cave for Yatra 2019. (150 Nos.)

S.No. : 39

Adv.Cost : 0.60 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Repair to the toilets/baths by way of welding the damaged sheets of walls, base and doors including cutting, welding, fixing of handles, lock bolts and Al- drops.	150	No.	RTQ		
2	Supply of Al-drops 8 inches, locking bolts of 4 inch size of Indian standards manufacturing. a. Al-drops (8 inches) b. Locking bolts (4 inches)	100 100	No. No.	RTQ RTQ		
3	Supply of M.S. flat of size 25 mm x 3mm including making of handles for doors .	40	Kg	Rs.80.50/-		
4	Carriage of material by head load from baltal to Holy Cave. a. Pony b. Porter	01 01	No. No.	RTQ RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Face lifting to the R-walls and grill at Holy Cave for Yatra - 2019

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Applying 01 coat water thinable cement primer of approved brand and manufacture on wall surface	500	Sqm	Rs.32.85/-		
2	Finishing walls with water proofing cement paint of required shade on new work (two or more coats) applied @ 3.84 kg/ 10 sqm	500	Sqm	Rs.56.90/-		
3	Finishing walls with water proofing cement paint of required shade on old work (two or more coats) applied @ 2.20 kg/ 10 sqm over primer coat.	49.68	Sqm	Rs.53/-		
4	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade on old steel work including carriage of paint (one or more coat)	74.35	Sqm	Rs.45.60/-		
5	Carriage of material by head load from Baltal to Holy Cave.	05	Ponies	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Carriage, assembling and erection in position of CR sheet Hut (04 Rooms of size 3.50x4.00meters with attach washroom of size 2.00x1.50 M)) before commencement of Yatra and laying of tile flooring in washrooms including cost of its dismantling, carriage upto SASB store near counting Hall and proper stacking after the culmination of Yatra-2019 at Holy Cave.

S.No. : 41

Adv. Cost: 2.75 lakh

S. No.	Particulars of Items	Qty	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/below %age)	Amount (in Rs.)
I	II	III	IV	V	VI	VII
1	Assembling of the prefabricated CR sheet hut panels composited with MS tube 50x25x3mm and CR sheet 1 mm thick with proper nuts and bolts (supply of required bolts also) and repair of doors ,windows, providing and fixing of Al-drops and handles including cost of its carriage from SASB store to erection site before commencement of Yatra.	229.45	Sqm	RTQ		
2	Fixing of PVC panels /boards to the walls and ceiling with self driven screws including cost of screws and other fixtures and fastenings	2468	Sft	RTQ		
3	Providing and fixing of beading of one inch wide and cornice to the joints of PVC board.					
	c. Beading	800	Rft	RTQ		
	d. Cornice	360	Rft	RTQ		

4	Providing and fixing of wood work in frame of false ceiling, walls sawn and fixed in position.	70	Cft	RTQ		
5	Providing and fixing of hangers with 08 pegs on the walls.	12	No.	RTQ		
6	Providing and fixing of all sanitary fittings including supply of flushing cistern, PVC connection, angle valves, jet spray, wash basin (with pedestal) and other all PVC and GI fittings. Washrooms	04	No.	RTQ		
7	Providing and fixing of electrical items a. Caping casing b. Switch 6 Amp c. Wall Angle holder d. 5 pin socket e. Wire f. Gang box for 3 switch & 01 socket g. Gang box for 1 switch & 01 socket h. LED lamp (15 Watt)	120 20 12 08 02 04 04 16	Rft No. No. No. No. No. No. No..	RTQ RTQ RTQ RTQ RTQ RTQ RTQ RTQ		
8	Providing and laying of ceramic glazed tiles conforming to IS : 1753 of minimum thickness 5 mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalent (Colour and design to be approved by engineer –in- charge) in skirting, rises of steps, floorings etc. in Mortar 1:3 and jointing with grey cement slurry.	14.08	Sqm	Rs.834.20/-		

9	Carriage of material by MT from Ganderbal to Baltal	01	Trip of LMV	RTQ		
10	Carriage of material by head load from baltal to Holy Cave. a. Pony (02 bags/pony) b. Porter	25 03	No. No.	RTQ RTQ		
11	Carriage of sand by head load for a lead of 6 km	0.183	Cum	Rs.2543.53/-		
12	Dismantling of the CR sheet panels and opening of ridges base frames etc including cost of its carriage and proper stacking in SASB store (as per the direction of site Engineer) near counting Hall after the conclusion of Yatra.	229.45	Sqm	RTQ		
13	Dismantling of PVC / WPC panels , sanitary items and electrical items including carriage and proper stacking after Yatra.	2468	Sft	RTQ		
Total cost of bid (to be quoted both in figures and words)						

Note: Any typographical error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Stage contract for the snow clearance (with frost) from entry stairs and exit stairs before the commencement of Yatra at Holy Cave. (Yatra - 2019)

S.No. : 42

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Clearing of snow with frost and gulla cutting in compressed snow from entry stairs and exit stairs at Holy Cave and carriage upto the nearby disposal site.	To be identified at site	Cum	Rs.2.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their Bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Stage contract for the snow clearance (with frost) from Pandal, huts site, shed site, cloak room, EAC and other required sites before the commencement of Yatra at Holy Cave. (Yatra - 2019)

S.No. : 42

S. No.	Particulars of Items	Quantity	Unit	Rate as per SSR of 2012	Rate to be quoted by the Bidder (above/ below %age)	Amount
I	II	III	IV	V	VI	VII
1	Clearing of snow with frost and gulla cutting in compressed snow from Pandal, huts site, shed site, cloak room, EAC and other required sites and carriage upto the nearby disposal site.	To be identified at site	Cum	Rs.2.25/-		
Total cost of bid (to be quoted both in figures and words)						

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2012.

DGM (W) Baltal

Signature of the Bidder