

# Shri Amarnathji Shrine Board



## **Jammu and Kashmir**

**Tender Document  
For  
Civil Works along Baltal axis  
For  
Yatra – 2021**

Sd/-  
**General Manager (Works)**  
Shri Amaranthji Shrine Board

**26.02.2021**

**CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2021**

**DETAILED NOTICE INVITING TENDER (DNIT)**

(Issued under no. SASB/Works/W/1283/2021/14      dated 26.02.2021)

<b>S. No.</b>	<b>CONTENT</b>	<b>PAGE(S)</b>
1.	Notice Inviting Tender (NIT) for advertisement	3-7
2.	Eligibility Criteria	8
3.	Documents establishing Bidder's eligibility	8
4.	Instructions to Bidders	9-11
5.	Terms and Conditions of Contract	11-14
6.	Schedule – A (Technical Bid)	15-16
7.	Bid Securing Declaration (Format)	17
7.	Schedule – B (Financial Bid)	18-77



## **SHRI AMARNATHJI SHRINE BOARD**

Chaitanya Ashram, Talab Tillo, Jammu (Nov - April)

Tele: 0191-2555662, Telefax: 0191-2503399

### **NOTICE INVITING TENDER CIVIL WORKS ALONG BALTAL AXIS FOR YATRA - 2021**

For and on behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.2/- revenue stamps, are invited from registered **JK PWD, CPWD Contractors** having a valid registration, for the execution of Civil Works as mentioned below. The bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **18.03.2021** upto **1400 hours**.

S. No.	Name of work	Estimated cost (Rs in lakh)	Cost of bid document (in Rs)	Earnest Money/ Bid Security (in Rs)	Class of Contractor	Time of Completion
1	Dismantling of Safety Panel of Departure Lounge pre Yatra, refixing of panels to convert as temporary room to be utilized during Yatra and dismantling of temporary CGI sheet rooms and re-fixing to Departure Lounge as safety panels post Yatra including electrification at Neelgrath for Yatra-2021.	1.51	200/-	<b>Bid Security Declaration to be made by the Bidder on non judicial stamp paper duly attested by Notary as per prescribed format.</b>	DEE	7 days
2	Clearance of choked drains and repairs to the firegaps, levelling of parking area including filling of depressions and leveling/dressing of outsource Hut site at Baltal Camp for Yatra 2021.	1.38	100/-		DEE	12 days
3	Supply & Fixing of agronet partition between Langars and Toilet Blocks, around Base Hospital (Hanger) and newly constructed four room Hut and Repair/Re-erection of barbed wire fencing at Baltal Camp, Helipad area including dismantling of the same after conclusion of Yatra-2021.	1.40	100/-		DEE	10 days
4	Fixing of Sign Boards including repairs and welding of damages, carriage from SASB stores to sites of installation before commencement of Yatra and dismantling and safe storage in SASB stores after culmination of Yatra along Baltal Axis at Neelgrath, Baltal, Panjtarni and Holycave Camps and enroute from Neelgrath, Rangamoh to Holy cave via Sangam and Kalimata track for Yatra-2021.	1.36	100/-		DEE	15 days

5	Dismantling of safety panel of Camp Director Office cum Residential Complex before Yatra and construction of 4 rooms for Medical Department and for security forces (by using safety panels) including dismantling after Yatra and re-fixing the same as safety panels to Camp Directors Huts at Dumail for Yatra 2021.	0.90	100/-		DEE	10 days	
6	Dismantling of safety panels of Prefab PUF paneled huts including Jacks of 04 No. Camp Director Huts, 01 No. Reserve Hut including canopy, 02 No. Medical Huts, 03 No. newly constructed Huts and refixing of same after conclusion of Yatra at Baltal for Yatra 2021.	1.10	100/-		DEE	10 days	
7	Repairs and fixing of CGI sheet roofing and dismantling after conclusion of Yatra including repairs and renovation of Base Hospital (Hangar) and electrification cum sanitary fittings at Baltal.	1.50	100/-		DEE	10 days	
8	Construction of substructure of Control Room for Service Providers for issuance of Smart Card to Yatrics at Dumail before commencement of Yatra-2021.	0.80	100/-		DEE	10 days	
9	Construction of substructure of Control Room for Service Providers for issuance of Smart Card and minor civil work of Sadhu Shed before Yatra including dismantling and safe stacking of Sadhu shed and Control room at Holycave	2.22	300/-		DEE	12 days	
10	Stage contract for the snow clearance (with frost) from Entrance and Exit stairs, path from Helipad to Entrance Stairs and other adjoining sites before the commencement of Yatra 2021 at Holy Cave	-	300/-		DEE	10 days	
11	Stage contract for the snow clearance (with frost) from Hutment area, Pandal area, Base Hospital site, Cloak Room, Shoe Rack site and from other Shed site before the commencement of Yatra at Holy Cave.	-	300/-		DEE	10 days	
12	Stage contract for the snow clearance (with frost) from Base Hospital and Toilet site area before the commencement of Yatra 2021 at Lower Holy Cave.	-	200/-		DEE	10 days	

13	Stage contract for the snow clearance (with frost) from Camp Directors' Hut area, Heliservices Staff accommodation and Service providers area before the commencement of Yatra 2021 at Lower Holy Cave.	-	200/-		DEE	10 days
14	Construction of approach path from VIP helipad at Holycave to Main entrance steps at Holycave for Yatra-2021.	6.60	1000/-		CEE, DEE	20 days
15	Construction of approach path from Market area to Access control Gate at Holycave for Yatra-2021.	13.45	1500/-		BEE, CEE, DEE	20 days
16	Construction of Substructure of 02 No. Huts of size 16'-00" x 16'-00" each with attached washrooms and 02 No. Kitchen of Size 8'-00" x10'-00" for Heli-services staff at Lower Holy Cave for Yatra-2021.	3.20	400/-		DEE	15 days
17	Carriage, erection /assembling of old Way Side Rest Shelters and fencing around Medical Camps enroute Dumail to Kalimata Track and Panjtarni to Sangam Top before commencement of Yatra and dismantling and safe storage after culmination of Yatra	1.31	100/-		DEE	15 days
18	Construction of the substructure of 01 No. Hut of size 16'-00" x 16'-00" with attached washroom and 01 No. Kitchen of Size 8'-00" x10'-00" for Heli-services staff at Sangam Top for Yatra-2021.	1.40	100/-		DEE	10 days
19	Construction of the substructure of 02 No. rooms of size 12'-00" x 11'-00" with attached washroom of Size 6'-00" x4'-6" for camp director and kitchen of size 8'-00"x10'-00" at Sangam Top for Yatra-2021.	1.85	200/-		DEE	15 days
20	Finishing/flooring of Store at Brarimarg and conversion of one room into residence with attached washroom of Camp Director Brarimarg.	3.18	400/-		DEE	15 days
21	Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 at Baltal Camp	3.78	400/-		DEE	15 days
22	Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 at Neelgrath and enroute Rangamorph to Dumail.	5.67	1000/-		CEE, DEE	20 days

23	Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 enroute Dumail to Holycave	1.73	200/-		DEE	10 days
24	Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 at Holycave.	3.00	300/-		DEE	10 days
25	Assembling of SASB Huts (Staff 07 Rooms, Base Hospital, Medical and Police Officers Hut, Meeting Hall, JK Bank Hut) at HolyCave before start of Yatra and its dismantling and safe stacking after conclusion of Yatra 2021.	2.80	300/-		DEE	10 days
26	Assembling/Erection of one no. Double room Hut (size 32'x16') with attached washrooms for Camp Directors and construction of Kitchen shed at Lower Holycave for Yatra 2021.	1.31	100/-		DEE	10 days
27	Carriage, assembling of Pandal at Holy Cave including its carriage upto site of erection/assembling and dismantling the same and carriage upto safe storage site after the culmination of Yatra (16 rooms of size 3.45 m x 3.45 m).	1.72	200/-		DEE	10 days
28	Assembling and fixing of one No. CR sheet Hut comprising of 4 rooms of size 3.5m x 4.0 m each with attached washrooms at Holy Cave, assembling and erection of PPGI sheet single room Huts of size 3.0mx3.0m each with attached washroom at Holycave and Brarimarg including carriage to and fro SASB stores and dismantling after conclusion of Yatra-2021.	1.40	100/-		DEE	10 days
29	Assembling of dismantled portion of Base Hospital at Lower Holycave before commencement of Yatra and dismantling and safe stacking after conclusion of Yatra 2021	1.56	200/-		DEE	7 days

- Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from **9.30 AM to 5.00 PM**, on any working day from **01.03.2021 to 16.03.2021** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu or can be downloaded from SASB website ([www.shriamarnathjishrine.com](http://www.shriamarnathjishrine.com))
- The Bids, duly completed, along with **Bid Security Declaration**, must reach the office of General Manager (Works) latest by **18.03.2021 upto 1400 Hrs.** The Bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through Speed Post/ Registered Post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reasons.

4. The Technical bid shall be opened on **18.03.2021 at 1500 Hrs** in the Office of General Manager (Works) at Jammu Office (address mentioned above) in presence of the Bidders who may wish to be present on the occasion.
5. Not more than three bid documents shall be issued to a single Bidder.
6. In case the last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day up to **1400 hours**.
7. The successful Bidder is bound to enter into an agreement with General Manager (Works), SASB, **within ten days** from the date of the receipt of Letter of Intent (LoI).
8. All addenda, corrigenda, dedenda and amendment shall be uploaded on website only and not in print media and the Bidders are advised to keep themselves updated on this account.

**No: SASB/NIT/W/1283/2021/14**  
**Dated: 26.02.2021**

**Sd/-**  
**General Manager (Works)**  
Shri Amarnathji Shrine Board

## **2. ELIGIBILITY CRITERIA**

The Bidder must be a Contractor registered with J&K, PWD, CPWD and must fulfil all the following eligibility requirements concurrently to technically qualify for bidding process:

Average Annual Turnover during the last three years, ending 31<sup>st</sup> March of the previous financial year (i.e. 2017-18, 2018-19, 2019-20) should be 30% of the advertised cost.

2.2 The bidder should have an experience of having successfully completed similar works in Hilly Regions during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-

a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or

b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or

c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.

2.3 The Bidder should not have been blacklisted on an earlier occasion by any of the Union Territory Government Organizations, U.T Autonomous Bodies or Local Bodies/ Municipalities.

## **3. DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY**

The Bidder must submit the following documents:

3.1 Registration Certificate.

3.2 Certified copies of Annual Turnover from Bank

3.3 Certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works, for fulfilling the eligibility criteria.

3.4 Certified copy of PAN Card.

3.5 Certified copy of GSTIN.

3.6 General Profile of the Bidder

3.7 Bid Security Declaration.

3.8 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect during technical evaluation or during execution of work, the following penalties are to be imposed;

3.8. i. in case the work is allotted to the agency, the contract shall be terminated and work executed through an alternate agency at the risk & cost of the allottee,

3.8. ii. Earnest Money Deposit, shall be forfeited

3.8. iii. the Bidder/ Allottee shall be debarred from tendering in SASB for next three years.



#### 4. **INSTRUCTIONS TO BIDDERS:**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from **9.30 AM to 5.00 PM** on any working day from **01.03.2021 to 16.03.2021** on payment of cost of Tender Document prescribed against each work in the DNIT in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB). Alternatively it can be downloaded from SASB website . ([www.shriamarnathjishrine.com](http://www.shriamarnathjishrine.com))
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of \_\_\_\_\_ Yatra 2021**” and “**Financial Bid for the work of \_\_\_\_\_ Yatra 2021**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of \_\_\_\_\_ (Yatra 2021)**” **mentioning NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The bids, duly completed, along with **Bid Security Declaration** must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered/ Speed Post to General Manager (Works), SASB at the aforesaid address, so as to reach latest on **18.03.2021 upto 1400 hours**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by speed post.
- 4.4 The cost of DNIT should be placed inside the envelope containing the Technical bid and Bid Security Declaration.
- 4.5 It would be deemed that by submitting the bid, the Bidder has made complete examination of the DNIT, received all information from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each Bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 4.7 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid not substantially responsive to the DNIT in every respect will be at Bidder's risk and may result in the rejection of the bid.
- 4.8 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be indicated in words as well as in figures. In case of any variation between

amount in figures and words, amount quoted in words shall be taken as authentic.

- 4.9 The rate quoted by the Contractor in item rate tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.10 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of DNIT as acceptance of all conditions contained therein and for the purpose of identification. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.11 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The General Manager (Works) may, at his discretion, extend the deadline for submission of bids. Any bid received after due date and time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.12 Clarifications, if any, may be sought by the Bidders prior to so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by General Manager (Works), SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hoisted on SASB website ([www.shriamarnathijshrine.com](http://www.shriamarnathijshrine.com)) and NOT in newspaper(s). The Bidders should keep themselves updated on this account.
- 4.13 The Technical Bid shall be opened on **18.03.2021 at 1500 Hrs** in the Office Chamber of General Manager (works) in presence of the authorized representatives of the Bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.14 The General Manager (Works), SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the Bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.15 The bid shall remain valid and open for acceptance for a period (i.e. Bid Validity Period) of **60 days from the last date prescribed for its receipt.**
- 4.16 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.

- 4.17 The General Manager (Works) may award the Contract to the Bidder whose bid has been evaluated to be responsive and who is eligible and qualified to perform the contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible Bidder a letter, hereinafter referred to as the 'Letter of Intent' (LoI) prescribing the amount which the Shrine Board will pay to the eligible Bidder in consideration of work/ services to be executed by the eligible Bidder as prescribed in the Contract.
- 4.18 The eligible Bidder will have to enter into an agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the **ten days** of the receipt of Letter of Intent.
- 4.19 General Manager (Works), SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reasons thereof. Any enquiry after the submission of tender will not be entertained.
- 4.20 Shri Amarnathji Shrine Board shall not be responsible for release of any DD/ CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the DDs/ CDRs of unsuccessful Bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

## **5. TERMS AND CONDITIONS OF THE CONTRACT:**

- 5.1 The Bidders are required to quote rate above/ below percentage on SSR of 2020 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. All rates/ percentages should be quoted in figures and words. The Bidders must also calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 5.2 Bids shall have to be submitted separately for each work as indicated in the NIT.
- 5.3 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- |           |   |  |
|-----------|---|--|
| 5.3 (i)   | First 3 days of delay                         | Penalty @1% of contract value.   |
| 5.3 (ii)  | 4 <sup>th</sup> day upto 10 <sup>th</sup> day | @2% of contract value  |
| 5.3 (iii) | Beyond 10 days                                | Earnest Money Deposit shall be forfeited and the contract automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm. |

- 5.4 Not with standing **Clause 5.3 above**, in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 5.5 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).
- 5.6 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per PWD/ CPWD Book of specifications.
- 5.7 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencement of work at site.
- 5.8 The Contractor shall submit **pictorial evidence (Photographs)** of execution of work (pre execution, during execution and after completion of work) with his claim.
- 5.9 The Contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 5.10 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the Contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 5.11 The Contractor shall abide at all times by all the applicable labour enactments and rules made there under, regulations, notifications and bye laws of the U.T or Central Government or Local Authority and any other labour laws (including rules), regulations, bylaws that may be passed or notifications that may be issued under any labour law in future either by the U.T. or the Central Government or the local authority. The Contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.
- 5.12 All risks of loss or damage to physical property and of personal injury and death which may arise during and in consequence of the performance of the contract shall be the sole responsibility of the Contractor.
- 5.13 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ Employees, employed by him for execution of work against any personal injury or death.

- 5.14 The agency shall be solely responsible for **Workmen's Compensation Act**, 1923 for payment of **compensation** to **workmen** and their dependants in case of injury and accident (including certain occupational disease) arising out of and in the course of employment and resulting in disablement or death.
- 5.15 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 5.16 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the Labour Law in Force.
- 5.17 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of **Letter of Intent** (LoI).
- 5.18 General Manager (Works), SASB shall be at liberty to suspend the agreement due to any Force Majeure conditions such as Government regulations, court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.
- 5.19 All disputes and differences between the parties arising out and relating to the agreement to be signed between the General Manager (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 5.20 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the Union Territory of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 5.21 The rates quoted by the Contractor shall be inclusive of all taxes including GST etc as are applicable.
- 5.22 If during the period of one year from the date of completion of work, the defects which have been caused by bad workmanship, use of inferior materials on the work, the Contractor shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the work shall be got rectified through alternate resourceful agency and the cost thereof shall be recovered from the dues of the Contractor.
- 5.23 The Earnest Money Deposit of the successful Bidder shall be released after completion of work in full and issue of completion certificate by the DGM, SASB.

**VI Payment Clause:**

- 6.1 Payment shall be made to the Contractor for complete item of work including cost of material and labour (finished work) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site duly checked by the Deputy General Manager Works.
- 6.2 The payment to the Bidder shall be made after successful completion of work within the stipulated time as per specifications and Terms & Conditions of agreement after satisfactory use/ function of the work during complete Yatra Period.
- 6.3 Any extra item (s) executed at site of work shall be paid strictly as per LoA (Contractor's appreciation/ depreciation on J&K **Sanctioned Schedule of Rates 2020.**)

**VII Time of completion:**

- 7.1 The time of completion of works stands mentioned against each work in the NIT.
- 7.2 Time of completion shall mean;  
Period of time of completion of work in all respects before start of Yatra – 2021 including the period of time involved in completely dismantling of the pre-fabricated structures with due care from damages and safe storage of the materials in the SASB stores to the entire satisfaction of the Deputy General Manager (Works) or his authorised representative.

Sd/-  
**General Manager (Works)**  
Shri Amarnathji Shrine Board

## **SCHEDULE A (TECHNICAL BID)**

**PART A: DETAILS OF COST OF DNIT AND BID SECURITY DECLARATION**

S. No.	Particular of item	Details
1	Amount and details of payment towards the cost of DNIT:	Rs. (in words):
		Receipt No./ Cheque No:
		Date:
2	Bid Securing Declaration	Dated:
		Bid No.
		Name of Notary

**PART – B: BASIC DETAILS ABOUT THE AGENCY.**

- i) Name and address of :  
the Agency.

Name: \_\_\_\_\_

Address: \_\_\_\_\_

---

---

Phone: \_\_\_\_\_

E-mail: \_\_\_\_\_



## **PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.**

The Bidder is required to furnish the following information/ documents:  
(Please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

#	Financial Year	Turnover (Rs.)
1	2017-18	
2	2018-19	
3	2019-20	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (in Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/ No)

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*
5. Certified copy of GSTIN – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*
7. Bid Security Declaration – *para 3.7 of Documents Establishing Bidder’s Eligibility’*
8. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility.*



## **Form of Bid Security Declaration**

(Duly notarized)

**The General Manager (Works),**  
Shri Amarnathji Shrine Board,  
Chaitanya Ashram, Talab Tillo, Jammu

**NIT No. & Date:** \_\_\_\_\_

**Name of work.** \_\_\_\_\_

1. I \_\_\_\_\_ s/o \_\_\_\_\_  
r/o \_\_\_\_\_ declared that;

I understand that, according to your conditions, bids must be supported by a Bid Securing Declaration.

2. I accept that I may be disqualified from any Contract with the Shri Amarnathji Shrine Board for a period of three years from the date of notification if am in a breach of any obligations (s) under the bid conditions, because I;

- a). have withdrawn/ modified/amended, impaired or derogated from the tender, my bid during the period of bid validity specified in the Letter of Bid, or
- b). having been notified of the acceptance of my Bid by the SASB during the period of bid validity of (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with Instructions to Bidders.

3. I understand this Bid- Securing Declaration shall cease/ expire to be valid if undersigned is not the successful Bidder, upon the earlier of (i) the receipt of your notification of the name of the successful Bidder; or (ii) sixty days Bid Validity Period.

**Signature of person**

(Signing the Bid Securing Declaration)

Dated on \_\_\_\_\_ day of \_\_\_\_\_

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Dismantling of Safety Panel of Departure Lounge pre Yatra, refixing of panels to convert as temporary room to be utilized during Yatra and dismantling of temporary CGI sheet rooms and re-fixing to Departure Lounge as safety panels post Yatra including electrification at Neelgrath for Yatra-2021.

**S.No: 01**

**Adv. Amount: Rs. 1.51 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Dismantling of safety panels of Mild Steel including welding etc and stacking properly	270.72	Sqm		
2	Fixing of safety panel to convert as in temporary room for the use of officials during yatra	235.41	Sqm		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	0.26	Cum		
4	Carriage of cement by Mechanical Transport from Ganderbal to Neelgrath for an avg. lead 60 km	0.06	Tonne		
5	Carriage of sand & bajri by MT for an average lead of 33 Km.	0.35	Cum		
6	Dismantling roofing including ridges, hips, valleys and gutters etc including propping, bracing the structure including welding, and stacking material within 50m lead of G.S Sheet.	235.41	Sqm		

7	Fixing of safety panel of MS around the departure lounge vertically to avoid damages during winter (complete).	270.72	Sqm		
8	Hire charges of Genset, welding set, electrodes and POL for strengthening of Departure Lounge with available material after conclusion of Yatra 2021 and Fixing of electrical items to temporary accommodation for service providers before Yatra including dismantling and safe stacking after Yatra by way of engaging skilled labour at Neelgrath.  Welding set , Genset , electrodes and POL : Blacksmith: Electrician: Helpers:	   01 01 06 08	   Day Day Day Day		
<b>Total cost of bid (to be quoted both in figures and words)</b>					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Clearance of choked drains and repairs to the firegaps, levelling of parking area including filling of depressions and leveling/dressing of outsource Hut site at Baltal Camp for Yatra 2021

**S.No: 02**

**Adv. Amount: Rs.1.38 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Earth work in excavation by manual means over areas for foundation, drains, cables, cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	90.00	Cum		
2	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth, lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge in all kinds of soil.	1270.00	Sqm		
Total cost of bid (to be quoted both in figures and words)					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Supply & Fixing of agronet partition between Langars and Toilet Blocks, around Base Hospital (Hanger) and newly constructed four room Hut and Repair/Re-erection of barbed wire fencing at Baltal Camp, Helipad area including dismantling of the same after conclusion of Yatra-2021.

**S.No: 03**

**Adv. Amount: Rs.1.40 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m. in all kind of soil.	400	No.		
2	Labour for fixing of steel angle iron posts and struts of required size (Angle size 45x45x6mm available in SASB store) including carriage from store to site of erection. Mazdoor:	18	No		
3	Fixing of agro net of 1.8 metres height including proper tightening with angle iron posts with necessary screws/wires etc complete.	810	Sqm		
4	Supply of agronet of approved make& design.	243.00	Sqm		

5	Labor for dismantling of agronet fencing and angle iron post including carriage and stacking in SASB store after culmination of Yatra. Mazdoor:	12	No		
6	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, barbed wire, earth work and concrete work to be paid for separately). Payment to be made per meter cost of total length of barbed wire used.	6300	Meter		
7	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking in SASB store at Baltal.	590.94	Kg		
<b>Total cost of bid (to be quoted both in figures and words)</b>					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Fixing of Sign Boards including repairs and welding of damages, carriage from SASB stores to sites of installation before commencement of Yatra and dismantling and safe storage in SASB stores after culmination of Yatra along Baltal Axis at Neelgrath, Baltal, Panjtarni and Holycave Camps and enroute from Neelgrath, Rangamorph to Holycave via Sangam and Kalimata track for Yatra-2021.

**S.No: 04**

**Adv. Amount: Rs.1.36 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Installation of sign boards of all sorts and sizes including repairs to damages by way of welding including earthwork by excavating holes of size 30cmx30cmx45cm and fixing including filling of earth and levelling etc complete job.				
	1.1 Neelgrath Camp,Baltal Camp,Dumail Camp and from Neelgrath/ Rangamorph to Dumail	130	No.		
	1.2 Holy Cave	20	No.		
	1.3 Panjtarni	20	No.		
	1.4 Enroute Dumail to Holycave via Sangam and Kalimata track.	30	No.		

2	Dismantling of the Sign Boards including carriage from site of installation to nearest store as per the instructions of site incharge and stacking in piles properly (complete job). 2.1 Neelgrath Camp,Baltal Camp,Dumail and enroute from Rangamoh to Dumail	130	No.		
	2.2 Holy Cave, Panjtarni & Enroute Dumail to Holycave via Sangam and Kalimata track.	70	No.		
3	Re-lettering with black Japan paint of approved brand and manufacture per letter per cm height	246.50	sft		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder



## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Dismantling of safety panel of Camp Director Office cum Residential Complex before Yatra and construction of 4 rooms for Medical Department and for security forces (by using safety panels) including dismantling after Yatra and re-fixing the same as safety panels to Camp Directors Huts at Dumail for Yatra 2021.

**S.No: 05**

**Adv. Amount: Rs.0.90 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Dismantling of safety panels of mild steel frame of Camp Directors Hut/Office and stacking properly .	183.82	Sqm		
2	Assembling/erection of safety panels for construction of 04 No temporary accommodation for medical department and security forces during Yatra.	190.10	Sqm		
3	Dismantling roofing including ridges, hips, valleys and gutters etc including propping, bracing the structure including welding, and stacking material within 50m lead of G.S Sheet.	190.10	Sqm		
4	Fixing of safety panel of M.S frame around Camp Director Office to avoid damages during winter including welding and repairs wherever required.	183.82	Sqm		
<b>Total cost of bid (to be quoted both in figures and words)</b>					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Dismantling of safety panels of Prefab PUF paneled huts including Jacks of 04 No. Camp Director Huts , 01 No. Reserve Hut including canopy, 02 No. Medical Huts, 03 No. newly constructed Huts and refixing of same after conclusion of Yatra at Baltal for Yatra 2021.

**S.No: 06**

**Adv. Amount: Rs. 1.10 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Dismantling of safety panels and stacking properly before commencement of Yatra.	506.74	Sqm		
2	Fixing of safety panels/ sheet paneling including supply of self driven screws and nails and welding etc complete job after conclusion of Yatra-2021.	506.74	Sqm		
Total cost of bid (to be quoted both in figures and words)					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Repairs and fixing of CGI sheet roofing and dismantling after conclusion of Yatra including repairs and renovation of Base Hospital (Hangar) and electrification cum sanitary fittings at Baltal.

**S.No: 07**

**Adv. Amount: Rs. 1.50 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Repairs to steel trusses of Hangar including strengthening of truss by way of welding etc Complete at Baltal.  a) Blacksmith  b) Helper  c) Welding set, Genset, electrodes and POL complete	03  03  03	No  No  Day		
2	Dismantling roofing, walling including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead ( Front wall) and dismantling of CGI sheet walls, roofing prefab huts vertical curved side including opening of doors, windows etc	309.56	Sqm		

3	Fixing of corrugated CGI sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required. 0.63 mm thick (Labour only)	309.56	Sqm		
4	Fixing of ridges or hips of width 60 cm overall width overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mm dia G.I limpet and bitumen washers complete	15.40	Meter		
5	Fixing of PVC sheet 2mm thick to vertical portion of Hall (Main Ward)	91.96	Sqm		
6	Cleaning/clearance of foreign matter and washing of the flooring and erection of the frame structure of kitchen shed for Doctors and other medical staff before yatra and dismantling of the same after the culmination of Yatra. Mazdoor:	24	No		
7	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping	75.84	Sqm		

	and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete				
8	Distempering with 1st quality Acrylic/oil bound washable distemper (ready-made) having VOC content less than 50 grams/litre of approved manufacturer and of required shade and colour complete as per manufacturers' specifications- One or more coats on old work.	75.84	Sqm		
9	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade- One or more coats on old work.	78.81	Sqm		
10	Labour for erection and assembling of wooden framed structure of kitchen shed for Doctors and other medical staff before yatra and dismantling of the same after the culmination of Yatra.  Carpenter Ist Class	08	No		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Construction of substructure of Control Room for Service Providers for issuance of Smart Card to Yatries at Dumail before commencement of Yatra-2021.**

**S.No: 08**

**Adv. Amount: Rs.0.80 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	2.71	Cum		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	3.64	Cum		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	5.42	Cum		
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.648	Cum		
5	Centering and shuttering including strutting, propping etc. and removal of	44.76	Sqm		

	form for: Foundations, footings, bases of columns etc. for mass concrete.				
6	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	24.81	Sqm		
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	2.20	Cum		
8	Providing and fixing strips in joints of terrazzo/ cement concrete floors. Glass strips- 40 mm wide and 4 mm thick	30.00	Meter		
9	Carriage of materials by MT from Ganderbal to Dumail for an avg lead of 73 kms.	2.52	Tonne		
10	Carriage by sand and stone aggregates by MT for an avg lead of 45 kms	14.76	Cum		
<b>Total cost of bid (to be quoted both in figures and words)</b>					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Construction of substructure of Control Room for Service Providers for issuance of Smart Card and minor civil work of Sadhu Shed before Yatra including dismantling and safe stacking of Sadhu shed and Control room at Holycave.**

**S.No: 09**

**Adv. Amount: Rs 2.22 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-incharge: 1:3:6 or richer mix	1.10	Cum		
2	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	2.71	Cum		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	3.42	Cum		
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6	5.42	Cum		



	graded stone aggregate 20 mm nominal size				
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1.75	Cum		
6	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	45.96	Sqm		
7	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	25.21	Sqm		
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	2.13	Cum		
9	Providing and fixing strips in joints of terrazzo/ cement concrete floors. Glass strips-40 mm wide and 4 mm thick	29.95	Meter		
10	Carriage of cement and all other materials by MT from Ganderbal to Dumail for an avg. lead of 73 kms.	2.40	Tonne		
11	Carriage by Head Load for:				
	a) Sand and stone aggregate for an avg lead of 5 Km	10.62	Cum		
	b) Metal (500 metres lead)	3.08	Cum		
	c) Cement and Glass strip (12 Km){Ponies}	24	No		

12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead : Of area of 3 sqm. and below	07	No.		
13	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 meters lead.	2161.98	Kg		
14	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : G.S. Sheet	203.94	Sqm		
15	Fixing and fitting of Chinaware i.e EWC, flushing cistern, washbasin, Looking mirror, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including testing and cost and carriage of G.I fittings by Head Load etc complete Job.				
	a) Washroom	01	No.		
Total cost of bid (to be quoted both in figures and words)					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Stage contract for the snow clearance (with frost) from Entrance and Exit stairs, path from Helipad to Entrance Stairs and other adjoining sites before the commencement of Yatra 2021 at Holy Cave.

**S.No :10**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>
1	Clearing snow with frost including gulla cutting in compressed snow and disposal at nearby designated site.	As per actual at site.	Cum	

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Stage contract for the snow clearance (with frost) from Hutment area, Pandal area, Base Hospital site, Cloak Room , Shoe Rack site and from other Shed site before the commencement of Yatra at Holy Cave.

**S.No : 11**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>
1	Clearing snow with frost including gulla cutting in compressed snow and disposal at nearby designated site.	As per actual at site.	Cum	

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Stage contract for the snow clearance (with frost) from Base Hospital and Toilet site area before the commencement of Yatra 2021 at Lower Holy Cave.

**S.No : 12**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>
1	Clearing snow with frost including gulla cutting in compressed snow and disposal at nearby designated site.	As per actual at site.	Cum	

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Stage contract for the snow clearance (with frost) from Camp Directors' Hut area, Heliservices Staff accommodation and Service providers area before the commencement of Yatra 2021 at Lower Holy Cave.

**S.No : 13**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>
1	Clearing snow with frost including gulla cutting in compressed snow and disposal at nearby designated site.	As per actual at site.	Cum	

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Construction of approach path from VIP helipad at Holycave to Main entrance steps at Holycave for Yatra-2021.**

**S.No: 14**

**Adv. Amount: Rs. 6.60 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	6.46	cum		
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m in -All kinds of soil.	158.67	sqm		

3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	18.39	cum		
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	6.46	cum		
5	Cement concrete pavement with 1:2:4 (1cement: 2 coarse sand: 4 graded crushed stone aggregate 20 mm nominal size) including finishing and curing complete.	13.79	cum		
6	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	76.54	sqm		
7	Supply and fixing of 6mm thick ply for expansion joints.	185.00	meter		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars <b>6mm</b> of grade Fe-500D or more.	270.44	Kgs		



9	Carriage by MT for 70 Km lead:				
	a. Cement	8.96	Tonne		
	b. Steel	0.269	Tonne		
	c. Ply	0.08	cum		
10	Carriage by Head load for:				
	a) Cement(12 Km lead from Dumail to Holycave ) :	90	Ponies		
	b) Steel(12 Km lead from Dumail to Holycave ):	5	Ponies		
	c) Ply (12 Km lead):	2	Porters		
	d) Sand and stone aggregate(5Km lead):	35.91	cum		
	e) Stone aggregate 40mm size for 1 Km	16.36	cum		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Construction of approach path from Market area to Access control Gate at Holycave for Yatra-2021.**

**S.No: 15**

**Adv. Amount: Rs.13.45 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	11.40	Cum		
2	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 Sqm on plan including disposal of excavated earth, lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil :	342.00	Sqm		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded	38.00	Cum		

	stone aggregate 40 mm nominal size)				
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	11.40	Cum		
5	Cement concrete pavement with 1:2:4 (1cement: 2 coarse sand: 4 graded crushed stone aggregate 20 mm nominal size) including finishing and curing complete.	28.50	Cum		
6	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	129.20	Sqm		
7	Supply and fixing of 6mm thick ply for expansion joints.	669.00	Meter		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars 6mm of grade Fe-500D or more	501.86	Kg		
9	Carriage by MT for 70 Km lead:				
	a. Cement	18.088	Tonne		
	b. Steel	0.5018	Tonne		
	c. Ply	0.30	Cum		
10	Carriage by Head load for:				

	a) Cement(12 Km lead from Dumail to Holycave ) :	181	Pony		
	b) Steel(12 Km lead from Dumail to Holycave ):	08	Pony		
	c) Ply (12 Km lead):	09	Porter		
	d) Sand and stone aggregate(5 Km lead):	70.455	Cum		
	e) Stone aggregate 40mm size for 1 Km	34.71	Cum		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE - B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Construction of Substructure of 02 No. Huts of size 16'-00" x 16'-00" each with attached washrooms and 02 No. Kitchen of Size 8'-00" x 10'-00" for Heli-services staff at Lower Holy Cave for Yatra-2021.**

**S.No: 16**

**Adv. Amount: Rs. 3.20 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder (in Rs.)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	7.18	Cum		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	8.78	Cum		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	7.30	Cum		
4	Providing and laying in position cement concrete of	0.92	Cum		

	specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)				
5	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	39.96	Sqm		
6	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	65.34	Sqm		
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	5.74	Cum		
8	Providing and fixing strips in joints of terrazzo/ cement concrete floors. Glass strips-40 mm wide and 4 mm thick	78.00	Meter		
9	Carriage of materials by MT:- a) Cement (73 Km)	4.60	Tonne		
10	Carriage by Head Load for: b) Sand and stone aggregate(5Kmlead)	17.25	Cum		
	c) Metal (0.50 Km)	7.90	Cum		
	d) Cement and all other items (12 Km) (i) Ponies:	46	Pony		

11	Fixing and fitting of Chinaware i.e EWC, flushing cistern, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including cost and carriage of G.I fittings, testing and hire charges of Tools and plants required for the completion of job. a) Washroom	02	No.		
Total cost of bid (to be quoted both in figures and words)					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Carriage, erection /assembling of old Way Side Rest Shelters and fencing around Medical Camps enroute Dumail to Kalimata Track and Panjtarni to Sangam Top before commencement of Yatra and dismantling and safe storage after culmination of Yatra.

**S. No. 17**

**Adv. Amount: 1.31 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs.)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Assembling/erection of the wayside shelters, fixing of PPGI sheet roofing with nuts and bolts of approved brand and size including carriage of material from nearest stacking place/SASB store to designated site (complete job)	10	No.		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	2.53	Cum		
3	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deported in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m. in all kind of soil.(04 Spots)	100	No		



4	Fixing of steel angle iron posts and struts of required size Angle size 45x45x6 available in SASB store including carriage from store to site of erection.(04 Spots) Mazdoor	08	Day		
5	Providing & Fixing of agro net of 1.8 metres height of approved brand and type including proper tightening with required arrangement..(04 Spots)	230.40	Sqm		
6	Dismantling of agronet fencing and angle iron post including carriage and stacking in SASB store after culmination of Yatra.(04 Spots) Mazdoor	12	No		
7	Dismantling of wayside shelters and safe stacking in the nearest SASB store/stacking site as per directions of Engineer-in-charge. After culmination of Yatra (complete job)	10	No.		
8	Carriage of cement and all other items by Mechanical Transport for lead of 73 Km	0.8	Tonn		
9	Carriage of Cement and all other items by head load from Dumail to Railpathri/Brarimarg Ponies	8	Pony		
10	Carriage of Sand and stone aggregates by head load for an avg lead lead of 4 Km	3.41	Cum		
Total cost of bid (to be quoted both in figures and words)					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Construction of the substructure of 01 No. Hut of size 16'-00" x 16'-00" with attached washroom and 01 No. Kitchen of Size 8'-00" x 10'-00" for Heli-services staff at Sangam Top for Yatra-2021.**

**S.No: 18**

**Adv. Amount: Rs. 1.40 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	3.59	Cum		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	4.39	Cum		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal	3.65	Cum		

	size)				
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.46	Cum		
5	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	19.98	Sqm		
6	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	32.67	Sqm		
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	2.87	Cum		
8	Providing and fixing glass strips in joints of terrazzo/ cement concrete floors. Glass strips- 40 mm wide and 4 mm thick	39.00	Meter		
9	Carriage of material by MT from Ganderbal to Dumail for an avg lead of 73 Kms	2.35	Tonne		

10	Carriage by Head Load for:				
	a) Sand and stone aggregate(3Kmlead)	7.71	Cum		
	b) Metal (2 Km from Lower Holy Cave to Sangam)	3.95	Cum		
	c) Cement and all other items (11 Km): Ponies	23	No		
11	Fixing and fitting of Chinaware i.e EWC, flushing cistern, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including carriage by both Mechanical Transport and Head Load ,testing and cost/Hire Charges of tools and plants required for completion of job. a) Washroom	01	No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Construction of the substructure of 01 No. Double room Camp Director Hut (2x12'-00"x11'-00") with attached washroom of size(2x6'-00"x4'-6") and 01 No. Kitchen of size 8'-00" x10'-00" at Sangam Top for Yatra-2021.

**S.No:19**

**Adv. Amount: Rs. 1.85 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	7.29	Cum		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	5.21	Cum		

3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	6.73	Cum		
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.623	Cum		
5	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	45.82	Sqm		
6	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20mm nominal size stone aggregate.	27.51	Sqm		
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	5.10	Cum		
8	Providing and fixing glass strips in joints of terrazzo/ cement concrete floors. Glass strips-	30.48	Meter		

	40 mm wide and 4 mm thick				
9	Carriage of material by MT from Ganderbal to Dumail for an avg lead of 73 Kms	3.00	Tonne		
10	Carriage by Head Load for: d) Sand and stone aggregate (3Km lead) e) Metal (2 Km from Lower Holy Cave to Sangam) f) Cement and all other items (11 Km): Ponies Porters	11.03 4.64  30 01	Cum Cum  No No		
11	Fixing and fitting of Chinaware i.e EWC, flushing cistern, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including carriage by both Mechanical Transport and Head Load ,testing and cost/Hire Charges of tools and plants required for completion of job. a) Washroom	         02	         No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Finishing/flooring of Store at Brarimarg and conversion of one room into residence with attached washroom of Camp Director Brarimarg .**

**S.No: 20**

**Adv. Amount: Rs. 3.18 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in 60% all kinds of soil,30% ordinary rock and 10% hard rock.	2.09	Cum		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal	5.34	Cum		



	size)				
3	Random Rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 Cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) upto plinth level and curing complete with: Cement mortar 1:6 (1 Cement : 6 coarse sand)	1.38	Cum		
4	Providing and laying damp-proof Course 50 mm thick with cement concrete 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate 20 mm nominal size) and curing complete	1.86	Sqm		
5	Random Rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including levelling up with cement concrete 1:6:12 (1 Cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) and curing complete at window sills, ceiling level and the like: Cement mortar 1:6 (1 Cement : 6 coarse sand)	3.21	Cum		
6	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	1.38	Cum		
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands,	0.26	Cum		

	plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)				
8	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50mm thick with 20 mm nominal size stone aggregate.	50.30	Sqm		
9	20mm Cement plaster of mix: 1 : 4 ( 1 cement : 4 fine sand)	59.26	Sqm		
10	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	59.26	Sqm		
11	Pointing on stone work with cement mortar 1 : 3 (1 cement : 3 fine sand) Raised and cut pointing	26.88	Sqm		
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	26 .00	Kg		
13	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases of columns etc. for mass concrete.	3.80	Sqm		
14	Labour for opening of roofing – Mazdoor	04	Day		

15	Fixing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead.	67.00	Sqm		
16	Providing and fixing strips in joints of terrazzo/ cement concrete floors. 11.16.1 Glass strips 40 mm wide and 6 mm thick	47.94	Sqm		
17	Carriage of materials i.e cement , steel and paint by MT for 73 kms from Ganderbal to Dumail	3.315	Tonne		
18	Carriage of cement, glass strips, windows, door and steel by head load for lead of 6 kms from Dumail to Brarimarg a) Ponies b) Porters c) Sand and stone aggregate (6 Km lead) d) Stones (2 km lead)	32 04 15.37 4.59	No. No. Cum Cum		
19	Fixing and fitting of Chinaware i.e EWC, flushing cistern, washbasin, Towel Rod, Looking mirror, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including carriage by Head Load from Baltal Store to site of installation at Brarimarg and testing and cost/Hire Charges of tools and plants required for completion of job including excavation of cess pit(if required).  b) Washroom	01	No.		
20	Electrification of Brarimarg store, Camp Director Room with attached washroom including fixing of all electronic gadgets and cost of screws and gutties but excluding cost of all electrical material including carriage from Baltal store to site of installation.	01	No.		

	(Labour only)				
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 at Baltal Camp.**

**S.No: 21**

**Adv. Amount: Rs. 3.78 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Assembling of toilets/baths at designated sites (before commencement of Yatra) including:- (i) Carriage from store to site of installation by head load. (ii) Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply of nuts & bolts etc of required size and number.				

	(iii) Maintenance of structure and sewerage system of Toilet/Baths during Yatra and Fixing/Laying of PVC disposal pipes with all fittings and excavation/ repair to the cess pits including covering of the same with available material etc. (Complete Job)				
	a) Indian Type Toilets/Baths	490	No.		
	b) European water closet including cost of fittings i.e CP connection, G.I pipe, G.I fittings but excluding the cost of WC, Seat cover, flushing Cistern, Bib Cock, Angle Valve etc. (Complete Job)	60	No.		
2	Dismantling of toilets/baths and carriage of material from erection site for safe storage to designated site as per direction of Engineer in charge after conclusion of Yatra.				
	a) Indian Type Toilets/Baths	490	No.		
	b) EWC including complete fittings	60	No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 at Neelgrath and enroute Rangamorph to Dumail.**

**S.No: 22**

**Adv. Amount: Rs. 5.67 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs.)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Assembling of toilets/baths at designated sites (before commencement of Yatra) including:- (i) Carriage from store to site of installation by head load. (ii) Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply of nuts & bolts etc of required				

	size and number. (iii) Maintenance of structure and sewerage system of Toilet/Baths during Yatra and Fixing/Laying of PVC disposal pipes with all fittings and excavation/ repair to the cess pits including covering of the same with available material etc. (Complete Job) a) Indian Type Toilets/Baths  b) European water closet including cost of fittings i.e CP connection, G.I pipe, G.I fittings but excluding the cost of WC, Seat cover, flushing Cistern, Bib Cock, Angle Valve etc. (Complete Job)	500  100	No.  No.		
2	Dismantling of toilets/baths and carriage of material from erection site for safe storage to designated site as per direction of Engineer in charge after conclusion of Yatra.  a) Indian Type Toilets/Baths  b) EWC including complete fittings	500  100	No.  No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 enroute Dumail to Holycave.**

**S.No: 23**

**Adv. Amount: Rs. 1.73 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs.)</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Assembling of toilets/baths at designated sites (before commencement of Yatra) including:- (i) Carriage from store to site of installation by head load. (ii) Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply of nuts & bolts etc of required size and number. (iii) Maintenance of structure and sewerage system of Toilet/Baths during Yatra and Fixing/Laying of PVC disposal pipes with all fittings and excavation/ repair to				



	the cess pits including covering of the same with available material etc. (Complete Job) a) Indian Type Toilets/Baths  b) European water closet including cost of fittings i.e CP connection, G.I pipe, G.I fittings but excluding the cost of WC, Seat cover, flushing Cistern, Bib Cock, Angle Valve etc. (Complete Job)	145  15	No.  No.		
2	Dismantling of toilets/baths and carriage of material from erection site for safe storage to designated site as per direction of Engineer in charge after conclusion of Yatra.  a) Indian Type Toilets/Baths  b) EWC including complete fittings	145  15	No.  No.		
3	Carriage of PVC pipes with fittings, flushing tanks, seat covers etc by Head Load from store at Baltal to enroute Railpathri, Brarimarg and Sangam. Porters:	06	No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Assembling/erection of Toilet/Baths including repairs before commencement of Yatra and dismantling and safe storage in SASB stores after conclusion of Yatra-2021 at Holycave.**

**S.No: 24**

**Adv. Amount: Rs. 3.00 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Assembling of toilets/baths at designated sites (before commencement of Yatra) including:- (i) Carriage from store to site of installation by head load. (ii) Minor repairs such as denting, welding & fixing of aldrops and handles etc including supply of nuts & bolts etc of required size and number. (iii) Maintenance of structure and sewerage system of Toilet/Baths during Yatra and Fixing/Laying of PVC disposal pipes with all fittings and excavation/ repair to the cess pits including covering of the same with available				

	material etc. (Complete Job) a) Indian Type Toilets/Baths	280	No.		
	b) European water closet including cost of fittings i.e CP connection, G.I pipe, G.I fittings but excluding the cost of WC, Seat cover, flushing Cistern, Bib Cock, Angle Valve etc. (Complete Job)	20	No.		
2	Dismantling of toilets/baths and carriage of material from erection site for safe storage to designated site as per direction of Engineer in charge after conclusion of Yatra.  a) Indian Type Toilets/Baths	280	No.		
	b) EWC including complete fittings	20	No.		
3	Carriage of PVC pipes with fittings, flushing tanks, seat covers etc by Head Load from store at Baltal to Holycave Porters:	16	No.		
Total cost of bid (to be quoted both in figures and words)					

**Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.**

**Junior Engineer**

**DGM**

**Signature of Bidder**

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work: Assembling of SASB Huts (Staff 07 Rooms, Base Hospital, Medical and Police Officers Hut, Meeting Hall, JK Bank Hut) at HolyCave before start of Yatra and its dismantling and safe stacking after conclusion of Yatra 2021.**

**S.No: 25**

**Adv. Amount: Rs. 2.80 lakh**

<b>S. No.</b>	<b>Particulars of Items</b>	<b>Approx. Quantity</b>	<b>Unit</b>	<b>Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)</b>	<b>Amount (in Rs. )</b>
<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>	<b>V</b>	<b>VI</b>
1	Fixing wood work in frames of false ceiling, partitions etc. sawn and fixed in position : Budloo/Fir Wood. (Labour rate)	4.873	Cum		
2	Fixing CGI.PPGI sheets for roofing, vertical walls, ridges, hips, valleys etc fixed with nails, washers, J or L hooks etc complete.	669.03	Sqm		
3	Fixing teak wood/hard board for ceiling, partition door and window etc and wall lining of Huts etc complete fixed with required nails and washers etc.	81.21	Sqm		

4	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 meters height including stacking the material within 50 meters lead : Of sectional area 40 sqcm. and above	5.17	Cum		
5	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : G.S. Sheet	702.77	Sqm		
6	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 meters lead : Thickness above 10 mm upto 25 mm	81.21	Sqm		
7	Electrification of Huts with washroom including fixing of all electronic gadgets and cost of screws and gutties but excluding cost of all electrical material. (Labour only)	03	No.		
8	Fixing and fitting of Chinaware i.e EWC, flushing cistern, washbasin, Towel Rod, Looking mirror, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including testing and cost/Hire Charges of tools and plants required for completion of job: Washroom	11	No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling/Erection of one no. Double room Hut (size 32'x16') with attached washrooms for Camp Directors and construction of Kitchen shed at Lower Holycave for Yatra 2021.

**S.No: 26**

**Adv. Amount: Rs. 1.31 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Fixing wood work in frames of false ceiling, partitions etc. sawn and fixed in position : Budloo/Fir Wood	1.584	Cum		
2	Fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per Sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat	136.80	Sqm		

	15-18 microns. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
3	Fixing teak wood/hard board for ceiling, partition door and window etc and wall lining of Huts etc complete fixed with required nails and washers etc.	106.75	Sqm		
4	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 meters height including stacking the material within 50 meters lead : Of sectional area 40 sqcm. and above	1.584	Cum		
5	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : G.S. Sheet	136.80	Sqm		
6	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 meters lead : Thickness above 10 mm upto 25 mm	106.75	Sqm		
7	Engagement of labour for Dismantling and safe stacking of sanitary and electrical items. Asst Fitter (Grade II)=	02	No		
8	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position : Budloo / Fir wood	0.152	Cum		

9	Providing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface)excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gram/m2.	21.46	Sqm		
10	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 meters height including stacking the material within 50 meters lead : Of sectional area 40 sqcm. and above	0.152	Cum		
11	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : G.S. Sheet	21.461	Sqm		
12	Carriage of materials by Mechanical Transport for 73 Kms lead from Ganderbal to Dumail.				
12.1	Wood/Timber	0.152	Cum		
12.2	CGI sheets	0.106	Tonne		
13	Carriage of materials by Head Load for 12 Kms lead from Dumail to Holycave. Wood & CGI sheets. Ponies:	03	Pony		
<b>Total cost of bid (to be quoted both in figures and words)</b>					



Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Carriage, assembling of Pandal at Holy Cave including their carriage upto site of erection/assembling and dismantling the same and carriage upto safe storage site after the culmination of Yatra (16 rooms of size 3.45 m x 3.45 m) .

**S.No:** 27

**Adv. Amount:** Rs. 1.72 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Assembling of Pre-fab PPGL sheet panels of Pandal with repair to doors, windows etc complete with MS tube 50x25x3 mm and PPGL sheet 1 mm thick with proper nuts & bolts including cost of carriage from SASB store to erection site before commencement of Yatra.	602.24	Sqm		
2	Dismantling of PPGL sheet panels of Pandal including proper stacking of material at appropriate designated site as per direction of Engineer-in-charge. Qty. vide Item 1 =	602.24	Sqm		

4	Add for repairs to damaged frames/panels including welding, straightening and fitting of hardware items wherever necessary :- a) Hire charges of Genset, welding set including cost of electrodes and POL etc complete. b) Blacksmith(2 <sup>nd</sup> class) c) Helper	02  02. 02	Day  Day Day		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

## **SCHEDULE – B (Format for Financial Bid)**

### **Rate List/ Quantity Schedule**

**Name of Work:** Assembling and fixing of one No. CR sheet Hut comprising of 4 rooms of size 3.5m x 4.0 m each with attached washrooms at Holy Cave, assembling and erection of PPGI sheet single room Huts of size 3.0mx3.0m each with attached washroom at Holycave and Brarimarg including carriage to and fro SASB stores and dismantling after conclusion of Yatra-2021.

S.No: 28

Adv. Amount: Rs. 1.40 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Assembling of prefab panels of CR sheet Hut including fixing up in position and supply of required nuts & bolts etc complete with fixing of doors and windows at appropriate position with head load of material etc complete.	235.85	Sqm		

2	Dismantling roofing , walling including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : CR sheet	235.85	Sqm		
3	Fixing 12 mm thick plywood wall lining over wooden frame for 04 Rooms with available material including supply of nails etc of required size for fixing and fixed up in position all complete including required frame work for fixing of ply wood with all carriage of material.	160.4	Sqm		
4	Dismantling of ply wood wall lining including proper stacking & dismantling of CR sheet panels from installation site with proper stacking at appropriate place including dismantling of wall lining.	160.4	Sqm		
7	Supply of skilled and semiskilled person for dismantling of PVC pipes for main sewer line and pipe having thermal stability including dismantling of all sanitary items including safe stacking at appropriate designated site. a) Blacksmith 2 <sup>nd</sup> class b) Helper	02 02	No. No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

**SCHEDULE – B (Format for Financial Bid)****Rate List/ Quantity Schedule**

**Name of Work:** Assembling of dismantled portion of Base Hospital at Lower Holycave and dismantling and safe stacking after conclusion of Yatra 2021.

**S.No: 29**

**Adv. Amount: Rs. 1.56 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSR 2020 (inclusive of GST)	Amount (in Rs. )
I	II	III	IV	V	VI
1	Fixing CGI/PPGI sheets for roofing,vertical walls,ridges,hips,valleys etc fixed with nails, washers, J or L hooks etc complete.	193.59	Sqm		
2	Fixing of ridge with nails, washers, etc complete.	14.02	Meter		
3	Fixing wood work in frames of false ceiling, partitions etc. sawn and fixed in position : Budloo/Fir Wood excluding	2.265	Cum		

	cost of wood (Labour rate)				
4	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10Sqm)	200.47	Sqm		
5	Fixing teak wood/hard board for ceiling, partition door and window etc and wall lining of Huts etc complete fixed with required nails and washers etc.	117.10	Sqm		
6	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : G.S. Sheet	207.61	Sqm		
7	Dismantling wood work in frames, trusses, purlins and rafters upto 10 meters span and 5 meters height including stacking the material within 50 meters lead : 15.14.1 Of sectional area 40 sqcm. and above	2.265	Cum		
8	Dismantling of 4 mm thick ply after conclusion of Yatra including carriage and safe stacking in designated SASB stores.	117.10	Sqm		
9	Carriage of Water proofing cement paint . A) By MT for 73 Km Lead B) By Head Load for 12 Km lead	0.076 1	Tonne Pony		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

