

Shri Amarnathji Shrine Board



Jammu and Kashmir

TENDER DOCUMENT

FOR

Civil Works along Pahalgam axis

comprising of ;

**(Nunwan, Chandanwari, Sheshnag, and Enroute from
Chandanwari to M.G Top**

for

Yatra - 2021

Sd/-

General Manager (Works)
Shri Amaranthji Shrien Board

12.02.2021

CIVIL WORKS ALONG PAHALGAM AXIS FOR YATRA 2021

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no. SASB/Works/W/1279/2021/ 07 dated 12.02.2021)

S. No.	CONTENT	PAGE(S)
1.	Notice Inviting Tender (NIT) for advertisement	3-6
2.	Eligibility Criteria	7
3.	Documents establishing Bidder's eligibility	7
4.	Instructions to Bidders	8-10
5.	Terms and Conditions of Contract	10-13
6.	Schedule – A (Technical Bid)	14-15
7	Bid Securing Declaration (Format)	16
7.	Schedule – B (Financial Bid)	17-48



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov - April)

Tele: 0191-2555662, Telefax: 0191-2503399

NOTICE INVITING TENDER CIVIL WORKS ALONG PAHALGAM AXIS FOR YATRA - 2021

For and on behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from experienced and financially sound registered **PWD Contractors** having a valid registration, for the execution of Civil Works as mentioned below, .The bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **03.03.2021** upto **1400 hours**.

S. No.	Name of work	Estimated cost (Rs in lakh)	Cost of bid document (in Rs)	Earnest Money/ Bid Security (in Rs)	Class of Contractor	Time of Completion
1	Improvement to fire gaps by way of cleaning of Kacha drains including removal of vegetation and grass of Camp area at Nunwan Camp.	0.40	100/-	Bid Securing Declaration to be made by the bidder in the shape notarized sworn statement on prescribed Format	DEE	7 days
2	Repair, rewriting and installation of Sign Boards including dismantling after conclusion of Yatra with safe storage at Nunwan Camp.	0.50	100/-		DEE	7 days
3	Providing of Pre cast tiles to paths from B-15 to Sadhu sheds for convenience of Yatris at Nunwan Camp =400 rft.	2.85	300/-		DEE	15 days
4	Repair, rewriting and installation of Sign Boards including dismantling after conclusion of Yatra with safe storage at Chandawari, Sheshnag and enroute from Chandawari to MG Top.	0.80	100/-		DEE	12 days
5	Installation of urinal points covered with PPGI sheets on mild steel frame at frisking Gate including dismantling after conclusion of Yatra at Nunwan and Chandawari.	0.50	100/-		DEE	7 days
6	Construction of one no. shed (wooden frame with PPGI sheet covering) comprising of 04 no. rooms for seasonal workers at Nunwan Camp.	3.00	300/-		DEE	15 days
7	Construction of platform for Nandi ji at Nunwan Base Camp.	4.50	400/-		DEE	15 days
8	Assembling/ installation of 08 no. wash basins (stainless steel) at C/wari and enroute from C/wari to Sheshnag with all carriage of material and dismantling after conclusion of Yatra including their carriage upto safe storage site.	0.32	100/-		DEE	7 days
9	Construction of soakage pits for Medical Camp and CRPF Camp at					

	Main Gate Chandanwari by way of using cement concrete collar (rings with required cover 04 Nos. at Chandanwari (10 Ft depth).	0.54	100/-		DEE	7 days
10	Construction of scanning cabin shed 01 No. (wooden frame with PPGI sheet covering) at entry point at Lower Camp Sheshnag including dismantling after Yatra with proper stacking at SASB store	1.30	100/-		DEE	10 days
11	Construction of PPGI shed (wooden frame with PPGI sheet covering) for Yatra counting/ frisking of Yatris at exit gate Sheshnag Camp.	1.30	100/-		DEE	12 days
12	Erection of fencing around Medical Camps by way of fixing M.S. angle posts and providing agronet from Chandanwari to MG Top.	1.50	150		DEE	12 days
13	Erection of way side resting shelter sheds at existing places from Chandanwari to M.G. Top (10 spots) with all carriage of material upto installation site before start of Yatra and its dismantling after conclusion of Yatra including repair to damaged shelter sheds complete.	1.00	100/-		DEE	12 days
14	Removal of snow before start of Yatra – 2021 at Sheshnag & M.G. Top (subject to actual at site).	-	100/-		DEE	7 days
15	Assembling/ erection of prefabricated toilets, baths (140 nos.) Including cost of its dismantling during or after Yatra – 2021 at outside Nunwan Camp.	1.94	200/-		DEE	15 days
16	Assembling/ erection of prefabricated toilets, baths (120 nos.) including cost of its dismantling during or after Yatra – 2021 at Lower Camp Chandanwari.	1.60	200/-		DEE	15 days
17	Assembling/ erection of prefabricated toilets, baths (100 nos.) including cost of its dismantling during or after Yatra – 2021 at Upper Camp Chandanwari.	1.42	100/-		DEE	15 days
18	Assembling/ erection of prefabricated toilets, baths (100 nos.) including cost of its dismantling during or after Yatra – 2021 in B Block at Sheshnag Camp	1.46	100/-		DEE	15 days
19	Assembling/ erection of prefabricated toilets, baths (100 nos.) including cost of its dismantling during or after Yatra – 2021 in Block A & C at Sheshnag Camp	1.46	100/-		DEE	15 days
20	Assembling/ erection of prefabricated toilets, baths (112 nos.) including cost of its dismantling during or after Yatra – 2021, outside at Sheshnag Camp	1.87	200/-		DEE	18 days

21	Assembling/ erection of prefabricated toilets, baths (75 nos.) including cost of its dismantling during or after Yatra – 2021, enroute from Chandanwari to Km 5.5 including Pissu Top.	1.40	100/-		DEE	15 days
22	Assembling/ erection of prefabricated toilets, baths (75 nos.) including cost of its dismantling during or after Yatra – 2021, enroute from Km 5.5 to Naga Koti including Zojibal.	1.42	100/-		DEE	15 days
23	Assembling/ erection of prefabricated toilets, baths (60 nos.) including cost of its dismantling during or after Yatra – 2021, from Sheshnag to M.G Top.	1.06	100/-		DEE	12 days
24	Providing and fixing of fitting items to European type toilets from Nunwan to M.G. Top (100 nos.)	1.50	150/-		DEE	15 days
25	Assembling of (02 no.) sheds with attached kitchen and waiting shed for free Medical Camp at Chandanwari Camp.	0.84	100/-		DEE	7 days
26	Assembling of prefabricated, Administrative huts (04 nos.) with minor repair including dismantling and stacking of material after conclusion of Yatra at Sheshnag Camp.	1.60	200/-		DEE	15 days
27	Providing and fixing of sanitary fittings to attached baths of Administrative & Outsourced huts 23 Nos. with minor repairs at Sheshnag Camp.	1.00	100/-		DEE	7 days
28	Covering of SASB area (Administrative Block) by way of providing available CGI sheet panels for fencing at Sheshnag Camp.	0.35	100/-		DEE	7 days
29	Repairs to CCTV camera cabin at Access Control Gate at Chandanwari.	0.25	100/-		DEE	7 days
30	Repairs the PVC pipe network of toilets/ baths with construction of regular manholes from erected Prefab toilets to main sewer line by using heavy grade (B Type PVC pipes) inside Nunwan Camp.	1.00	100/-		DEE	7 days

- Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from **9.30 AM to 5.00 PM**, on any working day from **12.02.2021 to 02.03.2021** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu.
- The Tenders, duly completed, along with **Bid Securing Declaration**, must reach the office of General Manager (Works) latest by **1400 hours on 03.03.2021**. The bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo,

Jammu. Alternatively, they may send the same through speed post/ registered post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reasons.

4. The Technical bid shall be opened on **04.03.2021** at **10. 00 am** in the office of General Manager (Works), (at Jammu Office; address mentioned above) in presence of the bidders who may wish to be present on the occasion.
5. Not more than three bid documents shall be issued to a single bidder.
6. In case the last date of receipt of bid happens to be a holiday, the bid shall be received on the next working day up to **1400 hours**.
7. The successful bidder is bound to enter into an agreement with General Manager (Works), SASB, **within ten days** from the date of the receipt of Letter of Intent.

No: SASB/NIT/W/1279/2021/07
Dated: 12.02.2021

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

II ELIGIBILITY CRITERIA

The Bidder must be a Contractor (registered with J&K, PWD, CPWD) and must fulfil all the following eligibility requirements concurrently to technically qualify for this bidding process:

Average Annual Turnover during the last three years, ending 31st March of the previous financial year (i.e. 2017-18, 2018-19, 2019-20) should be 30% of the advertised cost.

2.2 The bidder should have an experience of having successfully completed similar works in Hilly Regions during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-

Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or

b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or

c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.

2.3 The Bidder should not have been blacklisted on an earlier occasion by any of the Union Territory Government Organizations, U.T Autonomous Bodies or Local Bodies/ Municipalities.

III DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

3.1 Registration Certificate.

3.2 Certified copies of Annual Turnover from Bank

3.3 Certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works, for fulfilling the eligibility criteria.

3.4 Certified copy of PAN Card.

3.5 Certified copy of GSTIN.

3.6 General Profile of the Bidder

3.7 Bid Security Declaration.

3.8 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect during technical evaluation or during execution of work, the following penalties are to be imposed;

i. in case the work is allotted to the agency, the contract shall be terminated and work executed through an alternate agency at the risk & cost of the allottee,

ii. Earnest Money Deposit, if deposited shall be forfeited

iii. the bidder/ allottee shall be debarred from tendering in SASB for next three years.

IV. **INSTRUCTIONS TO BIDDERS:**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from **9.30 AM to 5.00 PM** on any working day till **02.03.2021** on payment of cost of Tender Document prescribed against each work in the DNIT in cash or in the shape of a Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB).
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed **“Technical Bid for the work of _____ Yatra 2021”** and **“Financial Bid for the work of _____ Yatra 2021”**. Both the sealed envelopes should be put in a third envelop, sealed and superscribed **“Tender for the work of _____ (Yatra 2021)” mentioning NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The bids, duly completed, along with **Bid Securing Declaration** must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered Speed Post to General Manager (Works), SASB at the aforesaid address, so as to reach latest on **03.03.2021 (1400 hours)**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by speed post.
- 4.4 The cost of DNIT should be placed inside the envelope containing the Technical bid and Bid Security Declaration.
- 4.5 It would be deemed that by submitting the bid, the bidder has made complete examination of the DNIT, received all information from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 4.7 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid not substantially responsive to the DNIT in every respect will be at bidder's risk and may result in the rejection of the bid.
- 4.8 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be indicated in words as well as in figures. In case of any variation between

amount in figures and words, amount quoted in words shall be taken as authentic.

- 4.9 The rate quoted by the Contractor in item rate tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.10 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the bidder. The bidder must also sign and stamp all pages of this DNIT as acceptance of all conditions contained therein and for the purpose of identification. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.11 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The General Manager (Works) may, at his discretion, extend the deadline for submission of bids. Any bid received after the last date/ time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.12 Clarifications, if any, may be sought by the bidders so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by General Manager (Works), SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hoisted on SASB website (www.shriamarnathjishrine.com) and NOT in newspaper(s). The bidders should keep themselves updated on this account.
- 4.13 The Technical Bid shall be opened on **04.03.2021 at 10.00 am** in the office chamber of General Manager (works) in the presence of the authorized representatives of the bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.14 The General Manager (Works), SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.15 The bid shall remain valid and open for acceptance for a period (i.e. Bid Validity Period) of **60 days from the last date prescribed for its receipt.**
- 4.16 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.

- 4.17 The General Manager (Works) may award the Contract to the bidder whose bid has been evaluated to be responsive and who is eligible and qualified to perform the Contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible bidder a letter (hereinafter referred to as the 'Letter of Intent') prescribing the amount which the Shrine Board will pay to the eligible bidder in consideration of work/ services to be executed by the eligible bidder as prescribed in the Contract.
- 4.18 The eligible bidder will have to enter into an agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the **ten days** of the receipt of Letter of Intent.
- 4.19 General Manager (Works), SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reasons thereof. Any enquiry after the submission of tender will not be entertained.
- 4.20 Shri Amarnathji Shrine Board shall not be responsible for release of any DD/ CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the DDs/ CDRs of unsuccessful bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

V. TERMS AND CONDITIONS OF THE CONTRACT:

- 5.1 The bidders are required to quote rate above/ below percentage on SSR of 2020 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. All rates/ percentages should be quoted in figures and words. The bidders must also calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 5.2 Bids shall have to be submitted separately for each work as indicated in the NIT.
- 5.3 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- | | | |
|-------|---|---|
| (i) | First 3 days of delay | Penalty 1% of contract value. |
| (ii) | 4 th day upto 10 th day | 2% of contract value |
| (iii) | Beyond 10 days | Earnest Money Deposit shall be forfeited and the contract automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost |

of the contractor without issuing any notice to the Contractor / Firm.

- 5.4 Not with standing **Clause 5.3 above** in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 5.5 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).
- 5.6 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per the specification provided in Work Allotment Letter.
- 5.7 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencing the work at site.
- 5.8 The Contractor shall submit **pictorial evidence (Photographs)** of execution of work (post execution, during execution and after completion of work) with his claim.
- 5.9 The contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 5.10 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 5.11 The Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the U.T or Central Government or Local Authority and any other labour laws (including rules), regulations, byelaws that may be passed or notification that may be issued under any labour law in future either by the U.T. or the Central Government or the local authority. The contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.
- 5.12 All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the contract shall be the sole responsibility of the contractor.

- 5.13 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ employees, employed by him for execution of work against any personal injury or death.
- 5.14 The agency shall be solely responsible for **Workmen's Compensation Act**, 1923 for payment of **compensation** to **workmen** and their dependants in case of injury and accident (including certain occupational disease) arising out of and in the course of employment and resulting in disablement or death.
- 5.15 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 5.16 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the Labour Law in Force.
- 5.17 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of **Letter of Intent** (LoI).
- 5.18 General Manager (Works), SASB shall be at liberty to suspend the agreement due to any Force Majeure conditions such as Government regulations, court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.
- 5.19 All disputes and differences between the parties arising out and relating to the agreement to be signed between the General Manager (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 5.20 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the Union Territory of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 5.21 The rates quoted by the contractor shall be inclusive of all taxes e.g. (GST etc) that are in vogue.
- 5.22 If during the period of one year from the date of completion of work, the defects which have been caused by bad workmanship, use of inferior materials on the work, the contractor shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the work shall be got through alternate resourceful agency and the cost thereof shall be recovered from the dues of the contractor.

- 5.23 The Earnest Money Deposit, if any deposited by successful bidder shall be released after completion of work in full and issue of completion certificate by the DGM (P).
- 5.24 The quantities of items of work provided in the NIT as per BOQ are approximate and may increase/ decrease upto 20% during execution of work as per necessity at site.

VI Payment Clause:

- 6.1 Payment shall be made to the contractor for complete item of work including cost of the material and labour (finished) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site (To be maintained for each work at site) duly checked by the Deputy General Manager Works.
- 6.2 The payment to the bidder shall be made after successful completion of work within the stipulated time (as per specifications and Terms and Conditions of agreement) after satisfactory use/ function of the work during complete Yatra Period.
- 6.3 Any extra item (s) executed at site of work shall be paid strictly as per LoA (contractors appreciation/ depreciation on J&K **Sanctioned Schedule of Rates 2020.**)

VII Time of completion:

- 4.8 The time of completion of works stands mentioned against each work in the NIT.
- 4.9 Time of completion shall mean;

Period of time of completion of work in all respects before start of Yatra – 2021 including the period of time involved in completely dismantling of the pre-fabricated structures with due care from damages and safe storage of the materials in the SASB stores to the entire satisfaction of the Deputy General Manager (Works) or his authorised representative.

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND BID SECURING DECLARATION

S. No.	Particular of item	Details
1	Amount and details of payment towards the cost of DNIT:	Rs. (in words):
		Receipt No./ Cheque No:
		Date:
2	Bid Securing Declaration	Dated:
		Bid No.
		Name of Notary

PART – B: BASIC DETAILS ABOUT THE AGENCY.

i) Name and address of :
the Agency.

Name: _____

Address: _____

Phone: _____

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:
(Please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

#	Financial Year	Turnover (Rs.)
1	2017-18	
2	2018-19	
3	2019-20	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (in Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/ No)

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*
5. Certified copy of GSTIN – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*
7. Bid Securing Declaration – *para 3.7 of Documents Establishing Bidder’s Eligibility’*
8. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility.*

Form of Bid Securing Declaration

Date _____

Bid No. _____

The General Manager (Works),

I, the undersigned declare that;

I understand that, according to your suspended bids must be supported by a Bid Securing Declaration.

I accept that undersigned will automatically be suspended from being eligible for bidding in any contract with the Shri Amarnathji Shrine Board for the period of time of three years starting on March, 2021, if undersigned breach the obligations (s) under the bid conditions, because undersigned;

- a). have withdrawn my bid during the period of bid validity specified in the Letter of Bid, or
- b). having been notified of the acceptance of my Bid by the SASB during the period of bid validity of (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with ITB 38.

I understand this Bid- Securing Declaration shall expire if undersigned is not the successful Bidder, upon the earlier of (i) my receipt of your notification to me of the name of the successful Bidder; or (ii) sixty days after the expiration of my Bid.

Name of the person
(Signing the bid securing declaration)

Duly authorized to sign the bid for and on behalf of bidder

Dated on _____ day of _____

Corporate seal
(where appropriate)

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of Work: Improvement/ Cleaning of Kacha drains including removal of vegetation and grass of camp area at Nunwan Camp.

S. No.01

Adv. Cost: 0.40 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	1377	Sqm		
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: {subject to actual requirement}.	10.00	Cum		
3	Supply of labour for up-keeping of Nunwan Camp including washing of Sadhu sheds, laying of mating to Huts sadhu sheds and other allied work before, during and after Yatra.	40	labour		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Repair, rewriting and installation of Sign Boards including dismantling after conclusion of Yatra with safe storage at Nunwan Camp.

S. No.02

Adv. Cost: 0.50 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Repairs the damaged sign Boards by way of fixing of legs repairs the bends and scratches with welding etc. complete job for 40 No boards.	40	Boards		
2	Re-writing of sign boards with approved paint as per requirement/ design including back painting etc complete. Actual as per site for repairs to old boards.	150	Sft		
3	Installation of Sign Board at appropriate sites with proper alignment etc Complete inside Camp and outside Camp including from Km 4th from D/S Nunwan Camp and from Nunwan Camp upto Pahalgam market by way of: Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m. All kind of soil.	150	Post holes		
4	Carriage of available sign boards from store to installation site including loading and unloading etc complete	08	Trips		
5	Dismantling of sign boards from installation site with back carriage and storing with appropriate store complete.	100	No.		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Providing of Pre Cast Tiles to the paths from B-15 to the Sadhu Sheds for convenience of yatris at Nunwan Camp.

S. No.03

Adv. Cost: 2.85 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs.)
I	II	III	IV	VI	VII
1	Chequerred precast cement concrete tiles 22mm thick in footpath and courtyard, jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing, cleaning and curing complete, on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) . Ordinary cement without any pigment.	167.28	Sqm		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) balance quantity of paths.	6.07	Cum		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) for sides of paths.	7.78	Cum		
4	Centering and shuttering including strutting, propping etc. Removal of frame work for foundations, footings, bases of columns etc. for mass concrete.	51.11	Sqm		
5	Carriage of material by M. Transport				
	a. Tiles from Anantnag to Pgm including head load upto site of work	4 trip	Trip		
	b. Sand and aggregates from 50 kms lead	22.03	Cum		
	c. Cement from 20 kms lead	6.80	MT		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Repair, rewriting and installation of Sign Boards including dismantling after conclusion of Yatra with safe storage at Chandanwari, Sheshnag and enroute from Chandanwari to M.G. Top.

S. No.04

Adv. Cost: 0.80 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV		VII
1	Repair, Repainting and re-writing of old available Sign Boards at Chandanwari and Sheshnag with approved paint as per requirement / design etc complete.	50	sft		
2	Erection of Sign Boards at designated sites with excavation of post holes up to 2'.0"depth,including maintenance of Sign Board for entire Yatra period including brought back after conclusion of Yatra with head load and stacking of material at respective stores from Chandanwari to M.G.Top.	124	Board		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Installation of urinal points covered with PPGI sheets on mild steel frame at frisking gate including dismantling after conclusion of Yatra at Nunwan and Chandanwari.

S. No.05

Adv. Cost: 0.50 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV		VII
1	Fixing of PPGI sheet panels all around the urinal blocks including repairs if any, fixed with required nuts and bolts etc complete for roof and walls etc (complete job).	83.66	sqm		
2	Supply and fixing of sanitary items to urinal blocks;				
	Urinal pot (china)	10	No.		
	PTMT Angle valve (15mm N.B)	10	No.		
	PVC connections 45 cm (15 mm)	10	No.		
	Waste pipe for urinal pot	10	No.		
3	Carriage of material by head load from SASB store to working sites	06	labour		
4	Dismantling of urinals blocks after conclusion of Yatra with back carriage of;	83.66	sqm		
	i. PPGI sheet panels (qnty. vide no. 1)				
	ii. Engagement of fitter for dismantling of sanitary items	04	no.		
	iii. Back carriage of material by head load.	06	labour		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Construction of one no. shed (wooden frame with PPGI sheet covering) comprising of 04 no. rooms for seasonal workers at Nunwan Camp.

S. No.06

Adv. Cost: 3.00 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1.	Earth work in surface excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 30cm in width) but exceeding 1.5 cm in width as well as 10sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5mtr including getting out excavated earth and disposal of surplus excavated earth and lead upto 1mtr from cutting edge, in all kinds of soil	92.94	sqm		
2	Excavation post holes upto 0.10 cum including getting out the excavated soil and then returned soil in layers with consolidation etc complete.	15	No.		
3	Wood work in frames of false ceiling, partitions etc sawn and fixed up in position;	3.09	cum		
4	Providing and fixing pre-coated galvanized 0.50 mm +- 0.05% thick fixed with required nuts and bolts or self draven bolts etc	159.48	sqm		
5	Supply and fixing of paneled or paneled and glazed shutters for doors windows and clerestory windows fixing with butt hinges o require size with necessary screws, including paneling, all complete as per direction of Engineer-in -charge. (04 nos.) using second class kail wood.	7.81	sqm		
6	Carriage of material by mechanical transport from Anantnag to Nunwan Camp	3.15	cum		
	i. Wooden struts				
	ii. PPGI sheets	0.757	MT		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Construction of platform for Nandi ji at Nunwan Camp.

S. No.07

Adv. Cost: 4.50 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1.	Earth work in excavation by manual means in trenches for foundation , drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5mtr including getting out excavated earth and disposal of surplus excavated earth and lead upto 1mtr from cutting edge, in all kinds of soil	3.00	cum		
2	Providing and laying of 1:3:6 cement concrete of specified grade including curing but excluding the cost of centring and shuttering all works upto plinth level	6.00	cum		
3	Dumping of stones/ RBM including ramming and cost of stones.	6.38	Cum		
4	Centering and shuttering including propping, strutting and removal of form wok for foundations, footings and bases of columns etc for mass concrete.	25.00	sqm		
5	Providing and laying of flooring with marble stone of specified thickness as per sample of marble approved by engineer-in-charge over 20 mm thick base of cement motor 1:4 laid and jointed with grey cement slurry including subbing polishing and curing complete with Raj Nagar plain 18 mm thick.	15.00	sqm		
6	Structural steel work in built up sections, trenches and framed work including cutting, hoisting, jising in position and applying a prime coat of approved steel primer all complete with welding.	2080	Kg		
7	Supplying and fixing rolling shutters of approved make made of required size ms laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets side guides and arrangements for inside and outside locking with push and pull operation complete including the cost of providing fixing necessary 27.5 cm long wire springs manufactures from high tensile steel wire of adequate strength	29.74	sqm		

	confirming to IS 4454 part and M.S. top cover of required thickness for rolling shutters.				
8	Providing and fixing of pre-coated galvanised iron profile sheets (size , shape and pitch of corrugation as approved by engineer-in-charge) 0.50mm (\pm 0.05%) total coated thickness with zinc coating 120 grams per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns, sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in a single length upto 12 m or as desired by engineer-in-charge. The sheet shall be fixed using self drilling/ self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	16	Sqm		
9	Providing and fixing of pre-coated galvanised steel sheet roofing ridge (500x600mm) using self driven/ self tapping screws.	12.00	rm		
10	Finishing walls with textured exterior paint of required shade on new work (two or more coats applied over and including base coat of exterior primer applied).	25.00	sqm		
11	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade (two or more coats on new work).	58.00	sqm		
12	Chequered precast cement concrete tiles 22 mm thick in footpath and courtyard, jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing, cleaning and curing complete, on 20 mm thick bed of cement mortar 1:4 (1 cement, 4 coarse sand)	30.00	sqm		
13	Carriage of material by mechanical transport from; i. Steel, cement etc. from 50 kms lead	3.50	MT		
	ii. Sand & aggregates from 50 kms avg.	21.60	cum		
	iii. stones from 20 kms avg.	6.38	cum		
	iv. tiles from average lead 50 kms	3 trip	RTQ		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling /installation of 08 no wash basins (stainless steel) at Chandanwari and enroute from C/wari to Sheshnag with all carriage of material and dismantling after conclusion of Yatra including their carriage upto safe storage site.

S. No.08

Adv. Cost: 0.32 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Carriage of wash basins from storage site up to site of installation including; i. Assembling of S.S. wash basins with required nuts/bolts etc, ii. Fixing of GI pipe line inside the wash basin complete, iii. Fixing of required sanitary items i.e. bib cock, pvc connection and waste pipes complete. iv. Fixing of PVC pipes for disposal of water up to appropriate place.	430.50	kgs		
2	Supply of pipes for disposal line 75mm dia fitting items; i. PVC pipe 75 mm dia ii. PVC Tee 75 mm dia iii. PVC bend 75 mm dia iv. Bib cock (PTMT) 15mmdia	48 9 16 12	Rm No. No. No.		
3	Carriage of material from Anantnag to Chandanwari including loading and unloading.	01	trip		
4	Dismantling of wash basins from installation site including head load of material with packing and storing in SASB store.	430.50	kg		
5	Carriage of PVC pipes from Chandnawari to installation site including fitting items up to Sheshnag.	02	pithoo		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Construction of soakage pits for Medical Camp for CRPF Camp at Main Gate Chandanwari by way of using cement concrete collar (rings with required cover) 04 nos. at Chandanwari (10' depth).

S. No.09

Adv. Cost: 0.54 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	26.9	Cum		
2	Additional lift of 1.5 mtr.	11	cum		
3	Supply and fixing of cement concrete rings of requisite dia and thickness including fixing at appropriate position with all carriages leads & lifts etc complete job; i. Precast cast cement concrete Rings ii. Concrete, Cover for pit	60 4	N0 No		
4	Back filling of trench with available excavated material.	19	Cum		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Construction of scanning cabin shed 01 no. (wooden frame with PPGI sheet covering) at entry point at Lower Camp Sheshnag including dismantling after conclusion of Yatra with proper stacking at SASB store.

S. No.10

Adv. Cost: 1.30 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Excavating post holes upto 0.10 cum including cutting out the excavated soil and returning the soil in layers etc including ramming etc by manual means	06	No.		
2	Providing wood work in frames of false ceiling partitions etc sawn and fixed up in position (size of shed 14'x10')	0.80	cum		
3	Providing and fixing of pre-coated galvanized iron profile sheets (PPGI sheets) 0.50mm -+ 0.05% thick fixed with necessary nuts, bolts and nail washers etc a self drawn bolts complete.	52.05	sqm		
4	Carriage of material by mechanical transport from Anantnag to Chandanwari Avg. distance 65 kms				
	i. Timber	0.80	cum		
	ii. PPGI sheets	0.247	MT		
5	Head load of material from Chandanwari to Sheshnag Camp (working site);	35	porters		
6	Dismantling of sheds by way of removing of roofs, side walls etc including stacking of material at appropriate site within 50 meters;				
	i. PPGI sheets	52.05	sqm		
	ii. Wooden struts	103.05	Rm		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Construction of PPGI shed (wooden frame with PPGI sheet covering) for Yatra counting/ frisking of Yatris at exit gate, Sheshnag Camp.

S. No.11

Adv. Cost: 1.30 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder with respect to SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Excavating post holes upto 0.10 cum including cutting out the excavated soil and returning the soil in layers etc including ramming etc by manual means	06	No.		
2	Providing wood work in frames of false ceiling partitions etc sawn and fixed up in position (size of shed 14'x10')	0.80	cum		
3	Providing and fixing of pre-coated galvanized iron profile sheets (PPGI sheets) 0.50mm -+ 0.05% thick fixed with necessary nuts, bolts and nail washers etc a self drawn bolts complete.	52.05	sqm		
4	Carriage of material by mechanical transport from Anantnag to Chandanwari Avg. distance 65 kms				
	i. Timber	0.80	cum		
	ii. PPGI sheets	0.247	MT		
5	Head load of material from Chandanwari to Sheshnag Camp (working site);	35	porters		
6	Dismantling of sheds by way of removing of roofs, side walls etc including stacking of material at appropriate site within 50 meters;				
	iii. PPGI sheets	52.05	sqm		
	iv. Wooden struts	103.05	Rm		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Erection of fencing around medical camps by way of providing of M .S .angle posts and Agronet from Chandanwari to MG Top.

S. No.12

Adv. Cost: 1.50 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r.t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Earth work in excavating upto 0.1 0 cum including getting out the excavated soil, then returning the soil as requires in layer not exceeding 20 cm in depth including consolidating each deposited layer by raining / watering etc, disposal of surplus excavated soil as directed within a lead of 50 mtr. and lift upto 1.5 mtr. In all kinds of soil by manual means.	96	hole		
2	Supply of steel angle iron posts struts of required size including bottom to be split/ bent at right angle in opposite direction for 10 cm length and drilling holes upto 10mm dia etc complete.	400	kg		
3	Providing and laying in position a specified grade cement concrete excluding the cost for centering and shuttering all works up to plinth level in 1:3:6 by using 20mm nominal size nallah aggregates.	2.03	cum		
4	Supply and fixing of agro-net along the MSposts	4000	Sft		
5	Centering and shuttering including propping strutting and removal of form wok from foundation, joisting and pedestals/ bases of columns.	9	sqm		
6	Erection of angle iron posts around Medical Camps including covering with agronet, with required bolts etc (complete) before start of Yatra from Chandanwari to MG Top with all leads of available material from nearby SASB stores and dismantling of all material both new and old after Yatra, complete job.	10	Spot		
7	Carriage of agronet and angle iron by mechanical transport from Anantrag to C/wari	01	trip		
8	Carriage of agro-net, cement & angle iron posts by head load from Chandanwari to site of work; i. Cement ii. Iron posts	13	Pony		
9	Supply & fixing of nuts and bolts for MS posts	10	kg		
10	Carriage of sand and bajri by head load from source to site for avg. lead of 5 km.	2.74	cum		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Erection of way side resting shelter sheds at existing places from Chandanwari to M.G. Top (10 spots) with all carriage of material upto installation site before start of Yatra and its dismantling after conclusion of Yatra including repair to damaged shelter sheds complete.

S. No.13

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs.)
I	II	III	IV	VI	VII
1	Erection of sheds at Km 2 and from Pissu-Top to MG TOP 10 spots including carriage of all material from storage site to working site and fixed the sheds at appropriate position etc. complete job	10	Sheds		
2	Dismantling of Shelter Sheds from erected locations including stacking of material at appropriate sites etc. complete job	10	Spots		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Removal of snow before start of Yatra – 2021 Sheshnag & M.G. Top (subject to actual at site).

S. No.14

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r.t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Clearing snow with frosted gulla cutting in compressed snow from working sites manually using picks and shawls etc. complete.	01	cum		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (140 nos.) including cost of its dismantling or after Yatra 2021 at outside Nunwan Base Camp.

S. No.15

Adv. Cost: 1.94 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc with all carriages of material.	140	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m)	210	RM		
	ii. PVC Bends (110mm)	100	No.		
	iii. PVC single equal Tee: (110x110x110mm)	25	No.		
	iv. PVC coupler (110mm)	60	No.		
3	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	30	Cm		
4	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking (complete job).	140	No.		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (120 nos.) including cost of its dismantling during or after Yatra 2021 at Lower Camp, Chandanwari.

S. No.16

Adv. Cost: 1.60 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc with all carriages of material.	120	No.		
2	Supply of P.V C items for disposal of toilets including all carriages. i. PVC pipes (110mmx3m)	150	RM		
	ii. PVC Bends (110mm)	60	No.		
	iii. PVC single equal Tee: (110x110x110mm)	24	No.		
	iv. PVC coupler (110mm)	60	No.		
3	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
4	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking (complete job).	120	No		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (100 nos.) including cost of its dismantling during or after Yatra 2021 at Upper Camp, Chandanwari.

S. No.17

Adv. Cost: 1.42 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc with all carriages of material.	105	No		
2	Supply of P.V C items for disposal of toilets. I. PVC pipes(110mmx3m)	120	RM		
	II. PVC Bends (110mm)	50	No.		
	III. PVC single equal Tee: (110x110x110mm)	60	No.		
	IV. PVC coupler (110mm)	48	No.		
3	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
4	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking (complete job).	105	No.		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (100 nos.) including cost of its dismantling during or after Yatra 2021 in B Block at Sheshnag Camp.

S. No.18

Adv. Cost: 1.46 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc	100	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m) ii. PVC Bends (110mm) iii. PVC single equal Tee:(110x110x110mm) iv. PVC coupler (110mm)	60 60 20 45	RM No. No. No.		
3	Carriage of material from source to site of erection by mechanical transport and head load; i. Mechanical transport ii. Head load (porter)	01 7	Trip Port		
4	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
5	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	100	No.		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (100 nos.) including cost of its dismantling during or after Yatra 2021 in Block A & C at Sheshnag Camp.

S. No.19

Adv. Cost: 1.46 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc	100	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m)	60	RM		
	ii. PVC Bends (110mm)	60	No.		
	iii. PVC single equal Tee:(110x110x110mm)	20	No.		
	iv. PVC coupler (110mm)	45	No.		
3	Carriage of material from source to site of erection by mechanical transport and head load i. Mechanical transport	01	Trip		
	ii. Head load (porter)	7	port		
4	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cum		
5	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	100	No.		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (112 nos.) including cost of its dismantling during or after Yatra 2021 outside at Sheshnag Camp.

S. No.20

Adv. Cost: 1.87 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc	112	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m)	75	RM		
	ii. PVC Bends (110mm)	60	No.		
	iii. PVC single equal Tee:(110x110x110mm)	30	No.		
	iv. PVC coupler (110mm)	45	No.		
3	Carriage of material from source to site of erection by mechanical transport and head load; i. Mechanical transport	01	Trip		
	ii. Head load (porter)	08	porter		
4	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
5	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	112	No.		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (75 nos.) including cost of its dismantling during or after Yatra 2021 enroute from Chandanwari to Km 5.5 including Pissu Top.

S. No.21

Adv. Cost: 1.40 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc.	75	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m)	105	RM		
	ii. PVC Bends (110mm)	75	No.		
	iii. PVC single equal Tee: (110x110x110mm)	20	No.		
	iv. PVC coupler (110mm)	30	No.		
3	Carriage of material from source to site of erection by mechanical transport and head load. i. Mechanical transport	01	Trip		
	ii. Head load (porter)	10	Potter		
4	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
5	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	75	No.		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (75 nos.) including cost of its dismantling during or after Yatra 2021 enroute from Km 5.5 to Naga-koti including Zojibal.

S. No.22

Adv. Cost: 1.42 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc.	75	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m)	105	RM		
	ii. PVC Bends (110mm)	75	No.		
	iii. PVC single equal Tee: (110x110x110mm)	20	No.		
	iv. PVC coupler (110mm)	30	No.		
3	Carriage of material from source to site of erection by mechanical transport and head load; i. Mechanical transport	01	Trip		
	ii. Head load (porter)	10	Potter		
4	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
5	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	75	No.		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling/ erection of prefabricated toilets and baths (60 nos.) including cost of its dismantling during or after Yatra - 2021 enroute from Sheshnag to MG Top.

S. No.23

Adv. Cost: 1.06 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Assembling of Toilet/ Baths at designated site (before commencement of Yatra) including: i. Carriage of Prefabricated panels and other parts from store to site of installation by head load. ii. Minor repairs such as denting, welding and fixing of aldrops and handles etc. iii. Supply of nuts and bolts etc of required size. iv. Fixing of disposal PVC pipe, bends, tee etc	60	No.		
2	Supply of P.V C items for disposal of toilets. i. PVC pipes (110mmx3m)	45	RM		
	ii. PVC Bends (110mm)	50	No.		
	iii. PVC single equal Tee:(110x110x110m)	10	No.		
	iv. PVC coupler (110mm)	25	No.		
3	Carriage of material from source to site of erection by mechanical transport and head lo i. Mechanical transport	01	Trip		
	ii. Head load (porter)	05	Porter		
4	Earth work in excavation by manual means cover areas for foundation, drains, cables cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil with covering of pits complete.	20	Cm		
5	Dismantling of Toilet/ Baths during or after Yatra (on the instruction of site Engineer) including carriage of the same from installation site to SASB store and its proper stacking. (complete job)	60	No.		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Providing and fixing of fitting items to European type toilets from Nunwan to MG Top (100 nos.).

S. No.24

Adv. Cost: 1.50 lakh

S. No	Particulars of Items	Quantity	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Supply, laying and fitting of GI pipes for fixing of internal fittings to European Type toilets 15 mm dia N. Brass with GI Fittings medium	150	Mtr.		
2	Providing and fixing of GI union 15 mm dia in GI pipe including cutting and threading the pipe etc.	60	No..		
3	Fixing of PVC low level flushing cistern with manually controlled device 10 ltr. Capacity white	50	No.		
4	Fixing of PVC solid plastic seat with lid for pedestal type W.C. pan complete.	50	No.		
5	Providing and fixing of PTMT angle stop cock of approved quality 15 mm dia N. brass	100	Nos.		
6	CP brass angle valve	10	No.		
7	CP Brass bib cock	10	No.		
8	Providing and fixing of un-plasticised PVC connection 45 cm long 15 mm dia	100	No.		
9	Providing and fixing of JET for European Type Toilets W. C	60	No.		
10	Providing and fixing of bib cock PTMT bib cock of approved quality	50	No.		
11	Carriage of material for 50 no. toilets from market to site of work (both mechanical and head load)	All material	Trip		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling of (02 no) sheds with attached kitchen and waiting shed for free Medical Camp at Chandanwari Camp.

S. No.25

Adv. Cost: 0.84 lakh

S. No.	Particulars of Items	Qty.	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Providing roofing and sides with CGI Sheets fixed with J or L hooks, bitumen and limpet washers etc. complete. Using available sheets . i. Medical shed. ii. Residential. hall for medical staff Kitchen shed iii. Waiting shed	280.00	Sqm		
2	Fixing of Door/Window at appropriate position Material available at site; i. Blacksmith 1 st class	02	No.		
	ii. Black smith(2 nd class)	02	No.		
	iii. Carpenter	04	No.		
3	Hire charges of welding set with gen- set including welding rods, P.O.L with all carriages.	01	day		
4	Carriage of material from SASB store to works site by M.T. including loading and unloading of material	01	Trip		
5	Dismantling of sheds after conclusion of yatra with all leads, lifts & stacking of material at store.	280.00	sqm		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Assembling of prefabricated administrative huts (04 nos.) with minor repair including dismantling and stacking of material conclusion of Yatra at Sheshnag Camp.

S. No.26

Adv. Cost: 1.60 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the bidder w. r. t. SSR - 2020	Amount (in Rs)
I	II	III	IV	V	VII
1	Repairs the steel structure of prefabricated huts to make it fit for fixing of PUF Panels in MS channels of huts including tightening leveling and fixed up at appropriate position for side walls ,with repair ,fixing of doors. windows etc complete job including all leads and lifts of material from store to erection site fixed required nuts bolts, J & L hooks, bitumen and limpet washers including fabrication where ever required etc. Complete job. for 04 no. huts	2750	Sft		
2	Fixing Roofing with CGI Sheets or PPGI sheets with required nuts and bolts etc complete.for 04 huts.	150	sqm		
2	Providing Wood work for ceiling and partition with available material at site with head load of all material both available and new from source to hut site (budloo/ fir wood). i. Available wood ii. New wood	0.70 0.40	Cum cum		
3	Providing and fixing of three layer particle boards 6mm thick for partition and ceiling of huts and 12mm thick water proofing ply wood not less than 30 kg weight for (8'x4' sheet) for flooring with all carriages of material both mechanical and head load up to working site: i. Available material 6mm thick	325	Sqm		
4	Supply and fixing of PVC Flexible Tarpaulin water resistant for laying upon the roof of huts of size 24ft x18 ft to retain the rain water with all carriages of material up to site,	04	No		
5	Dismantling of huts after conclusion of yatra including stacking of material at appropriate place for 04 no huts.	04	Huts		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Providing and fixing of sanitary fittings to attached baths of administrative and outsourced huts (23 nos.) with minor repairs at Sheshnag Camp.

S. No.27

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Quantity	Unit	Rate to be quoted by the Bidder w.r.t. SSSR 2020	Amount (in Rs)
I	II	III	IV	VI	VII
1	Supply and fixing of Sanitary items for attached baths of prefab huts;				
	Providing and fixing of white vitreous china pedestal type W. C. Pan (European type/ wash down type) water closet pan.	08	No		
	Providing and fixing of white vitreous china pedestal type water closet (European type) with seat and lid. 10 litre low level white vitreous china flushing cistern and CP flush bend with fittings and CI brackets. 40 mm flush bend. Overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete. Including painting of fittings and brackets cutting and making good the walls and floors wherever required	02	No		
3	Providing and fixing of P.V.C low level flushing cistern with manually controlled device (handle lever) conforming to IS:7231, with all fittings and fixtures complete. 10 Ltr capacity white	06	No		
4	Providing and fixing of solid plastic seat cover white.	10	No		
5	Providing and fixing wash basin with C.I/M.S brackets 15mm C.P brass pillar taps,32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required. White vitreous china wash basin size 550x400mm with single 15 mm C.P. brass pillar taps.	03	No		
6	China pedestals for wash basin completely recessed at the back of reception of pipesand fittings	03	No		
7	PVC waste pipes for sink or wash basins 32mm dia	12	No		
8	PTMT waste coupling for wash basins of approved quality and colour.	12	No		
9	Providing and fixing plasticized PVC connection pipe with brass unions. 45cm long , 15mm nominal bore	60	No		
10	Providing and fixing C.P brass angle valve for basin mixer and gyser points of approved make conforming to IS:8931. 15mm NB.	20	No		
11	Providing and fixing of brass bib cock of approved quality. 15mm NB.	24	No		
12	CP Brass pillar cock of approved quality 15 mm dia.NB	10	No		

13	Mirror of superior crystal rectangular shape and size with plastic molded frame of approved quality. 453x357MM	05	No		
14	Providing and fixing of GI pipes 15 mm dia with fittings; i. New pipe (medium) ii. Available pipes	90 100	Rm Rm		
15	Providing and fixing of PTMT towel rails	10	No.		
16	Providing and fixing of spray jett for WC	10	No.		
17	Carriage of material by Mechanical Transport including loading and unloading from Anantnag to Nunwan Camp complete.	01	Trip		
18	Head load of material from Chandanwari to Sheshnag by Ponies and pithos. a. W.c. and fitting items	25	No.		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Covering of SASB area (administrative Block) by way of providing available CGI sheet panels for fencing at Sheshnag Camp.

S. No.28

Adv. Cost: 0.35 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the Bidder w.r.t. SSSR 2020	Amount (in Rs.)
1	Dismantling of CGI sheet used as safety panels to Administrative huts including stacking of material at appropriate position upto 50 meters lead.	157.62	sqm		
2	Fixing of CGI sheets as fencing wall in front of Administrative huts for proper covering with available material for CGI/ PPGI sheets including wooden frame work where ever required nails and washers etc complete work	116.18	sqm		
3	Supply of wooden struts of required size sawn and fixed up in position for frame work of fencing wall. (popular wood)	7.00	cft		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Work of repairs to CCTV Camera cabin shed at Access Control Gate at Chandanwari..

S. No.29

Adv. Cost: 0.25 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the Bidder w.r.t. SSSR 2020	Amount (in Rs.)
1	Providing and fixing specified board medium density exterior (grade 1) to frame backing or studding with screws etc complete frames, backing or studding to be separately using flat. Pressed 3 layer particle board or graded wood parties board. (12 mm ply wood sheets).	29.74	sqm		
2	Providing and fixing of popular wooden struts sawn as frame work for walls repair and ceiling work.	5.56	cft		
3	Carriage of material by mechanical transport from Anantnag to Chandanwari including loading and unloading etc compete.	01	trip		
Total cost of bid (to be quoted both in figures and words)					

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder

SCHEDULE – B (Format for Financial Bid)

(Note: The Bidders are required to invariably quote rates (inclusive of all taxes and statutory levies) in both figures and words failing which their bid is liable to be rejected).

Rate List/ Quantity Schedule

Name of work: Repairs the PVC pipe network of toilets & baths with construction of regular manholes from erected prefab toilets to main sewer line by using heavy grade (B Type PVC pipes) inside Nunwan Camp.

S. No.30

Adv. Cost: 1.00 lakh

S. No.	Particulars of Items	Qty	Unit	Rate to be quoted by the Bidder w.r.t. SSSR 2020	Amount (in Rs.)
1	Earth work in excavations by manual means over areas for foundations, drains cesspits etc. up to the depth of 30cm, including disposal of excavated soil up to normal lead, disposed soil up to 1 mtr. From cutting edge, disposed earth to be leveled and neatly dressed in all kinds of soils	18.90	Cum		
2	Providing and laying of PVC. Pipes of required dia with PVC fittings of approved quality (Grade B) fixed with required rubber rings and sealant for making the pipes water tight. a. PVC pipe (110 mm dia) b. PVC Tee (100mm dia) c. PVC Bend (110mm dia) d. PVC Collar(110mm dia)	210.00 100.00 60.00 50.00	Mtr No No No		
3	Construction of inspection chamber by way of cement concrete in 1:2:4 mix on walls and flooring with required cement concrete cover 50mm thick by using 10mm dia bars @100/100 C/c 1:1.5:3 cement concrete for cover. The inspection chamber should be plastered on both sides with floating coat of neat cement (600x600x600mm) including shuttering and earthwork etc complete job.	05	Nos.		
7	Carriage of all material from source to site	01	Trip		
	Total cost of bid (to be quoted both in figures and words)				

Note: Any topography error found in rate list shall be read as:- the Rates/ Specification as provided in the revised SSR of 2020.

DGM (W) Pahalgam

Signature of the Bidder