

Shri Amarnathji Shrine Board



Jammu and Kashmir

**Tender Document
For
Civil Works along Baltal axis
For
Yatra – 2021**

Sd/-
General Manager (Works)
Shri Amaranthji Shrine Board

16.03.2021

CIVIL WORKS ALONG BALTAL AXIS FOR YATRA 2021

DETAILED NOTICE INVITING TENDER (DNIT)

(issued under no. SASB/Works/W/20211283//26 dated 17.03.2021)

S. No.	CONTENT	PAGE(S)
1.	Notice Inviting Tender (NIT) for advertisement	3-4
2.	Eligibility Criteria	5
3.	Documents establishing Bidder's eligibility	5
4.	Instructions to Bidders	6-8
5.	Terms and Conditions of Contract	8-11
6.	Schedule – A (Technical Bid)	12-13
7.	Bid Securing Declaration (Format)	14
7.	Schedule – B (Financial Bid)	15-38



SHRI AMARNATHJI SHRINE BOARD

Chaitanya Ashram, Talab Tillo, Jammu (Nov - April)

Tele: 0191-2555662, Telefax: 0191-2503399

NOTICE INVITING TENDER CIVIL WORKS ALONG BALTAL AXIS FOR YATRA - 2021

For and on behalf of Chairman, Shri Amarnathji Shrine Board, sealed tenders in two-bid format, affixed with Rs.6/- revenue stamps, are invited from registered **JK PWD, CPWD Contractors** having a valid registration, for the execution of Civil Works as mentioned below. The bids shall be received in the office of General Manager (Works), Shri Amarnathji Shrine Board, at Chaitanya Ashram, Talab Tillo, Jammu, on or before **06.04.2021** upto **1400 hours**.

S. No.	Name of work	Estimated cost (Rs in lakh)	Cost of bid document (in Rs)	Earnest Money/ Bid Security (in Rs)	Class of Contractor	Time of Completion
1	Renovation of washroom of Meeting Hall, Installation of 5000 litres capacity water tank and providing and fixing of water supply pipelines and construction of drain at Neelgrath for Yatra 2021.	1.82	200/-	Bid Security Declaration to be made by the Bidder on non judicial stamp paper duly attested by Notary as per prescribed format.	DEE	15 days
2	Extension of roofing over entrance doors of 04 No. Camp Director Huts and laying of flooring in one no. Hut at Baltal.	1.41	300/-		DEE	15 days
3	Construction of Sub-structure of Pravachan Hall (Pandal) at Baltal Base Camp for Yatra 2021.	4.30	400/-		DEE	15 days
4	Construction of 01 No. Additional room of size 12'x11' with attached washroom of size 6'x4'6" for Camp Director at Lower Holy Cave.	2.28	300/-		DEE	10 days
5	Assembling/erection of Camp Director Hut and kitchen shed before Yatra including dismantling and safe stacking of same and construction of Pucca sub-structure after conclusion of Yatra 2021 at Sangam.	2.30	300/-		DEE	15 days
6	Carriage, assembling of CGI sheet Sheds (Shoe Rack Shed of Size 30'x20'), Frisking Shed of Size 8'x8', Cloak Room of Size 20'x10', SASB Kitchen, SASB Store, SASB Staff Shed, BSNL Shed, Labour Shed, Information Booth, DD Shed) including dismantling after conclusion of Yatra-2021 at Holy Cave.	2.00	200/-		DEE	10 days

2. Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu from **9.30 AM to 5.00 PM**, on any working day from **17.03.2021 to 05.04.2021** on payment of cost of document in cash or in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB), Jammu or can be downloaded from SASB website (www.shriamarnathjishrine.com)
3. The Bids, duly completed, along with **Bid Security Declaration**, must reach the office of General Manager (Works) latest by **06.04.2021 upto 1400 Hrs.** The Bidders, in their own interest, are advised to deliver the bids personally in the office of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu. Alternatively, they may send the same through Speed Post/ Registered Post. The Board will not be responsible for any delay, wrong delivery or non-delivery of the bids due to any reasons.
4. The Technical bid shall be opened on **06.04.2021 at 1500 Hrs** in the Office of General Manager (Works) at Jammu Office (address mentioned above) in presence of the Bidders who may wish to be present on the occasion.
5. Not more than three bid documents shall be issued to a single Bidder.
6. In case the last date of receipt of bids happens to be a holiday, the bids shall be received on the next working day up to **1400 hours**.
7. The successful Bidder is bound to enter into an agreement with General Manager (Works), SASB, **within ten days** from the date of the receipt of Letter of Intent (LoI).
8. All addenda, corrigenda, dedenda and amendment shall be uploaded on website only and not in print media and the Bidders are advised to keep themselves updated on this account.

No: SASB/NIT/W/2021/1283/26

Dated: 17.03.2021

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

2. ELIGIBILITY CRITERIA

2.1 The Bidder must be a Contractor registered with J&K, PWD, CPWD and must fulfil all the following eligibility requirements concurrently to technically qualify for bidding process:

2.2 Average Annual Turnover during the last three years, ending 31st March of the previous financial year (i.e. 2017-18, 2018-19, 2019-20) should be 30% of the advertised cost.

2.3 The bidder should have an experience of having successfully completed similar works in Hilly Regions during the past seven years ending last day of month previous to the one in which applications are invited should be either of the following:-

a. Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

Or

b. Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

Or

c. One similar completed work costing not less than the amount equal to 80% of the estimated cost.

2.4 The Bidder should not have been blacklisted on an earlier occasion by any of the Union Territory Government Organizations, U.T Autonomous Bodies or Local Bodies/ Municipalities.

3. DOCUMENTS ESTABLISHING BIDDER'S ELIGIBILITY

The Bidder must submit the following documents:

3.1 Registration Certificate.

3.2 Certified copies of Annual Turnover from Bank

3.3 Certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works, for fulfilling the eligibility criteria.

3.4 Certified copy of PAN Card.

3.5 Certified copy of GSTIN.

3.6 General Profile of the Bidder

3.7 Bid Security Declaration.

3.8 An affidavit by the Bidder, Stamp Paper of Rs. 10, stating that all information furnished in the bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against him. If any information is found to be incorrect during technical evaluation or during execution of work, the following penalties are to be imposed;

3.8. i. in case the work is allotted to the agency, the contract shall be terminated and work executed through an alternate agency at the risk & cost of the allottee,

3.8. ii. Earnest Money Deposit, shall be forfeited

3.8. iii. the Bidder/ Allottee shall be debarred from tendering in SASB for next three years.

4. **INSTRUCTIONS TO BIDDERS:**

- 4.1 Detailed NIT (DNIT) can be obtained from the office of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu, from **9.30 AM to 5.00 PM** on any working day from **17.03.2021 to 05.04.2021** on payment of cost of Tender Document prescribed against each work in the DNIT in the shape of Demand Draft drawn in favour of FA/ Chief Accounts Officer, Shri Amarnathji Shrine Board (SASB). Alternatively it can be downloaded from SASB website . (www.shriamarnathjishrine.com)
- 4.2 The Bidders are required to submit the bid in two parts – **Technical** and **Financial** – strictly as per format given in **Schedule A** and **Schedule B** of the DNIT along with requisite supporting documents. The two parts of the **Bid** should be submitted in two separately sealed envelopes superscribed “**Technical Bid for the work of _____ Yatra 2021**” and “**Financial Bid for the work of _____ Yatra 2021**”. Both the sealed envelopes should be put in a third envelop, sealed and superscribed “**Tender for the work of _____ (Yatra 2021)**” **mentioning NIT No. & date**. The bids, as are not submitted as per format prescribed in **Schedule A and B**, are liable to be rejected.
- 4.3 The bids, duly completed, along with **Bid Security Declaration** must be dropped in the Tender Box kept in the office chamber of General Manager (Works), Shri Amarnathji Shrine Board, Chaitanya Ashram, Talab Tillo, Jammu or sent by Registered/ Speed Post to General Manager (Works), SASB at the aforesaid address, so as to reach latest on **06.04.2021 upto 1400 hours**. Bids received after the aforesaid date and time will not be considered. The Shrine Board shall not be responsible for any delay/ loss of documents or correspondence sent by speed post.
- 4.4 The cost of DNIT should be placed inside the envelope containing the Technical bid and Bid Security Declaration.
- 4.5 It would be deemed that by submitting the bid, the Bidder has made complete examination of the DNIT, received all information from SASB and made complete examination of the various aspects required for undertaking the stated works.
- 4.6 Each Bidder can submit only one bid in response to a work in the DNIT. Any bidder who submits more than one bid shall be disqualified.
- 4.7 The bidder is expected to examine all Instructions, Schedules, Formats, Terms and Conditions, Scope of Work mentioned in the DNIT. Failure to furnish all information required in the Tender Document or submission of bid not substantially responsive to the DNIT in every respect will be at Bidder's risk and may result in the rejection of the bid.
- 4.8 All entries in the Technical/ Financial Bids should be legible and should be free from corrections/ erasures/ overwriting/ cuttings. Bids with corrections/ erasures/ overwriting/ cuttings shall be out rightly rejected. Amounts shall be

indicated in words as well as in figures. In case of any variation between amount in figures and words, amount quoted in words shall be taken as authentic.

- 4.9 The rate quoted by the Contractor in item rate tenders shall be on correct basis and not the amount worked out by them. The rate quoted in words will be correct basis and not the rate shown in figures in case of discrepancy between them.
- 4.10 Each paper of the bid document shall be completed in all respects, page numbered, and duly signed in long hand, executed in ink and stamped at the bottom right hand corner by an authorized/ empowered representative of the Bidder. The Bidder must also sign and stamp all pages of DNIT as acceptance of all conditions contained therein and for the purpose of identification. Financial Bid received in the format other than specified in **Schedule B** (Financial Bid) is liable to be rejected.
- 4.11 Bids must be received at the address specified in this document not later than the date and time stipulated in the DNIT. The General Manager (Works) may, at his discretion, extend the deadline for submission of bids. Any bid received after due date and time for submission of bids, as stipulated above, shall not be considered and will be returned.
- 4.12 Clarifications, if any, may be sought by the Bidders prior to so as to reach General Manager (Works) at least seven days before last date prescribed for submission of bids. Except for any written clarification by General Manager (Works), SASB which is expressly stated to be an addendum to the DNIT, no written or oral communication, presentation or explanation by any other employee of the SASB shall be taken to bind or fetter the Shrine Board under the Contract. All corrigenda, addenda, amendments and clarifications to the DNIT will be hoisted on SASB website (www.shriamarnathijshrine.com) and NOT in newspaper(s). The Bidders should keep themselves updated on this account.
- 4.13 The Technical Bid shall be opened on **06.04.2021 at 1500 Hrs** in the Office Chamber of General Manager (works) in presence of the authorized representatives of the Bidders who may wish to be present at that time. Bidders whose Technical Bids have been accepted shall be informed about the date and time for opening of the Financial Bids.
- 4.14 The General Manager (Works), SASB is not bound to accept the lowest or any bid and may, at any time by notice in writing to the Bidders, terminate the tender proceedings without assigning any reason whatsoever.
- 4.15 The bid shall remain valid and open for acceptance for a period (i.e. Bid Validity Period) of **60 days from the last date prescribed for its receipt.**
- 4.16 To facilitate evaluation of Bids, the General Manager (Works) may, at his sole discretion, seek clarification in writing from any bidder regarding the bid. The request for such clarification or substantiation and the response shall be in writing or by facsimile or email. No material change in the substance of the bid would be permitted by way of such clarification/ substantiation.

- 4.17 The General Manager (Works) may award the Contract to the Bidder whose bid has been evaluated to be responsive and who is eligible and qualified to perform the contract satisfactorily as per the Terms and Conditions incorporated in the DNIT. The General Manager (Works), SASB will send to such eligible Bidder a letter, hereinafter referred to as the 'Letter of Intent' (LoI) prescribing the amount which the Shrine Board will pay to the eligible Bidder in consideration of work/ services to be executed by the eligible Bidder as prescribed in the Contract.
- 4.18 The eligible Bidder will have to enter into an agreement with the Shrine Board, as per the Terms and Conditions mentioned in the DNIT or such other Terms that may be prescribed, within the **ten days** of the receipt of Letter of Intent.
- 4.19 General Manager (Works), SASB reserves the right to reject all or any bid in whole, or in part, without assigning any reasons thereof. Any enquiry after the submission of tender will not be entertained.
- 4.20 Shri Amarnathji Shrine Board shall not be responsible for release of any DD/ CDR pledged to FA/ Chief Accounts Officer, SASB without submitting his tender in the tender box. However, the DDs/ CDRs of unsuccessful Bidders/ eligible bidders who have paid the prescribed tender document fee shall be released only after issuance of Letter of Award (LoA) in favour of the successful bidder.

5. **TERMS AND CONDITIONS OF THE CONTRACT:**

- 5.1 The Bidders are required to quote rate above/ below percentage on SSR of 2020 shown in the rate list of Schedule-B, (Format of Financial Bid) against each item of work. All rates/ percentages should be quoted in figures and words. The Bidders must also calculate and mention total cost of his bid in last row of the table of Schedule B, in both figures and words.
- 5.2 Bids shall have to be submitted separately for each work as indicated in the NIT.
- 5.3 The successful bidder shall have to start and complete the work on the allotted rates, within the stipulated time, failing which following penalties shall be imposed:
- | | | |
|-----------|---|--|
| 5.3 (i) | First 3 days of delay | Penalty @1% of contract value. |
| 5.3 (ii) | 4 th day upto 10 th day | @2% of contract value |
| 5.3 (iii) | Beyond 10 days | Earnest Money Deposit shall be forfeited and the contract automatically stands cancelled. The General Manager (Works), SASB shall be at liberty to get the work done through another suitable agency at the risk & cost of the contractor without issuing any notice to the Contractor / Firm. |

- 5.4 Not with standing **Clause 5.3 above**, in case progress of work is found to be slow, the Engineer In-charge shall be free to supplement the engagement of labour skilled/ unskilled or by engaging another agency in the interest of speedy execution of work.
- 5.5 The quantum of work can be increased or decreased as per the requirements and site conditions. The payment of extra work involved, if any, shall be paid as per SSR rates mentioned in the Allotment of Contract along with percentage increase/ decrease allowed on the rates allotted for each item of work in Letter of Award (LoA).
- 5.6 The Contractor shall start the work only after taking demarcation (nishandehi) from the site Engineer concerned and shall execute the work strictly as per PWD/ CPWD Book of specifications.
- 5.7 The date of start of work shall be reckoned by the site Engineer In-charge, keeping in view the feasibility of commencement of work at site.
- 5.8 The Contractor shall submit **pictorial evidence (Photographs)** of execution of work (pre execution, during execution and after completion of work) with his claim.
- 5.9 The Contractor shall be bound by the Rules and Regulations with regard to issue and purchase of Stores, Stock and other materials etc. and also the tender conditions incorporated in the tender document for the said work. The Contractor shall be responsible for arrangement of all the items required for completion of the work in time, like Electricity, Water, Manpower, Tools and Equipment etc.
- 5.10 The Contractor shall stand guarantee for the workman-ship in respect of the material used in the construction and if any material used is found defective in quality, the Contractor shall have to get it replaced on spot, free of charge, and the cost of dismantling the defective construction and its re-construction shall be responsibility of the Contractor.
- 5.11 The Contractor shall abide at all times by all the applicable labour enactments and rules made there under, regulations, notifications and bye laws of the U.T or Central Government or Local Authority and any other labour laws (including rules), regulations, bylaws that may be passed or notifications that may be issued under any labour law in future either by the U.T. or the Central Government or the local authority. The Contractor shall be solely responsible for failure, if any, for liabilities, adherence to the labour, laws, local laws and other related rules/regulations.
- 5.12 All risks of loss or damage to physical property and of personal injury and death which may arise during and in consequence of the performance of the contract shall be the sole responsibility of the Contractor.
- 5.13 The Contractor shall provide Insurance Cover from date of start to date of completion of work to the Labour/ Employees, employed by him for execution of work against any personal injury or death.

- 5.14 The agency shall be solely responsible for **Workmen's Compensation Act**, 1923 for payment of **compensation** to **workmen** and their dependants in case of injury and accident (including certain occupational disease) arising out of and in the course of employment and resulting in disablement or death.
- 5.15 The employees hired/ employed for the execution of work of the Contractor shall in no case whatsoever, be treated as the employees of SASB.
- 5.16 **Child Labour:** No child labour shall be engaged, the employment of child labour is strictly prohibited in any construction works and Contractor shall abide by the Labour Law in Force.
- 5.17 The Contractor is bound to draw an agreement with General Manager (Works), SASB within fifteen days from the date of receipt of **Letter of Intent** (LoI).
- 5.18 General Manager (Works), SASB shall be at liberty to suspend the agreement due to any Force Majeure conditions such as Government regulations, court orders, wars, accidents creating disturbed conditions, terrorist activity, strikes/riots, civil commotion etc.
- 5.19 All disputes and differences between the parties arising out and relating to the agreement to be signed between the General Manager (Works) SASB and the firm, including the interpretation of its Terms and Conditions shall be referable to the Sole Arbitrator to be nominated by the Chief Executive Officer, Shri Amarnathji Shrine Board whose decision shall be final and binding upon all the parties.
- 5.20 All questions relating to arbitration shall be determined in accordance with the provisions of J&K Conciliation and Arbitration Act, 1997 and, Courts in the Union Territory of Jammu & Kashmir alone shall have the Jurisdiction to deal with such questions.
- 5.21 The rates quoted by the Contractor shall be inclusive of all taxes including GST etc as are applicable.
- 5.22 If during the period of one year from the date of completion of work, the defects which have been caused by bad workmanship, use of inferior materials on the work, the Contractor shall be liable to remove the defects or make repairs at his own cost and expenses within a period of three days of the receipt of notice from the Deputy General Manager, Shri Amarnathji Shrine Board to that effect and in the event of his failure to remove these defects within the stipulated period, the work shall be got rectified through alternate resourceful agency and the cost thereof shall be recovered from the dues of the Contractor.
- 5.23 The Earnest Money Deposit of the successful Bidder shall be released after completion of work in full and issue of completion certificate by the DGM, SASB.

VI Payment Clause:

- 6.1 Payment shall be made to the Contractor for complete item of work including cost of material and labour (finished work) after recording the measurement in the **Works Register** by the Junior Engineer In-charge site duly checked by the Deputy General Manager Works.
- 6.2 The payment to the Bidder shall be made after successful completion of work within the stipulated time as per specifications and Terms & Conditions of agreement after satisfactory use/ function of the work during complete Yatra Period.
- 6.3 Any extra item (s) executed at site of work shall be paid strictly as per LoA (Contractor's appreciation/ depreciation on J&K **Sanctioned Schedule of Rates 2020.**)

VII Time of completion:

- 7.1 The time of completion of works stands mentioned against each work in the NIT.
- 7.2 Time of completion shall mean;
Period of time of completion of work in all respects before start of Yatra – 2021 including the period of time involved in completely dismantling of the pre-fabricated structures with due care from damages and safe storage of the materials in the SASB stores to the entire satisfaction of the Deputy General Manager (Works) or his authorised representative.

Sd/-
General Manager (Works)
Shri Amarnathji Shrine Board

SCHEDULE A (TECHNICAL BID)

PART A: DETAILS OF COST OF DNIT AND BID SECURITY DECLARATION

S. No.	Particular of item	Details
1	Amount and details of payment towards the cost of DNIT:	Rs. (in words):
		Receipt No./ Cheque No:
		Date:
2	Bid Securing Declaration	Dated:
		Bid No.
		Name of Notary

PART – B: BASIC DETAILS ABOUT THE AGENCY.

i) Name and address of :
the Agency.

Name: _____

Address: _____

Phone: _____

E-mail: _____

PART- C: DOCUMENTS ESTABLISHING BIDDERS ELIGIBILITY.

The Bidder is required to furnish the following information/ documents:
(Please attach separate sheets where necessary):

1. Registration No./ Other documents of the Agency (attach a certified copy of Registration Certificate/ other documents; *please see DNIT – Para 3.1 of ‘Documents Establishing Bidder’s Eligibility’*)
2. The Bidder must furnish certified copies of bank statement - *please see DNIT – Para 3.2 of ‘Documents Establishing Bidder’s Eligibility’*

#	Financial Year	Turnover (Rs.)
1	2017-18	
2	2018-19	
3	2019-20	

3. Documents to show that the contractor possesses relevant experience in past three years. The bidder must furnish certified documents like Letter of Award/ Work Order, Certificate of Completion etc. indicating experience and successful execution of similar works for fulfilling the eligibility criteria and also furnish information in following format (please add rows as necessary for other sectors, if applicable) - *Para 3.3 of Documents Establishing Bidder’s Eligibility*

S. No.	Name of work	Name of Client	Value of Completed work (in Rs.)	Date of commencement	Date of completion	Whether supporting documents (attested) enclosed (Yes/ No)

4. Certified copy of PAN Card - *Para 3.4 of ‘Documents Establishing Bidder’s Eligibility’*
5. Certified copy of GSTIN – *Para 3.5 of ‘Documents Establishing Bidder’s Eligibility’*
6. General Profile of the Bidder – *Para 3.6 of ‘Documents Establishing Bidder’s Eligibility’*
7. Bid Security Declaration – *para 3.7 of Documents Establishing Bidder’s Eligibility’*
8. Affidavit on Rs. 10/- Stamp paper stating that every information furnished in the Bid is correct and to the best of his knowledge and that no criminal/ income tax/ blacklisting case is pending against the bidder Agency. Please attach the affidavit - *Para 3.7 of Documents Establishing Bidder’s Eligibility.*

Form of Bid Security Declaration

(Duly notarized)

The General Manager (Works),

_____ ,

_____ .

NIT No. & Date: _____

Name of work. _____

1. I _____ s/o _____
r/o _____ declared that;

I understand that, according to your conditions, bids must be supported by a Bid Securing Declaration.

2. I accept that I may be disqualified from any Contract with the Shri Amarnathji Shrine Board for a period of three years from the date of notification if am in a breach of any obligations (s) under the bid conditions, because I;
- a). have withdrawn/ modified/amended, impaired or derogated from the tender, my bid during the period of bid validity specified in the Letter of Bid, or
 - b). having been notified of the acceptance of my Bid by the SASB during the period of bid validity of (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with Instructions to Bidders.
3. I understand this Bid- Securing Declaration shall cease/ expire to be valid if undersigned is not the successful Bidder, upon the earlier of (i) the receipt of your notification of the name of the successful Bidder; or (ii) sixty days Bid Validity Period.

Signature of person

(Signing the Bid Securing Declaration)

Dated on _____ day of _____

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Renovation of washroom of Meeting Hall, Installation of 5000 litres capacity water tank and providing and fixing of water supply pipelines and construction of drain at Neelgrath for Yatra 2021.

S.No: 01

Adv. Amount: Rs 1.82 lakh

S. No	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot and cold water supply, including all CPVC plain and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-charge.				
1.1	40mm nominal outer dia pipes.	110	Meter		
1.2	25mm nominal outer dia pipes	30	Meter		
1.3	15mm nominal outer dia pipes.	40	Meter		
2	Making connection from PVC tank with GI fittings including supply of all items required.	03	Nos.		
3	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required. 15 mm nominal bore	10	Nos.		

S. No	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
4	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with epoxy coated aluminium rod with L.P/H.P.H.D plastic balls. 40mm nominal bore, 206mm long, weighing not less than 690 gms	03	Nos.		
5	Earth work in excavation by manual means over areas for foundation, drains, cables, cesspits etc. including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be leveled and neatly dressed in all kinds of soil.	0.72	Cum		
6	Providing and laying in position cement concrete of specified grade including curing excluding cost of centring and shuttering all works up to plinth level. 1:4:8(1 cement :4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	2.39	Cum		
7	Providing and laying in position cement concrete of specified grade including curing but excluding cost of centring and shuttering all works up to plinth level.1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	3.337	Cum		
8	Centring and shuttering including strutting, propping etc. removal of frame work for Foundations, footings, bases for columns	12.26	Sqm		

S. No	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating Each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1.08	Cum		
10	Dumping of stones including cost of stones in horizontal on level by ramming the layers properly.	0.54	Cum		
11	Providing and laying damp-proof Course 50 mm thick with cement concrete 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate 20 mm nominal size) and curing complete	46.447	Sqm		
12	Making connection of G.I. distribution branch with G.I. main of following sizes by providing & fixing Tee, including cutting and threading the pipe etc. complete (25 to 40 mm nominal bore).	03	Nos.		
13	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete 20 mm nominal bore	04	Nos.		

S. No	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
14	<p>Labour for dismantling of door and washroom of Meeting Hall and its fixing at appropriate place and fixing PUF panels with washing etc complete job and installation of 5000 liters capacity PVC water tank including dismantling of existing connections/pipes etc complete.</p> <p>a) Blacksmith 2nd class b) Plumber/Asst fitter c) Mazdoor</p>	<p>01 01 02</p>	<p>Day Day Day</p>		
15	<p>Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per Sqm including pointing in white cement mixed with pigment of matching shade complete.</p>	8.36	Sqm		
16	<p>15mm Cement plaster on the rough side of single or half brick wall of mix 1 : 4 (1 cement : 4 coarse sand)</p>	18.60	Sqm		
17	<p>Dismantling of old sanitary fittings, plumbing items by engagement of skilled workers.</p> <p>2nd Class fitter</p>	01	No		

S. No	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
18	Providing and fixing CPVC pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.: Internal work-Exposed on wall 15 mm dia. nominal bore	15.00	Meter		
19	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (new work) 15 mm nominal bore	01	No.		
20	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size),inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total	01	No.		

	weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : 20.7.1.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5				
21	Carriage of cement by Mechanical Transport from Ganderbal to Neelgrath for an avg. lead 60 km	2.11	Tonne		
22	Carriage of sand, stones & stone aggregate by MT for site of source to site of work for an average lead of 33 Km.	11.795	Cum		
23	Fixing and fitting of Chinaware i.e EWC, flushing cistern, washbasin, Towel Rod, Looking mirror, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including testing and cost/Hire Charges of tools and plants required for completion of job. Washroom:	01	No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Extension of roofing over entrance doors of 04 No. Camp Directors Huts and laying of flooring in one no. Hut at Baltal.

S.No: 02

Adv. Amount: Rs. 1.41 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge: 1:3:6 or richer mix	1.44	Cum		
2	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	579.72	Kg		
3	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm+/-5% total coated thickness (TCT), Zinc coating 120 gsm as per IS:277 in 240 mpa stee grade 5-7 microns epoxy primer on both sides of the sheet and polyster top coat 15-18 microns. Sheet should have protective guard	15.6	Sqm		

	film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer –in-charge. The sheet shall be fixed using self drilling/ self tapping screws of size (5.5 x 55 mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work upto plinth level 1:4:8 (1 cement: 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	0.24	Cum		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work upto plinth level 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	0.48	Cum		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work upto plinth level 1:3:6 (1 cement: 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	4.16	Cum		
7	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	15.6	Sqm		
8	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns.	6.36	Sqm		
9	Labour for opening of the structure for proper joining of the frame structure i.e opening of bird cover and purlins etc and fixing of the same.				
9.1	Blacksmith	02	Day		
9.2	Helper / Mazdoor	02	Day		
9.3	Hire charges of Genset,Welding set,Electrodes and POL.	01	Day		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
10	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete.	16.00	Sqm		
10.1	40mm thick with 20 mm nominal size stone aggregate.				
11	Providing and fixing glass strips in joints of terrazzo/ cement concrete floors.	24.00	Meter		
11.1	40 mm wide and 4 mm thick				
12	Carriage of material by mechanical transport sand and bajri 73 km lead	2.404	Tonne		
13	Carriage of sand and bajri by MT for an avg lead of 43 kms.	8.50	Cum		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of substructure of Parvachan Hall (Pandal) at Baltal Camp for Yatra 2021.

S.No: 03

Adv. Amount: Rs. 4.30 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
1	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil :	198.00	Cum		
2	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deported in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m. In All kind of soil	68	No		
3	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth in all kinds of soil	7.25	Cum		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	2.42	cum		
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	8.06	cum		
6	Centering and shuttering including strutting, propping etc. and removal of form work for: a) Foundations, footings, bases of columns etc. for mass concrete.	32.24	Sqm		
7	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete all as per direction of Engineer-in-	375.00	Sqm		

	Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern				
8	Carriage of sand and bajri by Mechanical Transport for a lead of 43 kms.	33.00	Cum		
9	Carriage of cement & paver blocks by Mechanical Transport for a lead of 70 kms.	49.45	Tonne		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Construction of 01 No. Additional room of size 12'x11' with attached washroom of size 6'x4'6" for Camp Director at Lower Holy Cave.

S.No: 04

Adv. Amount: Rs. 2.28 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
1	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	3.46	Cum		
2	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	2.09	Cum		
3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	4.12	Cum		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
4	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	26.21	Sqm		
5	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20mm nominal size stone aggregate.	16.08	Sqm		
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	2.77	Cum		
7	Providing and fixing strips in joints of terrazzo/ cement concrete floors. Glass strips-40 mm wide and 4 mm thick	14.63	Meter		
8	Fixing and fitting of Chinaware i.e EWC, flushing cistern, water supply pipes, sewer pipes, CP fittings and all other fixtures/fittings required for making washroom functional including cost and carriage of G.I fittings, testing and hire charges of Tools and plants required for the completion of job. a) Washroom	01	No.		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
9	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position : Budloo / Fir wood	0.58	Cum		
10	Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	68.07	Sqm		
11	Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7	3.66	Rm		

	microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
12	Fixing of doors and windows with carriage by head load from store to site of erection (only labour rate) a) Doors b) Windows c) Ventilator	02 01 01	No. No. No.		
13	Carriage of materials by MT from Ganderbal to Dumail for an avg lead of 73 kms	2.00	Tonne		
14	Carriage by Head Load for: a) Sand and stone aggregate(5Kmlead) b) Metal (0.50 Km) c) Cement and all other items (12 Km) (i) Ponies:	7.33 1.86 24	Cum Cum No.		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)**Rate List/ Quantity Schedule**

Name of the work: Assembling/erection of Camp Director Hut and kitchen shed before Yatra including dismantling and safe stacking of same and construction of Pucca sub-structure after conclusion of Yatra 2021 at Sangam.

S. No. 05**Adv. Amount : Rs 2.30 lakh**

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs)	Amount (in Rs)
I	II	III	IV	V	VI
	<u>PRE-YATRA</u>				
1	Repair/ erection of the wooden frame structure ,walling and ceiling / roofing of the hut including supply of the missing members etc and Fixing of wooden work in frames of false ceiling, walls (sawn and fixed in position) carriage from dumping site to site of erection/work.	01	No.		
2	Fixing of hyrib (0.5mm thick) PPGI sheet/CGI sheet side walls with self driven screws excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required (including overlaps) and fixing of doors and windows including carriage upto site of erection. (labour rate only)	56.10	Sqm		
3	Fixing of 6 mm thick teak ply as approved by engineer incharge and fixing of doors and windows including carriage from dumping site to site of erection.	23.79	Sqm		
4	Providing and fixing of wooden beading on ply wood joints (40x6 mm) flat on vertical joints and angle type on corners including carriage upto Sangam Camp	25.00	Meter		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs)	Amount (in Rs)
I	II	III	IV	V	VI
5	Fixing of all sanitary fittings and electrification of hut and washroom including supply of PVC connection, PTMT fittings and GI fittings including cost and carriage of sanitary items from Baltal store to site of installation before Yatra including dismantling of the same after Yatra. Washrooms:	02	No.		
	<u>POST-YATRA</u>				
6	Dismantling of Prefabricated hut and all other fittings including stacking of the same as per the instructions of engineer –in-charge (Complete job)	01	No		
7	Earth work in excavation by manual means in trenches for foundation, drains, pipes, cables etc. (Not exceeding 1.5mtr in width) and for shafts, wells, cesspits and the like not exceeding 10Sqm on plan, depth upto 1.5mtr including disposal of excavated earth upto 1mtr from cutting edge, disposed earth is to be levelled and neatly dressed in all kinds of soil.	6.79	Cum		
8	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	5.88	Cum		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs)	Amount (in Rs)
I	II	III	IV	V	VI
9	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	8.48	Cum		
10	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.736	Cum		
11	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	53.00	Sqm		
12	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20mm nominal size stone aggregate.	42.10	Sqm		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs)	Amount (in Rs)
I	II	III	IV	V	VI
13	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	5.43	Cum		
14	Providing and fixing glass strips in joints of terrazzo/ cement concrete floors. Glass strips- 40 mm wide and 4 mm thick	53.03	Meter		
15	Carriage of materials by MT From Ganderbal to Dumail for an avg lead of 73 km	3.8	Tonne		
16	Carriage by Head Load for: 17.1 Sand and stone aggregate for an avg lead of 500 metres. 17.2 Cement and all other items from Dumail to Sangam 17.2.1 Ponies 17.2.2 Porters	22.68 38 01	Cum No No		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder

SCHEDULE – B (Format for Financial Bid)

Rate List/ Quantity Schedule

Name of Work: Carriage, assembling of CGI sheet Sheds (Shoe Rack Shed of Size 30'x20'), Frisking Shed of Size 8'x8', Cloak Room of Size 20'x10', SASB Kitchen, SASB Store, SASB Staff Shed, BSNL Shed, Labour Shed, Information Booth, DD Shed) including dismantling after conclusion of Yatra-2021 at Holy Cave.

S.No: 06

Adv. Amount: Rs. 2.00 lakh

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
1	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m. in All kind of soil.	33	No.		
2	Fixing wood work in frames of false ceiling, partitions etc. sawn and fixed in position :Budloo/Fir Wood	3.271	Cum		
3	Fixing corrugated G.S sheet roofing including vertical curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I Limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost	518.74	Sqm		

	of purlins, rafters and trusses and including cutting to size and shape where ever required including carriage of materials by Head Load to erection site before Yatra and back to store after conclusion of Yatra etc complete (Labour only)				
4	Erection of frame structure of BSNL and labour shed using steel members, steel pipes and wooden struts etc and carriage of material from SASB store to site of erection of sheds before commencement of Yatra and safe storage in SASB store after conclusion of Yatra. Sheds:	02	No.		
5	Dismantling wood work in frames, trusses, purlins and rafters upto 10 m span and 5 meter height including stacking material within 50 meter lead a) Of sectional area below 40 sqcm. b) Of sectional area 40 sqcm and above.	199.92 1.751	Meter Cum		
6	Supply of wood work for frame of shed. Budloo/Firwood Scantling:	0.50	Cum		
7	Fixing teak wood/hard board for ceiling, partition door and window etc and wall lining of Huts etc complete fixed with required nails and washers etc.(Labour only)	21.56	Sqm		
8	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 meters lead of : G.S. Sheet	518.74	Sqm		

S. No.	Particulars of Items	Approx. Quantity	Unit	Rate to be quoted by the Bidder (in Rs.)	Amount (in Rs.)
I	II	III	IV	V	VI
9	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 meters lead : Thickness above 10 mm upto 25 mm	21.56	Sqm		
Total cost of bid (to be quoted both in figures and words)					

Any typographical error found in Rate list must be read as per Item of J&K Schedule of Rates 2020.

Junior Engineer

DGM

Signature of Bidder